

GENERAL

1. ALL ACTIVITIES, WORKMANSHIP AND MATERIALS ARE TO BE IN ACCORDANCE WITH THE RELEVANT PROVISIONS OF THE QUEENSLAND BUILDING ACT, THE RELEVANT PROVISIONS OF THE NATIONAL CONSTRUCTION CODE, THE RELEVANT PROVISIONS OF THE RELEVANT AUSTRALIAN STANDARDS, THE RELEVANT PROVISIONS OF THE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINES, THESE CIVIL ENGINEERING DRAWINGS AND THE PROJECT SPECIFICATIONS.
2. THE CONTRACTOR IS TO COMPLY WITH THE REQUIREMENTS OF THE LOCAL AUTHORITY AND THE BUILDING CERTIFIER. ENSURE ALL PERMITS ARE IN PLACE BEFORE CONSTRUCTION.
3. ALL CONTRACTORS AND SUB-CONTRACTORS ARE TO HOLD APPROPRIATE REGISTRATION AND LICENCES.
4. PERFORM ALL ACTIVITIES IN A SAFE AND RESPONSIBLE MANNER AND IN ACCORDANCE WITH THE RELEVANT PROVISIONS OF THE QUEENSLAND WORK, HEALTH AND SAFETY ACT, QUEENSLAND WORK HEALTH AND SAFETY REGULATION, CODES OF PRACTICE AND INDUSTRY ACCEPTED CONSTRUCTION PRACTICE AND PRINCIPLES.
5. DURING THE CIVIL ENGINEERING DESIGN PROCESS FOR THIS PROJECT THE SAFETY OF THE PEOPLE WHO WILL CONSTRUCT, USE, MAINTAIN AND DEMOLISH THE CIVIL ELEMENTS HAVE BEEN CONSIDERED. RISKS TO THESE PEOPLE HAVE BEEN IDENTIFIED AND ARE DOCUMENTED IN THE SAFETY IN DESIGN REPORT.
6. ALL EXISTING SERVICES SHOWN ARE APPROXIMATE ONLY.

6.1. EXISTING SERVICES ARE SHOWN APPROXIMATELY BASED OFF RECORDS. THE CONTRACTOR IS TO CONFIRM LOCATION AND DEPTH OF ALL EXISTING SERVICES PRIOR TO CONSTRUCTION.

6.2. WHILST CARE HAS BEEN TAKEN TO IDENTIFY ALL SERVICES, SOME SERVICES MAY BE UNIDENTIFIED AND THE CONTRACTOR IS TO PERFORM THEIR OWN INVESTIGATION TO SATISFY THEMSELVES OF THE LOCATION AND DEPTH OF SERVICES PRIOR TO CONSTRUCTION.

6.3. FOR EXTENTS OF DEMOLITION (INCLUDING REMOVAL AND REALIGNING OF EXISTING SERVICES) REFER TO ARCHITECTURAL DOCUMENTATION.
7. ALL EXISTING SERVICES ARE TO BE LOCATED AND PROTECTED SO AS TO PREVENT DAMAGE.
8. DO NOT SCALE, PHYSICALLY OR ELECTRONICALLY, FROM THESE CIVIL ENGINEERING DRAWINGS.
9. THESE CIVIL ENGINEERING DRAWINGS HAVE BEEN BASED ON UNVERIFIED EXISTING DRAWINGS AND LIMITED VISUAL INSPECTIONS OF THE EXISTING CIVIL ELEMENTS. THE CONTRACTOR IS TO EXPOSE THE EXISTING CIVIL ELEMENTS TO ALLOW THE CIVIL ENGINEER TO CONFIRM THESE CIVIL ENGINEERING DRAWINGS BEFORE CONSTRUCTION AND FABRICATION BEGINS.
10. READ THESE CIVIL ENGINEERING DRAWINGS IN CONJUNCTION WITH ALL ARCHITECTURAL DRAWINGS, OTHER CONSULTANTS' DRAWINGS, THE PROJECT SPECIFICATIONS AND OTHER WRITTEN INSTRUCTIONS THAT MAY BE ISSUED. REFER ANY DISCREPANCIES TO THE CIVIL ENGINEER FOR CLARIFICATION BEFORE PROCEEDING WITH THAT PART OF WORKS.
11. UNLESS NOTED OTHERWISE , ALL STRUCTURAL DIMENSIONS ARE IN MILLIMETRES, ALL CIVIL DIMENSIONS ARE IN METRES AND ALL LEVELS ARE IN METRES TO THE AUSTRALIAN HEIGHT DATUM.
12. ALL PENETRATIONS, CHASES ETC IN CIVIL ELEMENTS ARE TO BE APPROVED BY THE CIVIL ENGINEER BEFORE CONSTRUCTION UNLESS SHOWN IN THESE CIVIL ENGINEERING DRAWINGS.
13. INSTALL ALL PROPRIETARY PRODUCTS IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATIONS, RECOMMENDATIONS AND DETAILS.
14. ANY DEVIATION OR SUBSTITUTION FROM THE INFORMATION IN THESE CIVIL ENGINEERING DRAWINGS IS TO BE APPROVED BY THE CIVIL ENGINEER BEFORE CONSTRUCTION FABRICATION BEGINS.
15. DURING CONSTRUCTION MAINTAIN THE WORKS ARE IN A STABLE CONDITION AND ENSURE NO PART IS OVERTRESSED. PROVIDE ALL TEMPORARY PROPPING, BRACING AND SHORING NECESSARY TO ACHIEVE THIS. ANY TEMPORARY WORKS SHOWN IN THESE CIVIL ENGINEERING DRAWINGS ARE INDICATIVE ONLY.
16. WHERE CIVIL ENGINEERING CERTIFICATION OF CONSTRUCTION IS REQUIRED, THE CIVIL ENGINEER IS TO PERFORM ADEQUATE SITE VISITS TO ENSURE THE DESIGN INTENT OF THESE CIVIL ENGINEERING DRAWINGS IS ACHIEVED DURING CONSTRUCTION. THE CONTRACTOR IS TO GIVE A MINIMUM OF 48 HOURS NOTICE BEFORE THE COMMENCEMENT AND BEFORE THE COMPLETION OF ALL CIVIL ELEMENTS SHOWN IN THESE CIVIL ENGINEERING DRAWINGS. THE CIVIL ENGINEER REQUIRES INSPECTIONS AT THE FOLLOWING STAGES OF CONSTRUCTION.

16.1. AT COMPLETION OF EARTHWORKS UNDER THE BUILDING

16.2. PRIOR TO BACKFILLING OF ALL STORMWATER PITS & PIPES.

16.3. AT COMPLETION OF CIVIL WORKS.
17. QUALITY ASSURANCE TESTING IS TO BE PROVIDED AS PER THE REQUIREMENTS STATED ON THESE CIVIL ENGINEERING DRAWINGS.
18. THE DETAILED SURVEY USED IN THE PREPARATION OF THESE DRAWINGS HAS NOT SPECIFIED A PERMANENT SURVEY MARK, VERTICAL AND HORIZONTAL HAVE BEEN ASSUMED TO BE ARBITRARY. THIS SURVEY HAS BEEN USED TO FORM THE BASIS OF THE DOCUMENTED DESIGN LEVELS.

EARTHWORKS

1. ALL EARTHWORKS ACTIVITIES AND MATERIALS ARE TO BE IN ACCORDANCE WITH AS3798 THESE CIVIL ENGINEERING DRAWINGS AND THE PROJECT SPECIFICATIONS.
2. FOR EARTHWORKS ACTIVITIES IN THE LANDSCAPING AREAS, REFER TO THE LANDSCAPE ARCHITECTS DOCUMENTATION.
3. FILL BATTERS OUTSIDE PAVEMENTS AND WORKING PADS ARE TO BE FILLED USING MATERIAL FROM THE ON-SITE CUT OPERATIONS, WHERE CUT MATERIAL IS TO BE FREE OF ORGANIC MATTER AND BUILDING WASTE.
4. ANY IMPORTED FILL MATERIAL OUTSIDE PAVEMENTS AND WORKING PADS IS TO BE CBR15 MINIMUM, WELL GRADED AND FREE OF ORGANIC MATTER.
5. ALL BATTERS ARE TO BE 1 IN 6 UNLESS NOTED OTHERWISE.
6. INSTALL AND MAINTAIN EROSION AND SEDIMENT CONTROL SYSTEMS IN ACCORDANCE WITH THE LOCAL AUTHORITY'S REQUIREMENTS AND THESE CIVIL ENGINEERING DRAWINGS.
7. THE CONSTRUCTION SITE IS TO BE MAINTAINED TO MINIMIZE PONDING, EROSION AND DUST.
8. POSSIBLE CONTAMINATION OF THIS SITE HAS NOT BEEN INVESTIGATED. REPORT SUSPECT SOILS EXPOSED DURING SITE WORKS.
9. THE PREPARATION OF THE EXISTING SUBGRADE AND EARTHWORKS ACTIVITIES FOR THE EXTERNAL CONCRETE AREAS (SLAB ON GROUND) AND GENERAL AREAS OUTSIDE PAVEMENTS AND WORKING PADS ARE TO COMPLY WITH THE FOLLOWING:

9.1. PREPARE SUBGRADE AND CONSTRUCT EARTHWORKS UNDER ALL CONCRETE SLABS TO BULK EARTHWORKS LEVEL AND FOR A FURTHER 0.3m ALL ROUND.

9.2. STRIP ALL UNSUITABLE FOUNDATION MATERIAL (TOP SOIL, VEGETATION, ORGANICS, EXISTING UNCONTROLLED FILLING, ETC).

9.3. ALL EARTHWORKS MATERIAL (IMPORTED FILL AND CUT MATERIAL) OUTSIDE PAVEMENTS IS TO BE CBR15 MINIMUM, PLACED IN 200mm THICK MAXIMUM LAYERS AND COMPACTED TO MINIMUM 95% STANDARD COMPACTION.
10. THE EXISTING SUBGRADE PREPARATION AND PROPOSED EARTHWORKS ACTIVITIES FOR GRAVEL WORKING PAD UNDER BUILDING ARE TO COMPLY WITH THE FOLLOWING:

10.1. PREPARE SUBGRADE AND CONSTRUCT EARTHWORKS FOR GRAVEL WORKING PAD UNDER THE BUILDING AS NOTED ON PLANS AND DETAILS.

10.2. STRIP ALL UNSUITABLE FOUNDATION MATERIAL (TOP SOIL, VEGETATION, ORGANICS, EXISTING UNCONTROLLED FILLING, ETC) AS NOTED ON PLAN AND DETAILS.

- 10.3. PROOF ROLL SUBGRADE. REMOVE ANY FURTHER UNSUITABLE MATERIAL AND PROOF ROLL AGAIN.
- 10.4. FOR TENDER PURPOSES ALLOW IN ADDITION TO THE QUANTITIES ABOVE, 50m³ OF FURTHER UNSUITABLE MATERIAL TO BE EXCAVATED, REPLACED AND COMPACTED AS PER BELOW.
- 10.5. PLACE IMPORTED BLENDED GRANULAR MATERIAL IN ALL EXCAVATED, FILLED, REPLACED AND GRAVEL WORKING PAD UNDER BUILDING ZONES.
- 10.6. THE IMPORTED BLENDED GRANULAR MATERIAL IS TO COMPLY WITH THE FOLLOWING:

10.6.1. THE MATERIAL IS TO CONTAIN SUFFICIENT FINES TO MINIMIZE MOISTURE PENETRATION.

10.6.2. THE MATERIAL IS TO BE CBR15 MINIMUM

10.6.3. THE SHRINKAGE PRODUCT OF THE MATERIAL (LINEAR SHRINKAGE x % PASSING 0.425mm SIEVE) IS TO BE IN THE RANGE OF 100 TO 350.

10.6.4. THE GRADING OF THE MATERIAL IS TO MEET GRADING A, B, C, OR D OF THE MAIN ROADS SPECIFICATION.

10.6.5. THE MATERIAL IS TO BE PLACED IN 200mm THICK LAYERS AND COMPACTED TO 95% STANDARD.
- 10.7. PROOF ROLL THE COMPLETED EARTHWORKS.
- 10.8. CONTRACTOR IS TO ARRANGE AND CARRY OUT FIELD DENSITY TESTING OF THE FILL WITH A TESTING FREQUENCY AS DEFINED IN TABLE 8.1 OF AS3798 FOR TYPE 2: SMALL SCALE OPERATIONS.
11. PRIOR TO ANY EXCAVATION IN ROCK THE SUPERINTENDENT MUST BE ADVISED AND INSPECT THE SITE WITH THE STRUCTURAL AND / OR CIVIL ENGINEER. THE CONTRACTOR SHALL MAKE AVAILABLE PLANT AND EQUIPMENT NECESSARY FOR THE SUPERINTENDENT / ENGINEER TO MAKE A REASONABLE ASSESSMENT AS TO THE PRESENCE OR OTHERWISE OF ROCK, AND IF REQUIRED AGREE ON THE METHODOLOGY OF EXCAVATION AND REMOVAL. ROCK SHALL BE DEFINED AS HARD ROCK GEOLOGICALLY IN PLACE WHICH IN THE OPINION OF THE STRUCTURAL AND / OR CIVIL ENGINEER REQUIRES THE USE OF PNEUMATIC DRILLS OR BREAKERS FOR ITS REMOVAL AND SHALL INCLUDE ANY BOULDERS OF EQUAL HARDNESS EXCEEDING 0.4m³ IN VOLUME. ROCK EXCAVATION SHALL BE DEEMED TO BE EXCAVATION WITH A MINIMUM 22 TONNE OPERATING WEIGHT HYDRAULIC EXCAVATOR, WHERE PRODUCTION FOR INSITU MATERIAL TO LOAD IN A REAR DUMP TRUCK IS LESS THAN 10m³ PER HOUR WHEN OPERATED BY AN EXPERIENCED OPERATOR USING THEIR BEST ENDEAVOURS AND DESIGN MAXIMUM BREAKOUT FORCE. THE BUCKET WIDTH SHALL BE SUITABLE FOR THE TYPE OF MATERIAL BEING EXCAVATED AND A SINGLE TIME ATTACHMENT SHOULD BE USED WHERE NECESSARY.

STORMWATER DRAINAGE

1. ALL STORMWATER DRAINAGE ACTIVITIES AND MATERIALS ARE TO BE IN ACCORDANCE WITH THE CIVIL ENGINEERING DRAWINGS AND THE PROJECT SPECIFICATIONS.
2. STORMWATER PIPES ARE TO COMPLY WITH THE FOLLOWING, UNLESS NOTED OTHERWISE IN THESE CIVIL ENGINEERING DRAWINGS:

ELEMENT	GRADE	STANDARD
POLYVINYL CHLORIDE uPVC PIPES AND FITTINGS	SN8	AS1254, AS/NZS1260, AS1273, AS/NZS1477, ASNZS2179.2, AS2037
3. PIPE LAYING IS TO COMMENCE AT THE DOWNSTREAM END OF EACH LINE AND TO CONTINUE WITH THE FEMALE PIPE ENDS FACING UPSTREAM.
4. PIPE LAYING ACTIVITIES ARE TO COMPLY WITH THE FOLLOWING UNLESS NOTED OTHERWISE ON THE CIVIL ENGINEERS DRAWINGS:

4.1. DRAINAGE PIPES ARE TO BE LAID WITH A MINIMUM OF 100mm OF BEDDING MATERIAL TO THE BOTTOM, SIDES AND TOP OF PIPES.

4.2. SUBMIT DETAILS OF BEDDING MATERIAL FOR REVIEW BY THE CIVIL ENGINEER.

4.3. DRAINAGE PIPE EXCAVATIONS ARE TO BE BACK FILLED WITH GRANULAR MATERIAL

4.4. SUBMIT DETAILS OF BACKFILL MATERIAL FOR REVIEW BY THE CIVIL ENGINEER.

4.5. GRANULAR BACKFILL MATERIAL IS TO BE PLACED IN 150mm THICK LAYERS AND COMPACTED TO 95% STANDARD COMPACTION.
5. ALL STORMWATER PITS ARE TO COMPLY WITH THE FOLLOWING, UNLESS NOTED OTHERWISE ON THESE CIVIL ENGINEERING DRAWINGS:

5.1. INTERNAL SURFACES ARE TO BE RENDERED TO ENSURE A SMOOTH FINISH, ESPECIALLY AROUND PIPE PENETRATIONS.

5.2. EXTERNAL CONCRETE COLLAR TO BE PROVIDED AROUND PIPE AT JUNCTION WITH PITS.

5.3. PIT BASES ARE TO BE GROUTED TO ENSURE NO PONDING OF WATER.

5.4. PRE-CAST PIT CHAMBERS ARE TO HAVE A MINIMUM 100mm THICK WALL UNLESS OTHERWISE APPROVED BY THE ENGINEER.

5.5. SURCHARGE GRATES TO BE GALVANISED STEEL AND BOLTED TO PRE-CAST CHAMBER IN ACCORDANCE WITH MANUFACTURER'S REQUIREMENTS.

5.6. GRATES IN TRAFFICABLE AREAS SHALL BE CLASS D.

5.7. GRATES IN FOOTPATH AREAS ARE TO BE CLASS B WITH HEEL PROOF CONFIGURATION.

5.8. GRATES IN GRASSED OR LANDSCAPE AREAS ARE TO BE CLASS B.

5.9. PIT LIDS TO SIT FLAT WITH SURROUND AND NOT BE LOOSE OR MOVE UNDER LOADING.
6. ALL CONCRETE WORKS ARE TO BE IN ACCORDANCE WITH THE CONCRETE NOTES SPECIFIED ON THE STRUCTURAL ENGINEERS DRAWINGS, UNLESS NOTED OTHERWISE IN THESE CIVIL ENGINEERING DRAWINGS.

EROSION AND SEDIMENT CONTROL

1. ALL EROSION AND SEDIMENT CONTROL IS TO BE IN ACCORDANCE WITH THE CMDG, QUEENSLAND STATE PLANNING POLICIES, IECA (INTERNATIONAL EROSION CONTROL ASSOCIATION AUSTRALASIA) AND THE DEPARTMENT OF ENVIRONMENT, TOURISM, SCIENCE AND INNOVATION REGULATIONS AND GUIDELINES.
2. ALL EROSION AND SEDIMENT CONTROL DEVICES AND TREATMENTS SHOWN ON THESE CIVIL ENGINEERING DRAWINGS ARE CONSIDERED BY THE CIVIL ENGINEER TO BE A MINIMUM STANDARD FOLLOWING COMPLETION OF THE BULK EARTHWORKS.
3. THE CONTRACTOR IS TO PREPARE SUITABLE EROSION AND SEDIMENT CONTROL PLANS FOR ALL STAGES OF CONSTRUCTION, TAKING INTO CONSIDERATION CONSTRUCTION STAGING AND MINIMISING THE AMOUNT OF "DISTURBED AREA" AT ANY GIVEN TIME. THE CONTRACTORS EROSION AND SEDIMENT CONTROL PLANS ARE TO BE PREPARED AND DISTRIBUTED TO THE CIVIL ENGINEER AND LOCAL AUTHORITY PRIOR TO THE PRE-START MEETING.
4. INSTALLATION OF ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES IS TO OCCUR PRIOR TO COMMENCEMENT OF EARTHWORKS OPERATIONS.
5. THE CONTRACTOR IS TO ENSURE ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES DOCUMENTED ON THESE CIVIL ENGINEERING DRAWINGS ARE MAINTAINED FOR THE DURATION OF THE CONSTRUCTION WORKS.
6. ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE CHECKED, MAINTAINED AND CORRECTED AS NECESSARY FOLLOWING RAIN EVENTS.
7. THE CONTRACTOR SHALL ENSURE DUST RESULTING FROM THE EARTHWORKS OPERATIONS IS KEPT TO A MINIMUM BY THE APPLICATION OF WATER TO THE EARTHWORKS AREA, ESPECIALLY ON DAYS OF WINDY WEATHER.
8. CONSTRUCTION VEHICLES ENTRY/EXIT SEDIMENT TRAPS ARE TO BE INSTALLED AT SITE ACCESS POINTS.
9. FOR ALL PERMANENT EROSION AND SEDIMENT CONTROL MEASURES REFER TO THE LANDSCAPE ARCHITECTS DOCUMENTATION.
10. THE CONTRACTOR IS TO MAINTAIN ALL PERMANENT EROSION AND SEDIMENT CONTROL DEVICES REGULARLY FOR A MINIMUM PERIOD OF 3 MONTHS OR UNTIL THE SATISFACTION OF THE CIVIL ENGINEER (I.E. TURF IS FIRMLY ROOTED).

QUALITY ASSURANCE TESTING

1. GRAVEL WORKING PAD UNDER BUILDING SUBGRADE

1.1. SOAKED CBR: 1 FOR THE GRAVEL WORKING PAD AREA

1.2. FIELD DENSITY: 2 FOR THE GRAVEL WORKING PAD AREA.
2. GRAVEL WORKING PAD UNDER BUILDING IMPORTED FILL

2.1. PARTICLE SIZE DISTRIBUTION: 1 NO REQUIRED OF COMPACTED SAMPLE.

2.2. ATTERBERG LIMITS: 1 NO REQUIRED OF COMPACTED SAMPLE.

2.3. SOAKED CBR: 1 FOR THE GRAVEL WORKING PAD AREA.

2.4. FIELD DENSITY: 2 FOR THE GRAVEL WORKING PAD AREA.
3. STORMWATER DRAINAGE BACKFILL: 1 FIELD DENSITY TEST PER TRENCH BETWEEN PITS.
4. AS-CONSTRUCTED:

4.1. THE CONTRACTOR SHALL PROVIDE LEVELS AND DIMENSION INFORMATION SUITABLE TO CONFIRM TO THE SATISFACTION OF THE ENGINEER THAT THE WORKS HAVE BEEN CONSTRUCTED TO THE LEVELS AND DIMENSIONS SHOWN ON THE DRAWINGS. THE AS-CONSTRUCTED DATA PROVIDED MUST BE SUITABLE FOR THE PREPARATION OF DRAWINGS TO BE SUBMITTED TO THE CLIENT FOR APPROVAL. THE MINIMUM INFORMATION REQUIREMENTS ARE AS FOLLOWS:

4.1.1. LOCATIONS OF STORMWATER PITS.

4.1.2. INVERT LEVELS OF INLET AND OUTLET PIPES AT STORMWATER ON LAYOUT PLAN.

4.1.3. TOP OF STORMWATER PIT LEVELS AT THE CENTRE POINT ON LAYOUT PLAN.

4.1.4. INDICATE ACTUAL PIPE SIZES, CLASSES AND GRADES ON THE LAYOUT PLAN.

4.1.5. DRAINAGE CHANNEL LOCATION, INVERT LEVELS & DIMENSIONS.

4.1.6. LEVELS AT CRITICAL DESIGN POINTS (AS NOTED ON DRAWINGS).

4.1.7. ALL DIMENSIONS SHALL BE PROVIDED IN METRES CORRECT TO 2 DECIMAL PLACES. ALL LEVELS SHALL BE ON AUSTRALIAN HEIGHT DATUM (AHD) AND THE AS-CONSTRUCTED SURVEY ON THE SAME COORDINATE SYSTEM AS THE DESIGN DOCUMENTATION SURVEY.

DRAWING LIST

C01	SPECIFICATION NOTES
C02	BULK EARTHWORKS PLAN
C03	CIVIL WORKS PLAN
C04	CIVIL DETAILS
C05	EROSION AND SEDIMENT CONTROL PLAN AND DETAILS
C06	CONCRETE PATHWAY LEVELS PLAN

Revision						Client	Project	TENDER	Project Number
Date	Revision Description			Drawn	Design				
1	03/11/2025	50% CD ISSUE	JC	JC	MD	STANWELL	Janes and Stewart Structures Pty Ltd 120 William Street Po Box 1072 Rockhampton 4700 07 4922 1948 janes.and.stewart@jsstructures.com.au ABN 30 620 233 025	NOT FOR CONSTRUCTION PURPOSES	25052
2	28/11/2025	90% CD ISSUE	JC	JC	MD				
3	19/12/2025	100% CD ISSUE	JC	JC	MD				
A	09/03/2026	FOR TENDER	JC	JC	MD				
						MATTHEW DENNIS R.P.E.Q.24862	Janes and Stewart Structural+Civil CONSULTANTS	SPECIFICATION NOTES	A
						APPROVAL FOR ISSUE FOR AND ON BEHALF OF JANES AND STEWART STRUCTURES PTY LTD			
						A3 SHEET - DO NOT SCALE			
								SWITCHYARD ROAD, STANWELL, QLD, 4702	