

Import Business Process detail items

STANWELL OFFICE BUILDING - CIVIL WORKS CONSTRUCTION QUANTITY ESTIMATE

Note: Do not change column structure

Do not enter symbols, such as currency or digit grouping, in the numeric fields.

Enter a negative numeric value using these formats only: -123456.99 or -123456.99.

D	Work Item ID	Cost Line Item Type	Work Item Description	Provisional	Quantity	Unit of Measure
D	MRP Items					
D	MRP11 Jul 17		Principal's Obligations			
D			Principal's Obligations			
D	19090	Lump Sum	Service investigation works		1	lumpsum
D	19100	Lump Sum	Service relocation and alterations		1	lumpsum
D	MRS Items					
D	MRS02 Nov 22		Provision for Traffic			
D			Provision for Traffic			
D	20004	Unit Cost	Supply of temporary barriers	P		m
D	20005	Unit Cost	Installation of temporary barriers	P		m
D	20018	Lump Sum	Design of temporary traffic management (TGS)		1	lumpsum
D	20019	Lump Sum	Implementation, maintenance and removal of temporary traffic management		1	lumpsum
D	20020	Lump Sum	Administration of temporary traffic management		1	lumpsum
D	MRS03 Jul 21		Drainage Structures, Retaining Structures and Embankment Slope Protections			
D			Supply and Installation of Culverts			
D	30251	Unit Cost	Supply and installation of steel-reinforced concrete pipe culvert components, Class [4], [375] mm diameter, [B2] environment		4.0	m
D			Pavement Drainage			
D	30451	Unit Cost	Concrete kerb, [600 x 150 mm flush kerb] Refer to drawing 25-595_A4 / 103		92	m
D	30454	Unit Cost	Concrete kerb and channel, [CMDG Type 2]		113	m
D	30465	Unit Cost	Precast concrete side inlet gullies with precast shaft, [2400 Left Unit 900x600x1000 mm pit] Refer to drawing25-595_A4 / 105		1	each
D			Subsurface Drainage			
D	30554	Unit Cost	Subsoil drain clean-out, [150] mm diameter, [PVC]		2	each
D	30556	Unit Cost	Strip filter drains [170] mm x [40] mm MEG170		180	m
D	30557	Unit Cost	Sheet or strip filter drain outlet connection, [DN100 adapter]		4	each
D	MRS04 Nov 22		General Earthworks			
D			Preparation			
D	32001	Unit Cost	Clearing and grubbing		2920	m^2
D	32003	Unit Cost	Stripping of topsoil (Provisional Quantity, as directed)	P	50	m^3
D			Excavation			
D	32101	Unit Cost	Excavation, all materials		227	m^3
D			Embankment			
D	32201	Unit Cost	Embankment		235	m^3
D	MRS05 Jul 22		Unbound Pavements			
D			Unbound Pavements			
D	40002	Unit Cost	Subtype 2.1, Unbound pavement, [Base / Laneway+Parking]		54	m^3
D	40004	Unit Cost	Subtype 2.3, Unbound pavement, [SubBase / Laneway+Parking]		71	m^3
D	MRS11 May 22		Sprayed Bituminous Treatments (Excluding Emulsion)			
D			Sprayed Bituminous Treatments (excluding Emulsion)			
D	40724	Unit Cost	Sprayed bituminous treatment, type [C170], [including 10mm] supply of cover aggregates, [Laneway + Parking], refer to Clause 2 of Annexure MRTS11.1		260	m^2
D	MRS14 Mar 22		Road Furniture			
D			Guidance and Information Systems			
D	50053	Unit Cost	Supply of regulatory, warning and hazard sign faces, [sign type] Refer to Drawing 25-595_A4 / 108		3	each
D	50057	Unit Cost	Installation of regulatory, warning and hazard signs, [2]		2	each
D	MRS16 Jul 17		Landscape and Revegetation Works			
D			Landscape and Revegetation - Imported Materials			
D	50709	Unit Cost	Imported topsoil (Provisional Quantity, if ordered) Subtract any site won material	P	95	m^3
D			Landscape and Revegetation - Ground Preparation			
D	50803	Unit Cost	Installation of topsoil [100 mm]		950	m^2
D			Landscape and Revegetation - Seeding			
D	50851	Unit Cost	Seed Mix - Grassland Mix [mix name]		45	kg
D	50854	Unit Cost	Installation of broadcast seeding []		950	m^2
D	MRS28 Nov 19		Contractor's Site Facilities and Camp			

D			Contractor's Site Facilities and Camp		
D	20101	Lump Sum	Contractor's site facilities	1	lumpsum
D	MRS30 Mar 22		Asphalt Pavements		
D			Medium Duty Dense Graded Asphalt		
D	41754	Unit Cost	Medium duty dense graded asphalt in surfacing course, AC [14] M mix	30.5	Tonne
D	MRS40 Nov 18		Concrete Pavements Base		
D			Concrete Pavement Base		
D	42903	Unit Cost	Supply and place concrete in jointed reinforced base	31	m^3
D	42906	Unit Cost	Finish, cure and texture base	305	m^2
D	MRS45 Nov 22		Road Surface Delineation		
D			Line Marking		
D	52116	Unit Cost	Transverse lines (stop lines, holding lines, markings at Stop and Give Way signs, pedestrian crosswalk lines, arrows, shapes, symbols and numerals), colour [colour], m	16	m^2
D	MRS52 Nov 21		Erosion and Sediment Control		
D			General		
D	20501	Lump Sum	Erosion and Sediment Control Plan(s)	1	lumpsum
D	20502	Lump Sum	Erosion and Sediment Control Devices (Non-Itemised)	1	lumpsum
D	Non-Standard 90000 Series Items				
D		each			
D	90501	Unit Cost	Non Standard Item - Supply and install metal drainage kerb adapters (100 mm) Refer to drawing 25-595_4A/105	3	each
D	90502	Unit Cost	Non Standard Item - Supply and install DN100 uPVC 45 deg Bend Fittings	4	each
D		m			
D	91001	Unit Cost	Non Standard Item - Supply and install DN100 Class 12 uPVC outlet for MEG170 drains Refer to drawing 25-595_4A/105	28	m