

SCOPE OF WORK

Project: SPS New Project Building (Supply & Install)

RFT # 1221995761

Date: 17 April 2026

Document Status	
Project No: #1221995761	Document Owner: Peter Smith – Procurement Manager

REV	DATE		
A	15/03/2026	Issued for Quotation	P. Smith

Endorse	Signature	Date
Peter Smith – Procurement Manager	P. Smith	16.04.2026

Approve	Signature	Date
Brenton Jensen – Major Programs Superintendent	B. Jensen	16.04.26

Table of Contents

Contents

1.0	Introduction	3
1.1	Purpose.....	3
1.2	Reference to Contract	3
1.2.1	Principal Acting Through the Superintendent	3
1.3	Principal Contractor Status	3
1.4	Project Overview	3
1.5	Location and Site Conditions	3
1.6	Key Interfaces	5
1.6.1	WHS Interface Clarification	5
1.6.2	Existing Stanwell power station operations.....	5
1.7	Principal's guides and procedures.....	6
1.8	Order of Precedence.....	6
1.9	Scope of Work Statement	6
2.0	Scope of Work Description	6
2.1.1	Scope Completeness	7
3.0	Works Included	7
3.1	Site Access, Security and Inductions.....	7
3.2	Mobilisation.....	8
3.2.1	Pre-Mobilisation Conditions	8
3.3	Temporary Building Works.....	8
3.4	Services, Utilities and Facilities.....	8
3.4.1	Existing Services	9
3.4.2	Foreseeable Conditions	9
3.5	Design.....	9
3.6	Procurement	9
3.6.1	Queensland Charter for Local Content (QCLC)	9
3.6.2	Planning and Tracking.....	10
3.7	Off-site fabrication	10
3.7.1	Quality Assurance and Traceability.....	11
3.7.2	Transport and Logistics.....	11
3.7.3	Offloading and Handling.....	11
3.7.4	Storage and Laydown	11
3.7.5	Preservation and Protection	11

3.8	Demolition	11
3.8.1	Pre-Demolition Requirements.....	12
3.8.2	Protection of People, Property and Operations	12
3.8.3	Services Disconnection and Removal	12
3.8.4	Environmental and Safety Controls	12
3.8.5	Materials, Waste and Salvage.....	12
3.8.6	Completion of Demolition.....	13
3.9	Construction Works.....	13
3.9.1	Design, Coordination and Interfaces.....	13
3.9.2	Services and Integration.....	13
3.9.3	Completion and Making Good.....	13
3.10	External & Site Works.....	14
3.11	Testing, Commissioning & Handover	14
3.11.1	Testing and Verification	14
3.11.2	Commissioning Execution	14
3.11.3	Handover and Practical Completion.....	15
3.11.4	Training.....	15
3.11.5	Defects and Close-Out	15
3.12	Demobilisation	15
3.12.1	Removal of Temporary Works and Plant.....	15
3.12.2	Make-Good and Reinstatement	16
3.12.3	Cleaning and Waste Removal.....	16
3.12.4	Services and Temporary Connections	16
3.12.5	Handover and Access Clearance.....	16
3.12.6	Documentation and Close-Out.....	16
3.12.7	Safety and Compliance.....	16
4.0	Works Excluded	16
4.1.1	Interfaces with Principal-Engaged Contractors.....	16
5.0	Design Responsibility	17
6.0	Authority Approvals & Fees	17
7.0	Project Management.....	17
7.1	General.....	17
7.2	Management Plans.....	18
7.2.1	Project Execution Plan.....	18
7.2.2	Construction Management Plan.....	18
7.2.3	Commissioning Plan.....	19

7.3	Project Information Management	20
7.3.1	Document Submission.....	20
7.4	As Built Requirements.....	20
7.4.1	As-Built Drawings.....	21
7.4.2	Calculations.....	22
7.4.3	Manuals.....	22
8.0	Reporting and Programming Requirements	22
8.1	Contract Program.....	22
8.2	Commodity Curves	23
8.3	90-Day Lookahead schedule	23
8.4	Monthly Status Report.....	24
8.5	Weekly & Daily Reports / Meetings.....	24
8.5.1	Contractor's Weekly Dashboard	24
8.5.2	Daily reports	25
8.5.3	Weekly Progress Meeting	25
8.5.4	Three-Week Lookahead Schedule	25
9.0	Health, Safety and Environment.....	26
10.0	Quality Management System	26
10.1	Quality Plan	27
10.2	Inspection and Test Plans	28
10.3	Requests for Information (RFI)	29
10.4	Non-Conformances	29
10.5	Quality Audits	30
10.6	Manufacturers Data Report	30
11.0	General Site Requirements	30
11.1	Fitness for Work.....	30
11.2	Standard Work Hours	30
12.0	Abbreviations and Definitions	31
13.0	Appendices	33
14.0	Appendix A - Reference Drawings and Documents.....	34
15.0	Appendix B – Supplier Deliverable Requirement List (SDRL)	39
16.0	Appendix C – HSE-PROC-18-Principal Contractor	44
17.0	Appendix D – Hazardous Building Materials Register	45

1.0 Introduction

1.1 Purpose

The purpose of this document is to describe the Scope of Works for the Stanwell New Projects Office (NPO) Project at Stanwell Power Station (SPS).

This document defines the scope boundaries, inclusions, exclusions, and responsibilities and is to be read in conjunction with the detailed Architectural Specification and the Contract.

1.2 Reference to Contract

Capitalised terms used in this Scope of Work have the same meaning as defined in the Contract, unless expressly stated otherwise.

1.2.1 Principal Acting Through the Superintendent

Except where expressly stated otherwise in the Contract, all rights, approvals, acceptances, directions, instructions and consents of the Principal under this Scope of Work are exercised by the Principal acting through the Superintendent.

No action or inaction by the Superintendent shall be construed as relieving the Contractor of any obligation, responsibility or risk under the Contract.

1.3 Principal Contractor Status

Without limiting clause 12 (Protection of people and property) of the Contract, the Contractor is appointed as the Principal Contractor under this Contract for the purposes of the Work Health and Safety Act 2011 (Qld) and associated Regulations and bears all statutory duties, obligations and responsibilities of a Principal Contractor in relation to the Work Under the Contract.

1.4 Project Overview

The project involves constructing a single-storey, suspended lightweight office building with a skillion roof and a total floor area of 1,543.2 m².

The building is organised around an elevated landscaped courtyard featuring a link bridge, water feature and stormwater system. It will provide modern workplace facilities for up to 107 staff, including offices, meeting and training spaces, amenities, kitchens, storage and covered outdoor areas.

The scope also includes external works such as landscaping, fencing, access ramps, stairs and mechanical plant enclosures, along with significant civil works including demolition of existing demountable offices as per the design drawings ([Appendix A – Reference Drawings and Documents](#)).

Acoustic treatments are incorporated to manage external noise and ensure suitable internal sound performance throughout the facility.

1.5 Location and Site Conditions

SPS is located 22km west of Rockhampton in central Queensland, with a capacity to generate 1,460 megawatts. Commissioned in 1993 – 1996 Stanwell Power Station is the most technologically advanced and automated coal fired power station in Australia.




Figure 1: Site Location



Figure 2: Site of Work location (detailed battery limits illustrated in Site Precinct Plan: A-040001)

Site conditions: Site conditions are based upon historical climate data (1939-2022) at the Rockhampton Aero weather station (039083).

Climate statistic	Unit	Value
Minimum temperature (039083)	°C	-1.0
Maximum temperature (039083)	°C	45.3
Mean relative humidity (039083)	%	40 – 73
Site elevation (Site of Work)	M (ASL)	60
Wind speed region (according to AS/NZS 1170.2:2021)	-	Region C
Corrosion region (to AS 4312-2019)		C3 – Very High (Industrial)
Importance level		2
Terrain category		2

1.6 Key Interfaces

The Contractor is responsible for managing all interfaces necessary to deliver the Work Under Contract (WUC), including interfaces with the Principal, Superintendent, separate contractors, consultants, authorities, existing operations, existing services, internal trades, end users, and the supply chain.

1.6.1 WHS Interface Clarification

Nothing in this Scope of Work shall be construed as transferring any duty of a Principal Contractor to the Principal or the Superintendent.

The Principal and Superintendent retain their respective roles under the Contract only and do not assume control of the Works or WHS management.

1.6.2 Existing Stanwell power station operations

The Contractor is required to interface with site during the works to minimise impact to operations and maintenance activities.

The following activities are anticipated to be occurring within close proximity of the construction are during all works related to this Contract:

1. General Operations;
2. Unit 3 outage between 30 May and 24 July 2026;
3. Unit 4 outage between 03 July and 27 July 2027; and
4. General Site Access.

The Contractor must provision for a significant increase to personnel and traffic interactions during the outage periods.

The Contractor must undertake a risk assessment prior to construction to confirm any critical times where operations / maintenance may not be completed.

1.7 Principal's guides and procedures

The Contractor is responsible for ensuring it is familiar with, and complies with, all Principal manuals, guides, policies, procedures and forms applicable to the Works and the WUC, as made available from time to time, including those published at [Stanwell Doing Business with Us](#).

Without limitation, the Contractor must fully comply with HSE-PROC-18 – Principal Contractor HSE Requirements ([Appendix C – HSE-PROC-18 – Principal Contract](#)), as amended from time to time, which sets out the Principal's minimum Health, Safety and Environment (HSE) requirements.

Compliance with HSE-PROC-18 is a mandatory contractual obligation and does not limit or reduce the Contractor's statutory duties as Principal Contractor under applicable legislation or its obligations under the Contract, and the Contractor must ensure all subcontractors, suppliers and personnel engaged in the Works comply with these requirements as applicable to their activities.

1.8 Order of Precedence

In the event of ambiguity or contradiction between references in this Scope of Work, the ambiguity or contradiction shall be resolved by giving precedence to the documentation in the order listed below:

5. Statutory and Legislative Requirements;
6. The Contract;
7. This description of the Work under Contract contained in this Scope of Work document;
8. Project specific design drawings;
9. Project specific design documentation;
10. Stanwell's Standards and Procedures; and
11. Australian Standards.

The Project specific drawings, documents and specifications shall be read in their entirety to describe the Work under Contract.

The Contractor must raise any conflicts between the referenced documents and submit the most onerous requirement for approval before proceeding.

1.9 Scope of Work Statement

The Scope of Work includes all management, labour, supervision, training, authorisations, construction plant and equipment, tooling, temporary works, tie-ins, facilities, materials and equipment, mobilisation and demobilisation, accommodation, transport, lubricants and consumables required for the safe delivery of scope requirements.

2.0 Scope of Work Description

The project comprises a single-storey, suspended lightweight building with a skillion roof, approximately 46.2m x 46.2m in size. The design is centred around an elevated landscaped courtyard, which serves as a focal point and includes a link bridge, water feature, and stormwater collection system.

The total built area is 1,543.2m², accommodating a modern workplace environment with the following key functional spaces:

Workplace Facilities:

1. Open-plan office space for up to 107 staff;
2. Meeting rooms and associated breakout areas;
3. Boardroom;

4. First aid room;
5. Kitchen and dining facilities;
6. Staff kitchen and outdoor kitchen;
7. Lockers and amenities;
8. Training rooms;
9. Storage areas;
10. Covered outdoor area; and
11. Associated support services.

External and Site Works:

1. Landscaping works including planting and hardscape paving;
2. Steel-framed mesh fencing;
3. External access ramps and stairs;
4. Relocation and refurbishment of two existing covered shade structures;
5. External mechanical plant enclosure for chilled water systems; and
6. Dedicated mechanical plant zones for air handling units, generally located above meeting spaces.

Infrastructure and Civil Works:

1. Demolition of approximately 1,700m² of existing demountable office buildings;
2. Installation of a new Fire Indicator Panel; and
3. Site regrading to support overland flow and integration of a new retaining wall for the courtyard.

2.1.1 Scope Completeness

The WUC includes all work, materials, services and activities necessary to deliver a complete, functional and compliant facility fit for its intended purpose, whether or not each item is expressly identified in the Contract (including this Scope of Work and the Architectural Specification).

3.0 Works Included

The Contractor's scope includes, but is not limited to, the following:

3.1 Site Access, Security and Inductions

The Contractor must:

1. Comply with all Stanwell Power Station site rules, security requirements, and induction processes should access be required;
2. Ensure that all Contractor personnel complete the required inductions to enter the Site;
3. Provide all temporary works including fencing, hoardings, protection, traffic management, and access control;
4. Coordinate deliveries within the permitted delivery time windows;
5. Be responsible for unloading, storage, preservation, care custody and control of all items delivered to Site; and
6. without limiting clause 14 (Care of WUC and reinstatement of damage) of the Contract, protect occupied premises during the period of WUC.

3.2 Mobilisation

The Contractor must not mobilise to Site until all pre-mobilisation requirements including its completion of Mobilisation Checklist (ref: T-3913) have been satisfied to the Principal's and Superintendent's acceptance.

3.2.1 Pre-Mobilisation Conditions

Prior to mobilisation, the Contractor must prepare, submit and obtain acceptance (where required) of all documents and information necessary to demonstrate readiness to mobilise, including but not limited to:

1. Construction Program identifying mobilisation activities, site establishment, sequencing and interfaces with concurrent or Principal-engaged works;
2. Project Quality Management Plan, including Inspection and Test Plans applicable to early works;
3. Environmental Management Plan and associated control measures (including erosion, sediment, dust, waste and noise controls);
4. Work Health and Safety Management Plan and Safe Work Method Statements for mobilisation and early site activities;
5. Site establishment layouts showing construction areas, laydown areas, access routes, fencing, signage, traffic management and temporary facilities; and
6. Details of the Contractor's nominated site representatives, including after-hours emergency contacts.

Mobilisation will not be deemed approved until all mandatory submissions have been made in accordance with the Contract Documents.

3.3 Temporary Building Works

The Contractor must establish the Site in a safe, orderly and compliant manner, including:

1. Installation and maintenance of temporary fencing, hoardings, barriers, signage and traffic management;
2. Establishment of approved construction areas, laydown areas and site offices strictly within the defined Site battery limits;
3. Provision, operation and maintenance of all Temporary Works necessary for execution of the Works; and
4. Protection of existing services, structures, assets and vegetation to remain.

No permanent Works may commence until site establishment has been completed and accepted by the Principal (acting through the Superintendent).

3.4 Services, Utilities and Facilities

The Contractor must provide and maintain all temporary services required for the Works, including power, water, telecommunications and internet.

No permanent ablution, welfare or communications facilities will be provided by the Principal, the Contractor shall provide all required amenities during WUC.

Existing services may only be used where expressly permitted and shall be protected from damage at all times.

3.4.1 Existing Services

The Contractor is responsible for identifying, protecting and managing all existing services affected by the Works.

Service locations are to be confirmed during planning, with underground and above-ground services positively identified and marked prior to any works.

All required isolations will be implemented by the Principal in accordance with Business Procedure OHS-PROC-149 – Isolation of Plant Handover and formally handed over to the Contractor through the Plant Handover process, with the Principal retaining control of isolations at all times.

The Contractor must maintain essential services unless otherwise approved, protect all services and assets to remain, comply with excavation and utility authority requirements, and rectify any damage at no cost to the Principal.

Where services are concealed, details must be submitted for approval and clearly recorded for future identification.

3.4.2 Foreseeable Conditions

Subject to clause 25 (Latent conditions) of the Contract, the Contractor acknowledges that the Works involve construction within an operational industrial environment and accepts the risk of all conditions that a competent and experienced contractor could reasonably foresee having regard to the Site, the Contract and the nature of the Works.

3.5 Design

Where the Contractor is responsible for any part of the design under the Contract, the Contractor must carry out and complete all design activities necessary for the proper execution and completion of the Works in accordance with the Contract.

The Contractor is fully responsible for the adequacy, accuracy, completeness and fitness for purpose of all design documents prepared by or on behalf of the Contractor, including compliance with the Scope of Work, Specifications, Drawings, applicable Australian Standards and all legislative and statutory requirements.

Without limiting clause 7A.2 (Contractor's Design) of the Contract, the Contractor must ensure that all design is coordinated with the Works, suitable for construction, and capable of achieving the required performance outcomes.

Without limiting clause 7A.3 (Superintendent may review Contractor's Design Documents) of the Contract, any review, comment, approval or non-rejection of design documents by the Principal, the Superintendent or their representatives does not relieve the Contractor of its design obligations, nor does it transfer design responsibility or risk.

The Contractor remains solely liable for all errors, omissions, non-compliances and consequences arising from the design, whether carried out directly or by subcontractors or consultants engaged by the Contractor.

3.6 Procurement

3.6.1 Queensland Charter for Local Content (QCLC)

The Works under this Contract are subject to the QCLC under the Queensland Industry Participation Policy Act 2011.

The QCLC registration number for the Works is **WR26/7897**.

Without limiting clause 49.3 (Queensland Charter for Local Content) of the Contract, the Contractor must, in planning and executing the supply, fabrication, delivery and installation of the Works, provide full, fair and reasonable opportunities for capable Queensland and regional suppliers, manufacturers and service providers to participate in the Works, where they are competitive and meet the technical, commercial and delivery requirements of the Contract.

The Contractor must comply with the requirements of the QCLC, including the preparation, submission and implementation of any required Statement of Intent and Project Outcome Report, in accordance with the Charter and the Contract.

[Queensland Charter for Local Content Website](#)

3.6.2 Planning and Tracking

The Contractor is to develop and maintain a procurement register to be used as the single source of truth for planning, tracking, and assuring all construction related procurement packages across the project lifecycle, from early works through close-out.

The procurement register must capture all procurement related to WUC, be developed in Microsoft Excel or similar and be made available to the Superintendent and Principal in native format.

Mandatory data fields are to include at a minimum:

1. Unique Procurement ID;
2. Package name and description;
3. Workstream description (e.g. Early Works / Main Works / Fit-out);
4. Required on site date;
5. Milestones applicable to the package (tender open, tender close, award, delivery, start dates etc.);
6. Vendor / suppliers; and
7. Specify any local, first nations and/or small to medium suppliers.

The register shall support:

1. Executive procurement dashboards;
2. Forward commitment and cash-flow forecasting;
3. Long-lead risk reporting; and
4. Audit and probity reviews.

3.7 Off-site fabrication

The Contractor must plan, coordinate and execute all off-site fabrication of components forming part of the Works, including any shop detailing, prefabrication, modularisation or pre-assembly, whether or not specifically identified in the Contract.

Off-site fabrication must comply with the Contract, approved shop drawings, specifications, relevant Australian Standards, and manufacturer's requirements.

The Contractor is responsible for quality, dimensional accuracy, finish, completeness, and fitness for purpose of all prefabricated items, notwithstanding any review or acceptance of shop drawings or inspections by the Superintendent or Principal.

3.7.1 Quality Assurance and Traceability

The Contractor must implement quality controls for off-site fabrication equivalent to those required for on-site WUC, including inspection and test plans, hold points where applicable, and full traceability of materials and components.

Records must be maintained for fabrication, inspection, testing, and corrective actions and made available to the Superintendent upon request.

3.7.2 Transport and Logistics

The Contractor must arrange and manage all transport and logistics associated with the delivery of prefabricated components from the place of manufacture to the Site.

Transport must:

1. Protect components from damage, deformation, contamination and weather exposure;
2. Comply with all legislative requirements, including Heavy Vehicle National Law and site access restrictions;
3. Be coordinated with the Principal (acting through the Superintendent), including delivery sequencing, delivery times, and access approvals; and
4. Allow for Site constraints, including shared roads, secure areas, delivery windows, and operational interfaces with Stanwell Power Station.

3.7.3 Offloading and Handling

The Contractor must provide all labour, supervision, lifting equipment, plant and temporary works necessary to safely offload prefabricated items at the Site.

3.7.4 Storage and Laydown

The Contractor is responsible for the storage of all prefabricated components, whether stored off-site or on-site.

3.7.5 Preservation and Protection

The Contractor must preserve and protect all prefabricated components in accordance with manufacturer's recommendations and good industry practice from fabrication through to incorporation into the Works.

3.8 Demolition

The Contractor must carry out all demolition works required to facilitate the Works as documented in the Contract, including but not limited to:

1. Demolition and removal of existing demountable office buildings and associated structures as required by the Contract;
2. Removal of redundant services, fixtures, fittings, pavements and ancillary elements affected by the Works; and
3. Making safe, capping, isolating or diverting existing services as required for demolition and subsequent construction.

Demolition shall be limited to the areas and extents documented. No additional demolition may be undertaken without the prior written direction of the Superintendent.

3.8.1 Pre-Demolition Requirements

Prior to commencing demolition, the Contractor must:

1. Verify the location, condition and status of all existing services, including underground services, noting that drawings of existing services are indicative only and no warranty is given as to their accuracy;
2. Submit demolition methodologies, sequencing and Safe Work Method Statements addressing safety, environmental controls and protection of adjacent assets; and
3. Coordinate demolition activities with Site operations, access constraints and any concurrent or Principal-engaged works.

Demolition must not commence until the Superintendent is satisfied that all pre-demolition requirements have been met.

3.8.2 Protection of People, Property and Operations

The Contractor must protect all persons, occupied premises, adjacent facilities, structures, services and assets to remain.

Safe access must be maintained at all times for Site occupants and operations.

Demolition activities shall be planned and executed to minimise nuisance, including noise, dust, vibration and disruption to ongoing operations.

Any damage caused by demolition activities must be promptly made good at the Contractor's cost.

3.8.3 Services Disconnection and Removal

Existing services affected by demolition must be isolated, disconnected, removed or diverted in a controlled manner.

Redundant services shall be removed or made safe as part of the demolition works.

Interruptions to existing services must be minimised and coordinated in advance with the Superintendent.

3.8.4 Environmental and Safety Controls

Demolition works must comply with the approved Environmental Management Plan and all statutory requirements.

Measures shall be implemented to control dust, noise, waste, runoff and pollution.

All demolition waste must be removed from Site and disposed of lawfully.

3.8.5 Materials, Waste and Salvage

Unless expressly stated otherwise in the Contract, demolished materials become the property of the Contractor and must be removed from Site.

Hazardous materials, if encountered, must be managed strictly in accordance with statutory requirements and the Contract. Refer to [Appendix D – Hazardous Building Materials Register](#).

3.8.6 Completion of Demolition

Following demolition, the Site must be left clean, safe and suitable for subsequent Works.

All temporary supports, protections and debris associated with demolition must be removed.

Demolition works must be deemed complete only when accepted by the Superintendent.

3.9 Construction Works

The Contractor must carry out all construction works necessary to deliver the Works in accordance with the Contract, including the Architectural Specification, drawings, schedules and referenced standards.

The construction works include, without limitation:

1. Construction of the new single-storey office facility and associated internal and external building works;
2. Structural, architectural and building fabric works, including framing, linings, finishes, doors, windows, glazing, roofing and cladding;
3. Coordination and integration of all building services works (mechanical, electrical, hydraulic, fire and communications) as documented; and
4. External works within the Site battery limits, including pavements, access ramps, stairs, landscaping and associated civil works.

All construction activities must be carried out to achieve a complete, functional and compliant facility.

3.9.1 Design, Coordination and Interfaces

The Contractor must coordinate all construction activities across trades and disciplines and manage interfaces between architectural, structural and services works.

Layouts shown on drawings are diagrammatic unless figured, the Contractor must verify dimensions, levels and conditions prior to construction.

The Contractor must coordinate construction with existing Site operations, occupied premises and any concurrent or Principal-engaged works.

3.9.2 Services and Integration

Building services must be installed, tested and commissioned in coordination with the construction works and to the satisfaction of the Superintendent.

Penetrations, fixings and supports required for services must be fully coordinated with architectural and structural elements.

No services shall be concealed until required inspections and approvals have been obtained.

3.9.3 Completion and Making Good

Works must be complete only when they are fit for their intended purpose, fully compliant with the Contract, and accepted by the Principal acting through the Superintendent.

The Contractor must make good all damage caused by construction activities and leave the Site clean, safe and fit for use.

3.10 External & Site Works

The Contractor must carry out all external works necessary to complete the Works in accordance with the Contract, including the Architectural Specification, drawings and referenced standards.

External works include, without limitation:

1. Site preparation, earthworks and regrading within the defined Site battery limits;
2. Stormwater drainage works and integration with existing drainage systems;
3. External pavements, footpaths, ramps, stairs and access ways;
4. Landscaping works, including planting, turf, garden beds and hardscape elements;
5. External fencing, gates and barriers;
6. External service trenches, pits, ducting and reinstatement associated with building services; and
7. External plant areas, plinths and enclosures.

External works must be executed to achieve documented levels, falls, tolerances and performance requirements, while maintaining safe access and minimising disruption to Site operations.

On completion, all disturbed areas must be reinstated, temporary works removed, and the Site left clean, safe and fit for use.

External works are deemed complete only when accepted by the Superintendent.

3.11 Testing, Commissioning & Handover

Commissioning must demonstrate not only compliance with technical requirements but that the Works are operationally ready for occupation, use and maintenance by the Principal.

Practical Completion will not be achieved unless the Works are capable of being operated safely and effectively in accordance with their intended purpose.

3.11.1 Testing and Verification

The Contractor must:

1. Carry out all inspections, tests and verifications required by the Contract, Specifications, Drawings, Australian Standards and statutory authorities;
2. Ensure testing is performed by suitably qualified and competent personnel;
3. Coordinate witness and hold points with the Superintendent in accordance with approved Inspection and Test Plans (ITPs); and
4. Rectify all defects, non-conformances or deficiencies identified during testing prior to re-testing.

No system or element of the Works shall be placed into service or concealed until all required inspections and tests have been completed and accepted.

3.11.2 Commissioning Execution

Commissioning must be undertaken in a structured and staged manner to demonstrate:

1. correct installation and operation of individual systems;
2. integrated performance of interfacing systems;
3. compliance with performance, safety, environmental and statutory requirements; and
4. readiness for occupation, operation and maintenance.

Commissioning records, test results and certifications must be progressively compiled and submitted as part of the Manufacturer's Data Reports (MDRs).

3.11.3 Handover and Practical Completion

Prior to requesting Practical Completion, the Contractor must:

1. complete all required testing and commissioning activities;
2. ensure all systems are operational, safe and compliant;
3. provide all documentation necessary for the use, operation and maintenance of the Works, including as-built drawings, test certificates, warranties and O&M manuals in accordance with the SDRL;
4. complete a joint inspection and walkthrough with the Principal (acting through the Superintendent); and
5. to identify any outstanding defects or punch list items.

Practical Completion will not be achieved until all requirements of testing, commissioning and handover have been satisfied to the Superintendent's acceptance.

3.11.4 Training

The Contractor must provide training for the Principal's nominated personnel in the operation, control, routine maintenance and emergency procedures for all relevant systems and equipment. Training must be coordinated with commissioning activities and supported by appropriate training materials and manuals.

3.11.5 Defects and Close-Out

Any defects or omissions identified during commissioning, handover or the Defects Liability Period must be rectified promptly in accordance with the Contract.

Defects and punch list management is to be proposed by the Contractor and agreed to by the Principal.

Final close-out documentation must reflect the completed Works and incorporate all approved changes arising from commissioning and defect rectification.

The Contractor's obligations in relation to fitness for purpose, design responsibility and performance of the Works survive Practical Completion and the issue of any certificate under the Contract.

3.12 Demobilisation

The Contractor must, upon achieving Practical Completion (or earlier if directed), fully demobilise from the Site in an orderly, safe, and timely manner.

Demobilisation must include, as a minimum, the following:

3.12.1 Removal of Temporary Works and Plant

Remove all Temporary Works, construction plant, equipment, scaffolding, hoardings, site offices, amenities, temporary services, signage, and surplus materials from the Site, unless otherwise directed by the Principal (acting through the Superintendent).

3.12.2 Make-Good and Reinstatement

Reinstate all affected areas to their original or specified condition, including surfaces, finishes, landscaping, pavements, roads, and existing services impacted by the Works. Repair any damage attributable to the Contractor's activities at no additional cost.

3.12.3 Cleaning and Waste Removal

Complete final cleaning of all work areas and adjoining affected areas. Remove all waste, debris, excess materials, and hazardous substances from the Site and dispose of them lawfully off-site.

3.12.4 Services and Temporary Connections

Isolate, disconnect, and remove all temporary service connections (power, water, data, drainage, etc.). Confirm permanent services are operational, compliant, and left in a safe condition.

3.12.5 Handover and Access Clearance

Return all keys, passes, permits, security credentials, and access devices issued to the Contractor. Clear all laydown and storage areas and surrender possession of the Site in accordance with the Contract.

3.12.6 Documentation and Close-Out

Prior to final demobilisation, submit all required close-out documentation, including as-built records, warranties, test results, certifications, and operation and maintenance information, as required under the Contract.

3.12.7 Safety and Compliance

Demobilisation activities must comply with all WHS, environmental, and site-specific requirements. The Site must be left in a safe, secure, and hazard-free condition.

4.0 Works Excluded

The Contractor's scope does not include the following, unless expressly stated or varied otherwise:

1. Audio Visual systems supplied under a separate contractor engaged by the Principal. The Contractor must give not less than three (3) weeks' written notice to the Principal and Superintendent of any requirement for Audio Visual works to occur on Site and must ensure all prerequisite works, access and readiness are complete;
2. Works explicitly identified outside of WUC;
3. Future parking works beyond the defined site boundary; and
4. Isolation of services within Stanwell Power Station boundary.

4.1.1 Interfaces with Principal-Engaged Contractors

Where elements of the Works interface with works performed by separate Principal-engaged contractors (including Audio Visual systems), the Contractor must allow for and provide all reasonably foreseeable provisions necessary to facilitate those interfaces, including but not limited to penetrations, sleeves, conduits, cable trays, fixings, supports, access, coordination, sequencing and protection.

5.0 Design Responsibility

The Contractor is responsible for all design necessary to execute and complete the Works, including any design development, detailing, coordination and certification required to satisfy the Contract, the Architectural Specification, the Drawings and all statutory requirements.

1. Completing and, where necessary, developing and documenting all design beyond the Principal's concept / documented design to the level required for construction (including shop drawings, setting out information, coordination models and installation details);
2. All Contractor-designed elements (including temporary works, off-site fabricated components, structural connections, penetrations, supports, interfaces and any delegated design), and ensuring such design is fit for purpose and constructible;
3. All performance solutions (if proposed or required) including development, documentation, consultation, evidence, certification and approvals, and integration into the WUC. This includes, without limitation, performance solutions relating to:
 - a. Façade and building envelope systems (including weatherproofing, thermal performance, condensation control, acoustic performance and structural adequacy);
 - b. Roof water drainage and stormwater performance, including box gutters, overflows and discharge arrangements; and
 - c. Building access, maintenance and safety systems (including roof access, fall prevention and safe access provisions).
4. Coordination of all design disciplines and interfaces (architectural, structural, civil, mechanical, electrical, hydraulic, fire and communications), including clash resolution, integrated detailing, and ensuring all elements are compatible, buildable and meet performance requirements; and
5. Obtaining and providing all required design certifications, approvals and supporting records, including (where applicable) Queensland Form 15 and Form 12, and any other producer statements, certificates, test reports and documentation necessary to demonstrate compliance.

6.0 Authority Approvals & Fees

Unless expressly stated otherwise the Contractor is responsible for obtaining all authority approvals, permits, inspections, and certifications.

The Contractor must provision for all associated fees, including plumbing and drainage authority charges.

Prior approvals listed in the contract documents are provided by the Principal only where explicitly identified.

7.0 Project Management

7.1 General

The Contractor must provide all resources, including personnel, tools and systems to actively manage and report on activities required to deliver the WUC throughout the various phases of the WUC.

The Contractor must provide all deliverables listed in [Appendix B – Supplier Deliverable Requirement List \(SDRL\)](#) in accordance with the specified timeframes within same.

7.2 Management Plans

The Contractor's deliverables including a number of management plans are detailed in the SDRL.

All management plans must be developed specifically for this WUC and identify and explain key management strategies for the delivery of the Project.

The management plans are submitted for review and acceptance without relieving the Contractor, as Principal Contractor, of any statutory responsibility for the planning or execution of the WUC.

7.2.1 Project Execution Plan

The Contractor's Project Execution Plan (PEP) is the highest-level document which defines the project specific management structure and resources as well as the principles, processes, procedures, systems, tools and templates to be implemented for use throughout the Project.

The PEP is to refer to related subordinate function management plans (where these are required under the SDRL) and must include a document map showing all related subordinate management plans.

The PEP may contain the following information as a minimum:

6. Project organisation and responsibilities including organisation chart;
7. HSE management;
8. Quality management;
9. Risk management;
10. Engineering management;
11. Procurement, fabrication and subcontracting;
12. Project services and controls;
13. Materials management;
14. Construction management;
15. Commissioning;
16. Project Information Management; and
17. Project Closeout.

7.2.2 Construction Management Plan

The Construction Management Plan (CMP) is a subordinate plan of the PEP and outlines the Contractor's delivery of the onsite related portion of the scope.

As a condition to receiving approval to mobilise to Site, the Contractor must submit a detailed CMP to the Principal for approval by the Principal's Representative.

If not already incorporated in the PEP, the CMP may contain the following information:

1. Project organisational structure for Site activities, including key roles and responsibilities;
2. Mobilisation / demobilisation plan;
3. Rosters, working time and travel arrangements:
 - a. The rosters, work times and travel arrangements must be developed to comply with the Company's fitness for work and fatigue management policies;
 - b. Industrial relations; and
 - c. Duty of care including end of roster travel arrangements must be clearly outlined.
4. Survey investigations, verification and reporting;
5. Materials management;
6. Interface management;
7. Contractor and vendor management;

8. Transport and logistics;
9. Lift plan – Major lift’s required during construction:
 - a. Any crane-based works (including size and estimated durations required onsite for each crane);
 - b. Lift studies (where required by the SHMS);
 - c. The Contractor must develop detailed lift plans at the completion of lift studies; and
 - d. The Contractor must specify the requirements for the crane lifting pads (where applicable).
10. Contractor productivity management and reporting:
 - a. Reporting must include all subcontractor and supplier reporting requirements.
11. Plant and equipment requirements;
12. Construction methodology:
 - a. Work packages;
 - b. Execution methodology;
 - c. Site Acceptance Testing, Hold Points;
 - d. Construction sequencing and its alignment with the requirements of the granted shutdown windows;
 - e. Method of protection of existing buried services during construction;
 - f. Installation of conduit and cables methodology (including cable ladders and cable support structures);
 - g. System integration works;
 - h. Permits;
 - i. Isolations;
 - j. Work methodologies;
 - k. Operational approvals;
 - l. Site notifications; and
 - m. Risk assessments.
13. Completions; and
14. Demobilisation.

7.2.3 Commissioning Plan

The Contractor must prepare, maintain and implement a Commissioning Plan covering all building systems and services, including architectural, structural, mechanical, electrical, hydraulic, fire, communications and integrated systems.

The Commissioning Plan shall be developed to the level of detail known at the time it is written. It must be revised as further detail becomes available.

The Commissioning Plan must identify and detail the following:

1. Project objectives;
2. Scope of commissioning works;
3. The commissioning team and their roles and responsibilities;
4. Commissioning requirements (process, documentation and technical);
5. The commissioning process and activities, including:
 - a. general commissioning sequence (including building tuning);
 - b. commissioning methodologies;
 - c. commissioning procedures;
 - d. witnessing of testing process;
 - e. monitoring, communication and reporting;
 - f. system dependencies and interactions; and

- g. commissioning issues and the defects management process, including the identification of priority of the defect, non-conformance or issue.
- 6. Commissioning program;
- 7. If not detailed within other management plans for the project, the Commissioning Plan must include;
 - a. the documentation review and acceptance process;
 - b. client/operator training requirements and process;
 - c. operation and maintenance manuals requirements, including structure and delivery method; and
 - d. the completions process.

7.3 Project Information Management

The Contractor, in its role as Principal Contractor, is solely responsible for the establishment, implementation and ongoing management of project document control for the duration of the WUC.

The Contractor must:

- 1. establish and maintain a document control system suitable for the management of all project documentation, including correspondence, drawings, calculations, schedules, registers, certifications, reports and records required under the Contract;
- 2. ensure all documents are uniquely identified, version-controlled, reviewed, approved and distributed in accordance with agreed workflows and Superintendent's directions;
- 3. manage all drawing control, including revisions, superseded documents and drawing change records, such that only current, approved documents are used for the execution of the Works;
- 4. ensure all documents generated by Subcontractors and Suppliers comply with the document control requirements of this Scope of Work; and
- 5. maintain complete, accurate and auditable records sufficient to demonstrate compliance with the Contract, statutory requirements and quality obligations.

The Contractor must compile documentation progressively throughout execution of the WUC and must provide all required documents and records at the times specified in the Contract and the SDRL.

At completion of the Works and as a precondition to Practical Completion, the Contractor must handover the complete, controlled project document set (including As-Built documentation) to the Principal in the formats specified in the Contract.

7.3.1 Document Submission

Document submissions shall include transmittal notice clearly noting the relevant Contract / Purchase Order number, person to issue to, person(s) to copy to, Document number(s), revision(s) and title(s), quantity, size, transmittal medium, and the reason for issue.

Contractor must supply required metadata for documents and drawings.

7.4 As Built Requirements

The Contractor must prepare, maintain and deliver complete, accurate and certified As-Built documentation reflecting the Works as constructed. As-Built documentation forms part of the Works and is a mandatory requirement for Practical Completion and final handover.

7.4.1 As-Built Drawings

The Contractor must:

1. Maintain a full set of construction drawings marked up progressively to record all approved changes, deviations and final installed conditions;
2. Clearly identify all approved deviations from Issued-For-Construction (IFC) drawings;
3. Ensure all dimensions, levels, coordinates and service locations reflect the Works as constructed; and
4. Certify each As-Built drawing as complete, dated and signed by the Contractor and the Principal's Representative.

As-Built drawings must be provided:

5. In signed PDF format;
6. In native editable file format, consistent with the original design platform; and
7. All drawings are to be on the Principal's template.

Electronic As-Built Data

Where As-Built information is maintained electronically:

1. As-Built data must be stored in clearly identifiable layers or revision structures;
2. File naming, revision control and metadata must align with the project document control requirements; and
3. Electronic As-Built records must be organised into logical, discipline-based folders suitable for transmission and long-term asset management.

Buried Services and Hidden Works

The Contractor must:

1. capture all buried, concealed or underground services installed, modified or made redundant as part of the Works;
2. Update buried services records within five (5) days of any change; and
3. Ensure locations, depths, alignments and reference points are accurately recorded and verifiable.

Certification and Supporting Records

As-Built documentation must be supported by:

1. Form 12 and Form 15 certifications (where applicable);
2. Test results, inspection records and commissioning data relevant to the installed systems; and
3. Approved design changes, DCRs and variation documentation impacting the final Works.

Timing and Handover

As-Built documentation must be:

1. compiled progressively during execution of the Works;
2. Submitted in accordance with the SDRL milestones;
3. Fully complete, reviewed and accepted prior to the achievement of Practical Completion; and
4. Incorporated into the final Manufacturer's Data Report (MDR) and handover package.

7.4.2 Calculations

Calculations provided by the Contractor to the Superintendent must be presented in a clear, concise and legible format. Calculations must be set out in such a way as to be readily followed and understood by other suitably qualified professionals.

All calculations must be submitted electronically in PDF format as per timelines detailed in the in SDRL. Each calculation must detail the software package and version, and design criteria upon which the calculation was performed.

Additionally, all assumptions made in performing the calculation must be noted. Where calculations relate to a specific drawing or drawings, the calculations must be indexed to those drawings, and the drawings shall be submitted with the calculation.

On completion of the Works, the Contractor shall provide a full set of all relevant calculations certified As-Built.

Any modelling and calculations using software shall be submitted to the Superintendent in their native format, unless otherwise request by the Superintendent.

7.4.3 Manuals

Manuals may be compiled using Original Equipment Manufacturer (OEM) documentation, Supplier created documentation, or a combination of these two.

These manuals must specify operational and maintenance requirements for all equipment and specify recommended spares strategy for the operation of the equipment.

Manuals shall be provided in both hard and electronic copy in accordance with the timelines detailed in the SDRL.

The Contractor shall supply replacement drawings in as-Built status for manuals containing drawings where the drawings have been as-Built subsequent to issue of the manual.

Technical illustrations or photographs used in technical manuals shall be supplied in their native file format and as .JPEG files in a separate folder.

8.0 Reporting and Programming Requirements

8.1 Contract Program

The Contractor must, within 20 Business Days of the Date of Contract, submit to the Superintendent a Program for the execution of the WUC in accordance with clause 32 (Programming) of the Contract.

The Program must:

1. Be provided in the native scheduling file format approved by the Principal and in PDF format;
2. Be resource-loaded, identifying major commodity quantities and all direct hours required to execute the WUC; and
3. Be developed in accordance with the Contract, including the Scope of Work and any Superintendent's direction.

The Program must reflect the Contractor's execution methodology and be accompanied by a narrative which must:

1. Describe the construction methodology in a logical and sequential manner;
2. Identify the materials, equipment and labour resources proposed to complete the WUC;
3. Identify all major and intermediate milestones, including interface milestones;
4. Describe the basis of assumptions, qualifications, durations, logic, sequencing and resource loading; and
5. Identify the critical path(s) for the WUC.

Unless otherwise approved by the Superintendent:

1. Activities must not exceed 30 days' duration;
2. Negative lags are not permitted; and
3. Mandatory constraints must not be used.

Upon acceptance by the Superintendent, the Program will constitute the Baseline Program for the purposes of monitoring progress under clauses 32 and 34 of the Contract.

The Contractor must update and resubmit the Program and Program narrative monthly, or at such other times as directed by the Superintendent and present the updated Program at the monthly progress meeting.

Each Program update must:

1. Reference the approved Baseline Program;
2. State the data date;
3. Include progress and commodity curves comparing planned, actual and forecast progress;
4. Include an equipment plan identifying type and quantity of equipment;
5. Include a critical path analysis and identification of impacts and mitigation measures;
6. Identify major and interface milestones with variance analysis;
7. Include procurement and fabrication activities, including transport to Site;
8. Include mobilisation and temporary works activities; and
9. Separately identify and code Principal-related interface activities.

If the Contractor proposes any amendment to logic or duration affecting the critical path, the Contractor must submit a revised Program narrative and variance analysis explaining the change and its impact on time and sequence.

8.2 Commodity Curves

The Contractor must prepare and submit commodity curves (S-curves) for major commodities, or such other commodities as directed by the Superintendent.

Commodity curves must:

1. Show planned, actual and forecast quantities over time;
2. Display both incremental and cumulative progress;
3. Include tabulated quantities, production rates and peak values; and
4. Align with the Program and Program Narrative.

Commodity curves must be updated weekly and submitted with the weekly report. Progress will be assessed against the planned quantities stated in the approved Program.

8.3 90-Day Lookahead schedule

The Contractor must submit a 90-day lookahead schedule covering the initial execution period or any other period directed by the Superintendent.

The 90-day lookahead schedule:

1. Must detail mobilisation, preparatory works and temporary works;
2. Will operate as an interim working schedule until acceptance of the Baseline Program; and
3. May be submitted in Excel format unless otherwise directed.

8.4 Monthly Status Report

The Contractor must submit a monthly status report documenting cost and schedule performance for the reporting period.

The report must:

1. Adopt a data date at the end of the reporting period (or as directed);
2. Include an overall WUC progress curve showing planned, actual and forecast progress;
3. Include discipline-based progress curves (Engineering, Procurement, Construction as applicable); and
4. Include a variance analysis explaining deviations from plan.

The monthly status report must include, as a minimum:

1. Cover Page (Project name, package details, Contractor, reporting period);
2. HSE Performance Summary, including incidents and corrective actions as per HSE-PROC-18;
3. Updated Program, submitted in PDF and native format, with narrative;
4. Critical Path Analysis, including changes from baseline;
5. Overall Progress Chart (% complete) supported by discipline weightings;
6. Updated Monthly Commodity Curves;
7. Delay and recovery narrative, including proposed mitigation;
8. Manpower gram, including headcount and man-hours by discipline;
9. Milestone comparison table (planned vs actual/forecast);
10. Cost report, including actuals, forecast to completion, approved variations and potential variations;
11. Cost and schedule risks and opportunities register;
12. Engineering Status Report (ESR), aligned to agreed rules of credit;
13. Procurement Status Report (PSR), aligned to purchase order control points; and
14. Quality Status Report, including QC inspections and NCR status.

8.5 Weekly & Daily Reports / Meetings

8.5.1 Contractor's Weekly Dashboard

The Contractor must submit a weekly dashboard presenting:

1. Safety statistics;
2. Commodity curves (12-week lookahead);
3. Overall earned-hours progress;
4. Performance factor (spent vs earned);
5. Manpower curves; and
6. Absenteeism statistics.

Material variances must be explained together with recovery actions.

8.5.2 Daily reports

The Contractor must prepare and submit a daily report before 10am each day for the Services performed the previous day.

Daily reports must be accurate, complete, and provided in the format and by the time nominated by the Principal (or its Representative).

As a minimum, each daily report must include:

1. date and reporting period;
2. work performed and progress against the program;
3. labour and supervision on site (including subcontractors) and hours worked;
4. plant and equipment used;
5. materials delivered and used;
6. location(s) of work and access constraints;
7. safety matters, incidents, hazards identified and controls implemented;
8. quality inspections/tests undertaken and nonconformances identified;
9. delays, disruptions, variations, and any causes of lost time (including weather conditions) and their impact;
10. interfaces with the Principal and other contractors; and
11. photographs and sketches where requested or where they assist in recording progress or conditions.

The Contractor must retain supporting records for the information reported (including timesheets, delivery dockets and plant records) and make them available to the Principal on request.

Submission of a daily report does not relieve the Contractor of any obligation under the Contract, and does not constitute acceptance of the reported matters by the Principal.

If the Contractor fails to submit a daily report in accordance with this clause, the Principal may direct the Contractor to provide the report and/or provide additional supporting information, and the Principal may maintain its own records; however, the Principal's records do not relieve the Contractor of responsibility for accurate reporting.

8.5.3 Weekly Progress Meeting

The Contractor must attend and support a weekly progress meeting and submit a weekly progress pack addressing safety, quality, engineering, procurement and construction status, including interface risks.

The Contractor is to provision for taking and maintaining meeting minutes.

Meeting minutes are to be made available to the Superintendent and Principal for review no later than 24 hours after the occurrence meeting. Final copies are to be available no less than 48 hours prior to the next meeting or as instructed by the Principal.

8.5.4 Three-Week Lookahead Schedule

The Contractor must submit a three-week lookahead schedule at a level of detail suitable for supervisory execution, including:

1. Prior week actuals;

2. Three-week forecast quantities and hours;
3. Identified engineering or procurement constraints; and
4. Any upcoming inspection obligations including hold points etc.

9.0 Health, Safety and Environment

The Contractor, in its capacity as Principal Contractor, is solely responsible for planning, managing and coordinating health, safety and environmental matters for the Works in accordance with the Contract, applicable WHS and environmental legislation, and the Principal's site requirements.

The Contractor must implement and maintain appropriate HSE systems, including risk assessments and SWMS, ensure all personnel are suitably inducted, trained and supervised, and coordinate subcontractors and interfaces to protect workers, occupants and adjacent operations.

The Site shall be always maintained in a safe condition, with effective control of access, noise, dust, hazardous substances and waste. All incidents and environmental events must be promptly reported and managed.

10.0 Quality Management System

The Contractor must maintain a Quality Management System that complies with all the requirements of AS/NZS ISO 9001 – 2016 ("ISO-9001") and the Principal's requirements.

A Quality Management Plan must be developed and submitted for Principal review and approval prior to mobilisation to Site.

Throughout the Project, the Contractor must ensure that they are working in compliance with the approved Quality Management Plan.

The Contractor must utilise their proprietary quality assurance processes and documents to capture the completions records associated with the Works.

The Contractor must submit to the Principal, a framework structure of the completion's documentation for review and endorsement prior to commencing Works. The submission must detail how the quality records are managed including the use of the testing and commissioning records.

The completions framework and supporting documentation must be arranged to support the progressive access and beneficial use of the Works by the Principal.

If required, the Contractor is to provide access to all necessary quality documentation to support the safe operation of the works during the beneficial use period. Final versions of the completion's documentation must be included in the Contractors MDR.

All testing and inspection data must be recorded progressively on the approved quality control check sheets and in a timely manner during the Contract. All reports prepared as part of the WUC must be prepared and submitted in a timely manner so as not to impede the progress of the WUC.

The following documents must be provided to permit audit and surveillance of the Contractor's quality system during the Scope of Works:

1. Quality Plan;
2. Inspection and Test Plan (ITP);
3. Quality Assurance and Quality Control Records; and
4. Manufacturing Data Reports (MDR).

The Contractor must perform all testing as specified in the referenced standards, specifications and in the drawings.

The Contractor must demonstrate through quality records that all requirements under this Contract have been achieved.

The Contractor must have or provide appropriately qualified and experienced persons to carry out inspections and testing activities.

The Contractor shall make available any information associated with its Quality Management System to the Principal on request (e.g. ITPs or material testing results).

The Contractor must be responsible for all Quality Assurance (QA) and Quality Control (QC) activities for the Project. This includes all inspection activities and the collation of all quality documentation to verify that the Works are completed and tested in accordance with this Scope of Work and referenced specifications and drawings.

The Principal reserves the right to inspect all materials and equipment during both offsite fabrication works and onsite construction and assembly activities.

10.1 Quality Plan

The Contractor must develop and implement a project specific Quality Management Plan (QMP) pursuant to the requirements of the approved PEP.

The plan must define the documented quality management system (QMS) to be applied by the Contractor throughout the performance of the Services, in accordance with the requirements of the Contract.

The scope of the QMP must cover the Quality Assurance and Quality Control (QA/QC) requirements for the Execution phase.

The Contractor and its Subcontractors must operate under a QMP, which meets the requirements of AS/NZS ISO 10005:2016 Quality Management Systems – Guidelines for Quality Plans.

The QMP must remain fully implemented and maintained throughout the Project duration.

The Contractor's QMP shall define how its QMS will be configured, implemented, resourced and verified in order to realise the specified quality objectives.

The QMP must be provided to the Principal for review and acceptance prior to the commencement of any Works.

The QMP may contain, as agreed with the Principal:

1. Description of the WUC;
2. Quality Policy Statement identifying the Contractor's approach and commitment to Quality Management;
3. Quality objectives that are specific and measurable;
4. Project communication matrix and reporting requirements;
5. Organisational roles, responsibilities and authorities of key staff;
6. Organisation chart showing the various positions and their inter-relations;
7. Risk management, including any identified quality risks and mitigation actions;
8. Procurement management;
9. Description of how Subcontractors are to be selected, awarded and continuity of evaluation;

10. List of approved Subcontractors and their scopes of the subcontracted WUC;
11. List of related standards & procedures;
12. Management of change including scope, design, development and technical queries;
13. Verification and validation activities and certification;
14. Register of inspection and test plans (ITPs);
15. Nonconformities management;
16. Management of sourced and Free Issue materials and equipment;
17. Preservation and packaging of product, equipment protection, storage and handling;
18. Contractor's internal audit schedule and Contractor's Supplier audit schedule;
19. Management reviews; and
20. Procedure for documents and records management, including MDR management.

10.2 Inspection and Test Plans

Inspection and Test Plans (ITPs) templates must be issued to the Superintendent for endorsement at least three (3) weeks prior to the programmed commencement date.

No works must commence prior to Principal review and endorsement of the ITP templates.

The ITP must identify those activities where inspection, testing and verification is deemed necessary by the Contractor and Superintendent to prevent the WUC progressing beyond a point where failure to implement such control may prejudice the integrity of the Works.

The Contractor shall supply an ITR matrix of all Works.

ITPs may contain, as agreed with the Principal:

1. Identification of tests / inspections against specific requirements of the Contract;
2. Hold points and witness points;
3. The identification of records to be maintained;
4. Details of test equipment to be used; and
5. The Contractor and Principal progressively at agreed Hold and Witness points shall sign off ITPs. If Subcontractors are to be used, the main Contractor is wholly responsible for the WUC carried out by those Subcontractors.

Example activities and verifying documentation are included in Table 6 below.

Example Activity	Example Verifying Documentation
Preparation of drawings and documentation	Documents submitted to Company for review and comment.
Document control	Documents submitted to Company for review and comment.
Procurement of materials to be incorporated into the permanent works	Material test certificates, material analysis reports, heat numbers, NDT Reports (e.g. testing for laminations), certificates of compliance and certificates for weld consumables.
Weld procedures and weld qualifications	Weld procedures (for both prequalified and qualified welds) and associated NATA reports for qualified weld procedures.
Welder qualifications	Register of welders, welder testing records, and associated NATA reports for welder qualifications.
Assembly of components for fabrication	Dimensional and set-up quality control check sheets (completed and signed).

Welding (including pre-weld, welding and post weld activities)	Weld maps, pre and post weld dimensional check sheets, welder and weld traceability register, preheat, post weld heat treatment, completed and signed check sheets.
Stress relieving (if required)	Post weld heat treatment reports.
NDT inspections	Weld inspections and testing, associated NATA reports.
Machining	Machining register, machining tolerance and surface finish reports.
Dimensional and tolerance checks	Dimensional and tolerance validation report, compliance certificates.
Trial Assembly	Trial assembly reports and completed and signed check sheets.
Protective treatment preparation	Protective Treatment materials batch numbers, completed and signed check sheets for blasting and other preparation.
Protective treatment (including pre, during and post protective treatment application)	Completed and signed check sheets for application of protective treatment and curing, visual and dry film thickness measurement reports.
Non-conformances and corrective actions	Non-Conformance Reports (NCR's) and Corrective Action Reports (CAR's).
Final Inspection	Final Inspection Report.

The Principal will review the ITP's, insert hold points and witness points as required and return them to the Contractor within seven (7) days of receiving the ITP's.

For the purposes of this section, the following definitions apply:

1. Hold Points means a position in the production and inspection cycle beyond which WUC must not proceed without mandatory verification and acceptance by the Superintendent; and
2. Witness Points means a position in the production and inspection cycle where the option of attendance for the purposes of verification and acceptance may be exercised by the Superintendent.

The Contractor must give the Superintendent a minimum of seven (7) working days' notice of a forthcoming Hold or Witness Point.

All completed construction ITPs must be submitted to the Principal in the agreed format.

Proceeding past a Hold Point without the Principal's written approval shall constitute a non-conformance.

10.3 Requests for Information (RFI)

Requests for information are to be submitted in a format mutually agreed between the Contractor and the Principal.

10.4 Non-Conformances

The Contractor's Quality Plan must include a procedure for the management and control of non-conforming elements or processes for the WUC.

Any non-conforming components must not be covered up nor be further incorporated into the goods in unless the non-conformance has been rectified.

A notice of any non-conformance must be provided to the Principal 24 hours after the issue being identified. Failure to comply with this will constitute a non-conformance.

Any items found to be non-conforming must be removed by the Contractor at the Contractor's expense.

10.5 Quality Audits

The Principal may choose to carry out ad-hoc quality audits of the Contractor and/or its Subcontractors during the Project after giving the Contractor a minimum of three (3) working days' notice.

The Contractor must provide full access to the relevant facilities and must ensure full cooperation for these audits.

The Principal may engage specialist consultants and/or inspection agencies on its' behalf to perform the audits, quality assurance surveillance, inspections, checks and/or tests.

10.6 Manufacturers Data Report

Quality records must be maintained and supplied as part of a Manufacturer's Data Report (MDR).

A proposed MDR Index and method of management must be provided to the Principal for review and acceptance within four (4) weeks of contract award.

MDR contents must be collated, reviewed and compiled progressively by the Contractor.

Manufactured items delivered to Site for permanent installation and/or use must be supplied with either an approved MDR report or all records accepted by the Principal.

The following Manufacturer Data Reports (MDRs) must be submitted progressively and upon completion, as part of the quality assurance and handover process:

1. Design calculations and certifications (structural and mechanical);
2. Fabrication drawings and as-built drawings;
3. Welding procedures and welder qualifications;
4. Material test certificates (MTCs) for structural steel and liners;
5. Inspection and test plans (ITPs) and associated records;
6. Non-destructive testing (NDT) reports;
7. Coating and corrosion protection records;
8. Lifting and rigging plans;
9. Commissioning and functional test reports; and
10. O&M manuals and warranty documentation.

All MDRs must be compiled in accordance with the project's document control procedures and submitted for review and approval prior to commissioning.

11.0 General Site Requirements

11.1 Fitness for Work

The Contractor is to incorporate Principal's policies into their HSE plan for the Project.

11.2 Standard Work Hours

1. Working days: 7 days per week;
2. Working hours: 06:00hrs to 18:00hrs each working day; and

3. Delivery Times: Deliveries should be avoided during operation shift start and end periods, these are between 06:30hrs to 07:30hrs and 16:00hrs to 17:00hrs Monday to Friday.

12.0 Abbreviations and Definitions

Capitalised terms used in this Scope of Work have the same meaning as defined in the Contract, unless expressly stated otherwise.

Abbreviations used within this document are:

Abbrev.	Meaning
AS	Australian Standard
AS 4000	AS 4000 – General Conditions of Contract
AV	Audio Visual
BOM	Bureau of Meteorology
BCA	Building Code of Australia (now NCC)
CAR	Corrective Action Report
CEMP	Construction Environmental Management Plan
CMP	Construction Management Plan
DCR	Design Change Request
DFT	Dry Film Thickness
DLP	Defects Liability Period
DOC	Document (Document Control Reference)
EHS / HSE	Environment, Health and Safety
EV	Earned Value
FAT	Factory Acceptance Test
FC	Final Certificate
IFC	Issued for Construction
ITP	Inspection and Test Plan
ITR / ITC	Inspection and Test Record / Inspection Test Checksheet
JSEA	Job Safety and Environmental Analysis
KPI	Key Performance Indicator
LUNR	Stanwell Drawing Management System
MDR	Manufacturer's Data Report
MoM	Method of Measure
NCC	National Construction Code
NCR	Non-Conformance Report
NDT	Non-Destructive Testing
O&M	Operations and Maintenance
OEM	Original Equipment Manufacturer
OWP	Operational Works Permit
PC	Principal Contractor
PEP	Project Execution Plan
PM	Project Manager
PO	Purchase Order
PQ	Pre-Qualification
PSR	Procurement Status Report
QA	Quality Assurance
QC	Quality Control
QCLC	Queensland Charter for Local Content
QMP	Quality Management Plan

QMS	Quality Management System
QPP	Queensland Procurement Policy
RAG	Red / Amber / Green (status)
RFI	Request for Information
RoC	Rule of Credit
SDRL	Supplier Deliverable Requirement List
SHMS	Site Safety & Health Management System
SOW	Scope of Work
SPI	Schedule Performance Index
SPS	Stanwell Power Station
SWMS	Safe Work Method Statement
TRIFR	Total Recordable Injury Frequency Rate
WBS	Work Breakdown Structure
WHS	Work Health and Safety
WHSMP	Work Health and Safety Management Plan
WUC	Work under the Contract

13.0 Appendices

1. Appendix A - [Reference Drawings and Documents](#);
2. Appendix B - [Supplier Deliverable Requirement List \(SDRL\)](#);
3. Appendix C- [Appendix C – HSE-PROC-18-Principal Contractor](#); and
4. Appendix D - [Hazardous Building Materials Register](#).

14.0 Appendix A – Reference Drawings and Documents

Document Number	Title
Structural	
25052 S1.01	Specification Notes Sheet 1
25052 S1.02	Specification Notes Sheet 2
25052 S1.03	Site and External Works Key Plan
25052 S2.01	Slab/Footing Plan
25052 S2.02	Slab/Footing Details
25052 S3.01	Floor Framing Plan
25052 S3.02	Floor Framing Details Sheet 1
25052 S3.03	Floor Framing Details Sheet 2
25052 S4.01	Lower Roof and Ceiling Framing Plan
25052 S4.02	Roof Framing Plan
25052 S5.01	Framing Elevations Sheet 1
25052 S5.02	Framing Elevations Sheet 2
25052 S6.01	Roof Framing Details Sheet 1
25052 S6.02	Roof Framing Details Sheet 2
25052 S6.03	Roof Framing Details Sheet 3
25052 S7.01	External Slab Plan and Details
25052 S8.01	Generator Area Slab/Footing Plan and Details
25052 S9.01	Hat Stand Slab/Footing Plan and Details
25052 S9.02	Hat Stand Framing Plan and Details
Civil	
25052 C01	SPECIFICATION NOTES
25052 C02	BULK EARTHWORKS PLAN
25052 C03	CIVIL WORKS PLAN
25052 C04	CIVIL DETAILS
25052 C05	EROSION AND SEDIMENT CONTROL PLAN AND DETAILS
25052 C06	CONCRETE PATHWAY LEVELS PLAN
25052 C101	VEHICLE PARKING SPECIFICATION NOTES
25052 C102	VEHICLE PARKING LAYOUT AND LINEMARKING PLAN AND DETAILS
25052 C102	LINEMARKING PLAN AND DETAILS
25052 C103	VEHICLE PARKING CONCRETE SLAB PLAN AND DETAILS AND DETAILS
25052 C104	VEHICLE PARKING EROSION AND SEDIMENT CONTROL PLAN AND DETAILS
Supplementary Documents List	
Acoustic	Acoustic Specification
ESD	Section J – J1V3 Report
Façade	F3P1 Performance Based Design Brief
Façade	Façade Performance Schedules
Façade	Façade Performance Specification
Façade	FP1.4 Document Review

Document Number	Title
Geotech	Geotechnical Investigation Proposed Projects Office
Geotech	Preliminary Contamination Investigation
Hydraulic	Performance Solution - Roofwater Drainage Box Gutter Design
Land Survey	Additional Detail Survey of Part of Stanwell Power Station
Mechanical Services	
M0000	COVER SHEET AND DRAWING LIST
M0001	LEGEND, SCHEDULES, SITE PLAN AND GENERAL NOTES
M0002	STANDARD DETAILS 1 OF 3
M0003	STANDARD DETAILS 2 OF 3
M0004	STANDARD DETAILS 3 OF 3
M1000	LEVEL 0 AIR CONDITIONING AND VENTILATION LAYOUT
M1010	ROOF AIR CONDITIONING AND VENTILATION LAYOUT
M2000	SECTIONS
Landscape	
L0.00	COVER SHEET
L0.01	PLANT SCHEDULE
L0.02	MATERIALS AND FINISHES
L0.03	MATERIALS AND FINISHES
L1.01	EXTERNAL WORKS - GROUND EXTERNAL WORKS - GROUND
L1.02	EXTERNAL WORKS - GROUND
L1.03	EXTERNAL WORKS - GROUND
L1.04	EXTERNAL WORKS - GROUND
L1.05	EXTERNAL WORKS - COURTYARD
L1.06	EXTERNAL WORKS - SITE PLAN
L2.01	LANDSCAPE PLAN - GROUND
L2.02	LANDSCAPE PLAN - GROUND
L2.03	LANDSCAPE PLAN - GROUND
L2.04	LANDSCAPE PLAN - GROUND
L2.05	LANDSCAPE PLAN - COURTYARD
L3.01	SECTION
L3.02	SECTION
L3.03	SECTION
L4.01	DETAILS
L4.02	DETAILS
L4.03	DETAILS
Hydraulic Services	
H0000	COVER SHEET AND DRAWING LIST
H0001	LEGEND, SCHEDULES, SITE PLAN AND GENERAL NOTES
H0002	NOTES
H0003	SCHEDULES
H0010	SITE PLAN
H1000	GROUND FLOOR DRAINAGE SERVICES

Document Number	Title
H1001	ROOF DRAINAGE SERVICES
H2000	GROUND FLOOR WATER & FIRE SERVICES
H4000	GROUND FLOOR FIRE COVERAGE
H6000	GROUND FLOOR DRAINAGE INSET
H6001	GROUND FLOOR WATER INSET
H8000	DIAGRAMMATICS
H9000	DETAILS
Electrical Services	
E0000	COVER SHEET AND DRAWING LIST
E0001	LEGEND OF SYMBOLS AND GENERAL NOTES
E0002	LUMINAIRE SCHEDULE SHEET 1
E0003	LUMINAIRE SCHEDULE SHEET 2
E0005	DEMOLITION PLAN
E0010	ELECTRICAL SITE PLAN
E1000	GROUND FLOOR LIGHTING AND FIRE DETECTION LAYOUT
E2000	GROUND FLOOR POWER, COMMUNICATIONS AND SECURITY LAYOUT
E2001	ROOF POWER, COMMUNICATIONS AND SECURITY LAYOUT
E8000	SCHEMATICS SHEET 1
E8001	SCHEMATICS SHEET 2
E8002	SCHEMATICS SHEET 3
-	ELECTRICAL SERVICES SPECIFICATION
Architectural	
A-000001	TITLE SHEET AND DOCUMENTS SCHEDULE
A-040001	SITE PRECINCT PLAN
A-040002	SITE PLAN - EXISTING + DEMOLITION
A-040003	SITE PLAN - PROPOSED
A-050001	GRID AND SETOUT PLAN
A-060001	AREA PLAN - FECA AND UCA
A-070001	NCC PLAN
A-200001	GENERAL ARRANGEMENT PLAN
A-200002	ROOF PLAN
A-200003	ROOF CAVITY PLAN
A-210001	REFLECTED CEILING PLAN
A-210002	REFLECTED CEILING PLAN - BATTENS
A-220001	WALL TYPES
A-220002	WALL TYPES ROOF CAVITY
A-230001	FLOOR FINISHES PLAN
A-260001	GENERAL ELEVATIONS
A-260002	GENERAL ELEVATIONS
A-270001	GENERAL SECTIONS
A-270002	GENERAL SECTIONS
A-300001	STRUCTURE OUTLINE PLAN

Document Number	Title
A-300002	STRUCTURE OUTLINE SUB-FLOOR PLAN
A-300003	STRUCTURE OUTLINE ROOF PLAN
A-390001	STRUCTURE DETAILS
A-400001	FACADE PLANS & ELEVATION - NORTH
A-400002	FACADE PLANS & ELEVATION - EAST
A-400003	FACADE PLANS & ELEVATION - SOUTH
A-400004	FACADE PLANS & ELEVATION - WEST
A-400101	FACADE ELEVATION - COURTYARD
A-400102	FACADE ELEVATION - ENTRIES
A-410001	FACADE SECTIONS - EAST
A-410002	FACADE SECTIONS - EAST
A-410003	FACADE SECTIONS - NORTH
A-410004	FACADE SECTIONS - WEST + SOUTH
A-410010	FACADE SECTIONS - COURTYARD
A-410011	FACADE SECTIONS - COURTYARD
A-420001	INTERNAL SECTIONS
A-500001	STAIRS 1 & 2
A-500002	WALKWAYS
A-600001	INTERIOR PLAN AND ELEVATIONS - 0.02 - COVERED OUTDOOR
A-600002	INTERIOR PLAN AND ELEVATIONS - 0.04-0.05 - DINING AND KITCHEN
A-600003	INTERIOR PLAN AND ELEVATIONS - 0.06-0.07 SOUTH CIRCULATION AND TRAINING KITCHEN
A-600004	INTERIOR PLAN AND ELEVATIONS - 0.08 - BOARDROOM
A-600005	INTERIOR PLAN AND ELEVATIONS - 0.09 - HEALTH ROOM
A-600006	INTERIOR PLAN AND ELEVATIONS - 0.10 - TRAINING 01
A-600007	INTERIOR PLAN AND ELEVATIONS - 0.11 - TRAINING 02
A-600008	INTERIOR PLAN AND ELEVATIONS - 0.12-0.13 - STORE AND COMMS
A-600009	INTERIOR PLAN AND ELEVATIONS - 0.18 - FIRST AID
A-600010	INTERIOR PLAN AND ELEVATIONS - 0.23-0.26 - WORKSPACE (WEST) AND UTILITY 2
A-600011	INTERIOR PLAN AND ELEVATIONS - 0.23-0.26 - WORKSPACE (WEST) UTILITY 1 AND 2, OFFICE 1
A-600012	INTERIOR PLAN AND ELEVATIONS - 0.27-0.28 MEETING 5 AND MEETING 6
A-600013	INTERIOR PLAN AND ELEVATIONS - 0.29 - WORKSPACE (NORTH)
A-600014	INTERIOR PLAN AND ELEVATIONS - 0.29 - WORKSPACE (NORTH)
A-600015	INTERIOR PLAN AND ELEVATIONS - 0.30-0.31 MEETING 3 AND MEETING 4
A-600016	INTERIOR PLAN AND ELEVATIONS - 0.32-0.34 - MEETING 2, OFFICE AND MEETING 1
A-600017	INTERIOR PLAN AND ELEVATIONS - 0.35 - WORKSPACE (EAST)
A-620001	WET AREA PLAN AND ELEVATIONS - 0.13 - SHOWER
A-620002	WET AREA PLAN AND ELEVATIONS - 0.14 - PWD
A-620003	WET AREA PLAN AND ELEVATIONS - 0.15 FEMALE

Document Number	Title
A-620004	WET AREA PLAN AND ELEVATIONS - 0.16 - MALE
A-710001	PLAN DETAILS - FACADE
A-710005	PLAN DETAILS - COURTYARD & OUTDOOR AREA
A-710010	PLAN DETAILS - INT PARTITIONS
A-720001	SECTION DETAILS - FAÇADE - EXTERNAL
A-720002	SECTION DETAILS - FAÇADE - ENTRIES
A-720005	SECTION DETAILS - FAÇADE - COURTYARD
A-720007	SECTION DETAILS - ROOF
A-720010	SECTION DETAILS - INT FLOOR
A-720011	SECTION DETAILS - INT GLAZED PARTITIONS
A-720012	SECTION DETAILS - INT CEILING
A-730001	DOOR TYPES
A-730002	BATTENS LAYOUT DIAGRAMS
A-760001	ARCHITECTURAL METALWORK - AM-1,2,3,4
A-780001	JOINERY DETAILS
A-780002	JOINERY DETAILS JO-BD-1, 2, 3 & 4
A-780003	JOINERY DETAILS JO-BD-5
A-780004	JOINERY DETAILS JO-BW-1
A-780005	JOINERY DETAILS JO-BW-2
A-780006	JOINERY DETAILS JO-BW-3 & 4
A-780007	JOINERY DETAILS JO-BW-5 & 6
A-780008	JOINERY DETAILS JO-BW-7 & JO-ST-1
A-780009	JOINERY DETAILS JO-BW-8 & 9
A-780010	JOINERY DETAILS JO-SE-1, JO-ST-3 & JO-SE-2
A-780011	JOINERY DETAILS JO-LKR-1
A-780012	JOINERY DETAILS JO-ST-2
A-780015	FURNITURE DETAILS G1-CPD-1B
A-800001	PLANT ROOM
A-810001	HAT STAND
A-910001	DESIGN DEVELOPMENT NOTES
SPEC	ARCHITECTURAL SPECIFICATION
SPEC A	APPENDIX A - T-SHEET
SPEC B	APPENDIX B - WALL SCHEDULE
SPEC C	APPENDIX C - DOOR HARDWARE SCHEDULE
SPEC D	APPENDIX D - WATERPROOFING SPECIFICATION
SPEC E	APPENDIX E - PAINT SPECIFICATION
SPEC F	APPENDIX F - ACOUSTIC SLIDING DOOR SPECIFICATION
SPEC G	APPENDIX G - BUILDING ACCESS SYSTEM
SPEC Y	APPENDIX Y - PRINCIPAL SUPPLIED DOCUMENTS
SPEC Z	APPENDIX Z - SUBSTITUTION REQUEST FORM

15.0 Appendix B – Supplier Deliverable Requirement List (SDRL)

As part of successful completion of the project the Contractor must provide the deliverables set out below, and any other deliverables required under the Contract and as directed by the Principal.

Required Deliverables:

Ref	Deliverable	Document Reference	Phase	Timing	Format
Management & Planning Deliverables					
M-01	Project Execution Plan (PEP)	SOW 4.1; Contract Clause 30	Pre-Mobilisation	10 Business Days prior to mobilisation	PDF
M-02	Construction Management Plan (CMP)	SOW 4.2	Pre-Mobilisation	10 Business Days prior to mobilisation	PDF
M-03	Work Health & Safety Management Plan (WHSMP)	Contract Clause 11; SOW 4.3	Pre-Mobilisation	≤ 10 Business Days from Mobilisation	PDF
M-04	Construction Environmental Management Plan (CEMP)	SOW 4.4	Pre-Mobilisation	≤ 10 Business Days from Mobilisation	PDF
M-05	Commissioning Plan	SOW 4.5	Pre-Commissioning	Prior to commissioning	PDF
M-06	Contract Program (Baseline)	Contract Clause 30	Pre-Mobilisation	≤ 20 Business Days from Contract	Native + PDF
M-07	Monthly Program Updates + Narrative	Contract Clause 30	Construction	Monthly	Native + PDF
M-08	90-Day Lookahead Schedule	SOW 4.6	Construction	Monthly / As Directed	Excel / PDF
M-09	3-Week Lookahead Schedule	SOW 4.6	Construction	Weekly	Excel / PDF
M-10	Procurement Register	SOW 4.7	Construction	Progressive	Excel (Native)
M-11	Risk Register (Project & Construction)	SOW 4.8	All Phases	Progressive	Excel / PDF
M-12	Program Narrative / Basis of Program	Contract Clause 30	Construction	With baseline program	PDF
M-13	Detailed Mobilisation Plan	SOW 4.9	Pre-Mobilisation	10 Business Days prior to mobilisation	PDF
M-14	Project Organisation Chart & Resource Matrix	Contract Clause 8; SOW 4.10	Pre-Mobilisation	10 Business Days prior to mobilisation	PDF
M-15	Interface Management Plan	SOW 4.11	Pre-Mobilisation	10 Business Days prior to mobilisation	PDF

Ref	Deliverable	Document Reference	Phase	Timing	Format
M-16	Variations Register	Contract Clause 36	Construction	Progressive	Excel
M-17	Contractor Personnel Register	Contract Clause 8	Pre-Mobilisation	10 Business Days prior to mobilisation	Excel
M-18	Key Personnel CVs & Qualifications	Contract Clause 8	Pre-Mobilisation	10 Business Days prior to mobilisation	PDF
M-19	Subcontractor Management Plan	Contract Clause 9	Pre-Mobilisation	10 Business Days prior to mobilisation	PDF
M-20	Progress Reports (Monthly)	Contract Clause 30	Construction	Monthly	PDF
M-21	Progress Claims & Supporting Documentation	Contract Clause 37	Construction	Monthly (25th)	PDF + Native
Design & Engineering Deliverables					
D-01	Contractor Design Documents (all disciplines)	Contract Clause 10; SOW 5.1	Design	Prior to IFC	PDF + Native
D-02	Design Calculations (Structural / Services)	Contract Clause 10; SOW 5.2	Design	With Design Submissions	PDF + Native
D-03	Performance Solutions & Certifications	SOW 5.3	Design	Prior to construction	PDF
D-04	Form 15 Certifications	Building Act	Construction	Prior to PC	PDF
D-05	Form 12 As-Built Certifications	Building Act	Close-Out	Prior to PC	PDF
Drawings & Document Control					
DOC-01	Shop Drawings (all trades)	SOW 6.1	Construction	As per ITP	PDF + Native
DOC-02	IFC Drawings	SOW 6.2	Construction	Prior to works	PDF + Native
DOC-03	Drawing Change Requests (DCRs)	SOW 6.3	All Phases	As required	Lunr Workflow
DOC-04	As-Built Drawings	Contract Clause 34; SOW 6.4	Close-Out	Prior to PC	PDF + Native
DOC-05	Buried Services Maps	SOW 6.5	Construction	≤ 5 days from change	PDF + Native
Quality & Inspection Deliverables					
Q-01	Quality Management Plan (QMP)	Contract Clause 29; SOW 7.1	Pre-Mobilisation	10 Business Days prior to mobilisation	PDF
Q-02	ITP Register / Matrix	SOW 7.2	Pre-Construction	Prior to works	PDF

Ref	Deliverable	Document Reference	Phase	Timing	Format
Q-03	Inspection & Test Plans (ITPs)	SOW 7.3	Construction	≥ 3 weeks prior	PDF
Q-04	Inspection & Test Records (ITRs)	SOW 7.4	Construction	Progressive	PDF
Q-05	Non-Conformance Reports (NCRs)	SOW 7.5	Construction	As required	PDF
Q-06	Quality Audit Reports	Contract Clause 29	Construction	As conducted	PDF
Off-Site Fabrication Deliverables					
OF-01	Off-Site Fabrication QA Plan	SOW 8.1	Fabrication	Prior to fabrication	PDF
OF-02	Fabrication ITPs & Records	SOW 8.2	Fabrication	Progressive	PDF
OF-03	Material Traceability Records	SOW 8.3	Fabrication	Progressive	PDF
OF-04	Factory Acceptance Test (FAT) Reports	SOW 8.4	Fabrication	Prior to dispatch	PDF
OF-05	Transport & Handling Plan	SOW 8.5	Fabrication	Prior to dispatch	PDF
Testing & Commissioning Deliverables					
C-01	Commissioning Plan	SOW 9.1	Commissioning	Prior to commissioning	PDF
C-02	Pre-Commissioning Checklists	SOW 9.2	Commissioning	Prior to testing	PDF
C-03	System Test Reports (All Services)	SOW 9.3	Commissioning	Progressive	PDF
C-04	Integrated Systems Test Reports	SOW 9.4	Commissioning	Prior to PC	PDF
C-05	Fire Systems Test & Certifications	SOW 9.5; Building Act	Commissioning	Prior to PC	PDF
C-06	Commissioning Records (Full Set)	SOW 9.6	Commissioning	Progressive	PDF
Handover & Close-Out Deliverables					
H-01	Operations & Maintenance Manuals	Contract Clause 34; SOW 10.1	Close-Out	Prior to PC	PDF + Native
H-02	Asset Registers (Services & Equipment)	SOW 10.2	Close-Out	Prior to PC	Excel
H-03	Warranties & Guarantees	Contract Clause 34; SOW 10.3	Close-Out	Prior to PC	PDF

Ref	Deliverable	Document Reference	Phase	Timing	Format
H-04	Training Materials & Attendance Records	SOW 10.4	Close-Out	Prior to PC	PDF
H-05	Final MDR (Complete Index & Set)	Contract Clause 34; SOW 10.5	Close-Out	Prior to PC	PDF
H-06	Defects / Punch List Closure Evidence	Contract Clause 35; SOW 10.6	Close-Out	Prior to Final Cert	PDF
Security & Insurance Deliverables					
S-01	Unconditional Bank Guarantee (Security)	Contract Clause 5	Pre-Mobilisation	Prior to mobilisation	Original
S-02	Evidence of Insurance (Contract Works)	Contract Clause 18	Pre-Mobilisation	Prior to mobilisation	PDF
S-03	Evidence of Insurance (Public Liability)	Contract Clause 18	Pre-Mobilisation	Prior to mobilisation	PDF
S-04	Evidence of Insurance (Workers Compensation)	Contract Clause 18	Pre-Mobilisation	Prior to mobilisation	PDF
S-05	Evidence of Insurance (Professional Indemnity)	Contract Clause 18	Pre-Mobilisation	Prior to mobilisation	PDF
Work Health & Safety Deliverables					
WHS-01	Safe Work Method Statements (SWMS)	Contract Clause 11; SOW 11.1	Construction	Prior to high-risk works	PDF
WHS-02	Site Safety Induction Records	Contract Clause 11; SOW 11.2	Construction	Progressive	PDF
WHS-03	Incident / Hazard Reports	Contract Clause 11; SOW 11.3	Construction	Within 24 hours of event	PDF
WHS-04	Asbestos Management Plan	Contract Clause 11; SOW 11.4	Pre-Mobilisation	Prior to demolition works	PDF
WHS-05	Traffic Management Plan	SOW 11.5	Pre-Mobilisation	Prior to mobilisation	PDF
Environmental Deliverables					
ENV-01	Waste Management Plan	SOW 12.1	Pre-Mobilisation	10 Business Days prior to mobilisation	PDF
ENV-02	Erosion & Sediment Control Plan	SOW 12.2	Pre-Mobilisation	Prior to earthworks	PDF
Compliance & Approvals Deliverables					

Ref	Deliverable	Document Reference	Phase	Timing	Format
COMP-01	Building Approval / Development Consent	Building Act; SOW 13.1	Design	Prior to construction	PDF
COMP-02	Occupation Certificate	Building Act; Contract Clause 34	Close-Out	Prior to PC	PDF
COMP-03	Compliance Certificates (All Trades)	SOW 13.2	Close-Out	Prior to PC	PDF
COMP-04	Final Inspection Certificate	Building Act	Close-Out	Prior to PC	PDF
Specialist Services Deliverables					
SP-01	Mechanical Services Submissions	SOW 14.1	Design	Prior to installation	PDF + Native
SP-02	Electrical Services Submissions	SOW 14.2	Design	Prior to installation	PDF + Native
SP-03	Hydraulic Services Submissions	SOW 14.3	Design	Prior to installation	PDF + Native
SP-04	Fire Services Submissions	SOW 14.4	Design	Prior to installation	PDF + Native
SP-05	Security & Access Control Submissions	SOW 14.5	Design	Prior to installation	PDF + Native
SP-06	ICT & Data Infrastructure Submissions	SOW 14.6	Design	Prior to installation	PDF + Native
SP-07	Lift Installation Submissions	SOW 14.7	Design	Prior to installation	PDF + Native
Defects Liability Period Deliverables					
DLP-01	Defects Liability Period Inspection Reports	Contract Clause 35	DLP	As scheduled	PDF
DLP-02	Final Defects Rectification Evidence	Contract Clause 35	DLP	Prior to Final Certificate	PDF

Where the Contractor does not provide the above, the Contractor must generate written or other information to the Principal indicating what the Contractor must do, what the Contractor has done, or what needs to be done to meet these requirements.

16.0 Appendix C – HSE-PROC-18-Principal Contractor



stanwell

BUSINESS PROCEDURE

Principal Contractor HSE Requirements HSE-PROC-18



This document applies to:

All Sites



WRITTEN BY: Jayde Smith

ENDORSED/CHECKED BY: Carl Rothman

APPROVED BY: Kriss Ussher

Doc No: HSE-PROC-18

Revision No: 0

Revision Date: 21.08.2024

Page: 1 of 24

THIS DOCUMENT IS UNCONTROLLED IN HARD COPY FORMAT

Table of Contents

1.0	Purpose/Scope	4
2.0	Legislative Requirements	4
3.0	Project HSE Management Plans	4
3.1	HSE Management System	4
3.2	WHS Management Plan	4
3.3	Environmental Management Plan	5
3.4	Management Plan Review	5
4.0	Site Mobilisation.....	5
5.0	Risk Management.....	5
5.1	Risk Appetite	5
5.2	General Risk Management Requirements	7
5.3	Risk Register	7
5.4	Risk Assessment.....	7
5.5	Permit to Work	7
5.6	Electrical Safety	8
5.7	Management of Change.....	Error! Bookmark not defined.
5.8	Safety in Design.....	8
6.0	Leadership and Commitment.....	8
7.0	Induction, Training and Competency	9
7.1	Induction.....	9
7.2	Training and Competency	9
8.0	Subcontractor Management.....	10
9.0	Communication and Consultation.....	10
9.1	Consultation, Cooperation and Coordination	10
9.2	Communication	10
10.0	Facilities and Amenities	10
11.0	Site Security and Access	11
12.0	Health and Wellbeing.....	11
12.1	Health Risk Assessment, Pre-Employment Medicals and Health Monitoring	11
12.2	Fitness for Work.....	11
12.2.1	Alcohol and Other Drugs	11
12.2.2	Fatigue Management	11
12.3	Psychosocial Safety	11
12.4	Rehabilitation and Return to Work	12

13.0	Personal Protective Equipment.....	12
14.0	Incident Reporting and Investigation	12
14.1	Incident Reporting	12
14.2	External Regulator Notification	13
14.3	Investigation	13
15.0	Emergency Management	13
15.1	Emergency Management Plan	13
15.2	First Aid.....	14
16.0	Environmental Management.....	14
16.1	Environmental and Planning Approvals.....	14
16.2	Environmental Authority.....	14
16.3	Land and Vegetation Disturbance	14
16.4	Species Management Program.....	15
16.5	Emissions Reporting.....	15
16.6	Waste Reporting	15
16.7	Sustainability	15
16.8	Cultural Heritage	15
17.0	HSE Performance Reporting.....	16
18.0	Stanwell Governance and Assurance.....	18
19.0	Corrective Action Management	18
20.0	Site Handover.....	19
21.0	Document and Records Management.....	19
22.0	Responsibilities.....	19
22.1	Project Teams	19
22.2	Health, Safety and Environment Team	19
22.3	Principal Contractors	19
23.0	Review, Consultation and Communication.....	19
24.0	References.....	20
25.0	Definitions.....	21
26.0	Revision History	24

1.0 Purpose/Scope

This Business Procedure describes the minimum Health, Safety and Environment (HSE) requirements for a Principal Contractor (PC) engaged by Stanwell Corporation Limited (Stanwell) for a Construction Project.

This Business Procedure applies to all PCs appointed by Stanwell under the Work Health and Safety (WHS) legislation. The Business Procedure must be used by Principal Contractors to support the contractual arrangements to meet Stanwell's HSE requirements.

2.0 Legislative Requirements

The PC must comply with duties as a PC under the *QLD Work Health and Safety Regulation 2011*, which include but are not limited to:

- installation of signage identifying the PC;
- preparation of a Workplace Health and Safety (WHS) Management Plan, before work on the project commences;
- informing all persons of the WHS Management Plan before they commence;
- reviewing the WHS Management Plan and ensuring that each person carrying out construction work is made aware of any revision;
- obtaining copies of Safe Work Method Statements (SWMS) relating to high-risk construction work before the high-risk construction work commences;
- implementing arrangements for ensuring compliance with specified requirements such as facilities and amenities; and
- managing risks associated with construction materials and waste, plant, traffic, and essential services.

The PC must also comply with environmental legislative requirements, as outlined within Section 16 of this Business Procedure.

3.0 Project HSE Management Plans

3.1 HSE Management System

The PC must have, or must develop, a robust HSE management system which complies with the HSE legislation and aligns with *AS/NZS ISO 45001:2018 Occupational Health and Safety Management Systems* and *AS/NZS ISO 14001:2016 Environmental Management Systems*.

3.2 WHS Management Plan

The PC must develop and provide a WHS Management Plan for the project that complies with the *Qld Work Health and Safety Regulation 2011* and demonstrates how the PC will manage project specific health and safety risks.

In developing the WHS Management Plan, the PC must consider the requirements of:

- Acts and Regulations relevant to the scope of work;
- codes of practice, guides, and Australian Standards relevant to the scope of work;
- contractual requirements outlined in the Contract with Stanwell; and
- other requirements outlined within this Business Procedure.

The WHS Management Plan must refer to other related topic specific management plans, such as Traffic Management, Emergency Management, Interface Management, etc.

3.3 Environmental Management Plan

The PC must develop and provide a project specific Construction Environmental Management Plan (CEMP) (or combined HSE Management Plan) based on the requirements of the scope of work, inherent environmental risks and other requirements outlined within this Business Procedure.

In developing the CEMP, the PC must consider the requirements of:

- Acts and Regulations relevant to the scope of work;
- codes, policies, guidelines, and Australian Standards relevant to the scope of work;
- environmental approval obligations (i.e. Environmental Authorities, Species Management Programs, Permits);
- contractual requirements outlined in the Contract with Stanwell; and
- other requirements outlined within this Business Procedure.

The CEMP must refer to other related aspect specific sub-management plans, such as Erosion and Sediment Control, Water Quality Management, Air Quality Management, Noise and Vibration Management, Biosecurity and Weed Management, Waste Management, etc.

3.4 Management Plan Review

The PC Management Plans and supporting documentation must be submitted to Stanwell for review prior to mobilisation to site.

The PC must also review and revise the Management Plans to ensure that they remain up to date throughout the project. The PC must ensure that each person carrying out construction work in connection with the project is made aware of any revision to the Management Plans.

4.0 Site Mobilisation

Prior to mobilisation to site the PC must provide all required HSE documentation as required by the Contract, Scope of Work, this Business Procedure and as outlined within the *Stanwell Mobilisation Readiness Checklist (T-3913)*.

The PC must also participate in a 'Project Kick Off Meeting' which must include health, safety and environment as an agenda item.

Following receipt and review of mobilisation deliverables from the PC, Stanwell will issue a *Notice giving Possession of Site (CM 15/72971)* for the Project Site/ Licenced Construction Area (LCA).

5.0 Risk Management

5.1 Risk Appetite

In undertaking the project, the PC should consider Stanwell's risk appetite for HSE risks as per the *Stanwell Risk Appetite Statement (GOV-POL-38)*, this includes:

Risk Category	Sub-Risk Category	Risk Appetite Statement
Health & Safety	Health & Safety Management	Stanwell cares for the health, safety and wellbeing of its people. Stanwell has no appetite for events / circumstances that cause serious injury or fatality, or serious negative impact to the health and wellbeing of our people.
	Regulatory Compliance	Stanwell is committed to complying with applicable health and safety regulatory requirements. Stanwell has no appetite for incidences of: • material breaches of health and safety regulations; • repeat breaches of health and safety regulations; or • intentional breaches of health and safety regulations, or Stanwell's policies or practices.
Environmental	Neighbour Impact	Stanwell has a conservative appetite for managing our asset's impacts on neighbours; we comply with Environmental Authority conditions, and wherever possible, avoid negatively impacting neighbours, while ensuring any commercial cost is reasonable.
	Environmental Management	Stanwell is committed to managing environmental risks and complying with legal and other relevant environmental requirements. Stanwell has no appetite for incidences of: • material breaches of environmental regulations or environmental authority conditions; • repeat breaches of environmental regulations or environmental authority conditions (except those related to administrative or sampling errors with no environmental harm, have no impact to risk profile and are not seen as significant by the regulating authority); or • intentional breaches of environmental regulations or environmental authority conditions.
	Rehabilitation	Stanwell has no appetite for not completing effective rehabilitation activities in a timely manner.

5.2 General Risk Management Requirements

The PC must develop and implement risk management processes to identify project specific HSE hazards, assess risks and control and communicate those risks and control measures.

The PC must eliminate HSE risks so far as is reasonably practicable, and if not reasonably practicable to eliminate HSE risks, utilise the hierarchy of controls to minimise those risks so far as is reasonably practicable.

Risks must be assessed using a risk assessment matrix that includes likelihood and consequence criteria. The risk assessment matrix must be provided to Stanwell for review prior to risk assessments being conducted.

5.3 Risk Register

The PC must undertake a Project HSE Risk Assessment and maintain a Project HSE Risk Register (Risk Register). The Risk Register must be provided to Stanwell prior to the commencement of construction.

The Risk Register must identify all HSE risks associated with the works and identify mitigations in place to eliminate or reduce risks through the application of the hierarchy of controls.

The Risk Register must be maintained and regularly reviewed, by the PC to ensure that it remains current until such time that the project has been handed over successfully. The PC must provide Stanwell with records of any changes to the Risk Register, as soon as practicable.

5.4 Risk Assessment

The PC must ensure that risk assessments are prepared for activities undertaken on site. The PC must determine the most appropriate risk assessment tool, depending on the nature of the works, in accordance with their risk management procedures.

Safe Work Method Statements (SWMS) must be prepared for high-risk construction work activities in accordance with the *Old Work Health and Safety Regulation 2011*. The PC must establish and include within the WHS Management Plan, arrangements for the collection and any assessment, monitoring, and review of SWMS.

5.5 Permit to Work

The PC must establish and implement adequate work procedures and processes relevant to the project scope of work.

The PC should identify and consider relevant work activities that require a permit, such as:

- hot work;
- electrical work;
- isolations;
- confined space work;
- work at height;
- demolition;
- asbestos removal;
- excavation / land and vegetation disturbance work; and
- diving operations.

The PC must provide a copy of their permit to work procedures to Stanwell before undertaking any relevant work activities.

5.6 Electrical Safety

The PC must ensure risks associated with electrical installations and work are identified and managed. Processes must be developed in accordance with relevant legislation, including but not limited to:

- *Qld Electrical Safety Act 2002;*
- *Qld Electrical Safety Regulation 2013;*
- *Qld Managing Electrical Risks in the Workplace Code of Practice 2021;*
- *Qld Electrical Safety Code of Practice 2020 – Works;*
- *Qld Working Near Overhead and Underground Electric Lines Code of Practice 2020; and*
- *AS/NZS 3012:2019 Electrical Installations – Construction and Demolition Sites.*

5.7 Safety in Design

The PC must implement Safety in Design processes and integrate control measures early in the design process to eliminate or, if this is not reasonably practicable, minimise risks to health, safety and the environment.

When designing structures, the PC must undertake Safety in Design activities in accordance with the *Qld Work Health and Safety Regulation 2011* and *Qld Safe Design of Structures Code of Practice 2021*.

The PC must also consider the requirements of the environmental legislation, including but not limited to:

- *Qld Environmental Protection Act 1994;*
- *Qld Environmental Protection Regulation 2019;*
- *Qld Environmental Protection (Air) Policy 2019;*
- *Qld Environmental Protection (Noise) Policy 2019;*
- *Qld Environmental Protection (Water and Wetland Biodiversity) Policy 2019; and*
- Environmental Authority, where applicable.

Risk workshops including Safety in Design (SiD), Hazard identification (HAZID) and Hazard and Operability (HAZOP) must be undertaken, with consideration to the following requirements:

- facilitation by appropriately qualified and experienced professionals;
- attendance by relevant personnel, including but not limited to, designers, engineers, construction workers, health and safety and environmental professionals;
- invitations for attendance extended to representatives from Stanwell; and
- provision of supporting documentation for review prior to the workshop.

The PC must provide written Safety in Design reports to Stanwell that specify the hazards relating to the design.

6.0 Leadership and Commitment

The PC should demonstrate effective leadership and commitment to managing HSE for the project. The PC's leadership team management must:

- take overall responsibility and accountability for the prevention of work-related injury and ill health;
- ensure a HSE Policy and related HSE objectives and targets are established and are compatible with the project;

- ensure the integration of the PC's HSE management system requirements into the project's processes;
- ensure adequate HSE resources (including people, facilities, and equipment) are provided and available in accordance with the Contract;
- ensure and promote continual HSE improvement;
- support reporting of incidents, hazards, risks, and opportunities; and
- establish and implement processes for consultation and participation of workers.

The PC should consider establishing a Field Leadership Program to improve HSE outcomes through visible and engaged leaders. The Field Leadership Program should be designed primarily for leaders with operational accountabilities to engage with their teams on HSE in the field through activities, such as:

- HSE observations / interactions;
- critical control verifications; and
- inspections / audits.

The Field Leadership Program is to be documented within the WHS Management Plan, or another readily available document.

7.0 Induction, Training and Competency

7.1 Induction

The PC must establish and implement an induction program which provides information about the HSE risks and work practices specific to the project, some items to consider include:

- hazards and control measures relevant to the site;
- project specific HSE documents, policies, and plans;
- supervisory, consultation, issue resolution and reporting arrangements;
- site HSE rules;
- workplace facilities, including their location, use and maintenance;
- first aid provisions and emergency procedures, including after-hours emergency contacts;
- health monitoring requirements and procedures;
- location of underground / overhead services; and
- access, egress and security.

Relevant content relating to Stanwell specific requirements must be included in the PC Induction.

The PC may also be required to participate in Stanwell induction processes. This may include participation in online and/or face to face training. These requirements are to be confirmed and agreed prior to mobilisation.

The PC must also ensure that any person who is to carry out construction work has completed General Construction Induction Training in accordance with the *Qld Work Health and Safety Regulation 2011*.

7.2 Training and Competency

The PC must establish and implement training and competency processes for the project, including but not limited to:

- undertake a Training Needs Analysis and determine the required HSE training and competency requirements for personnel undertaking work on the project;
- provide training as required by applicable laws and standards;

- ensure that all workers hold and have proof of a high-risk work licence or competency applicable to the work being undertaken out on site;
- develop and implement a Verification of Competency (VOC) process (or similar) for high-risk work licences and mobile plant operation; and
- maintain a Training Register (or similar) of training and competency qualifications for project personnel.

8.0 Subcontractor Management

The PC must establish processes for the management of subcontractors working on the project. This should include consideration to selection, onboarding / induction, monitoring arrangements and actions that will be implemented if the subcontractor is not complying with legislative requirements or the requirements of the HSE Management Plan.

Depending on the locality of the project, subcontractors may also be required to participate in Stanwell Induction processes. This may include participation in online and/or face to face training. These requirements are to be confirmed and agreed prior to mobilisation.

The PC must document subcontractor management processes within the WHS Management Plan for the project.

9.0 Communication and Consultation

9.1 Consultation, Cooperation and Coordination

The PC must develop and implement consultation, cooperation, and coordination processes that comply with consultation requirements under the *Qld Work Health and Safety Act 2011*, *Qld Work Health and Safety Act 2011* and *Qld Work Health and Safety Consultation, Cooperation and Coordination Code of Practice 2021*.

The PC must document consultation, cooperation, and coordination processes within the WHS Management Plan for the project.

9.2 Communication

The PC must establish processes for the distribution and communication of HSE information relating to the project, for example:

- inductions;
- pre-start meetings;
- toolbox talks;
- health and safety committee meetings;
- HSE Alerts, lessons learnt and bulletins; and
- noticeboards.

The PC should consider diversity aspects (e.g. gender, language, culture, literacy, disability) when determining communication methods.

The PC must share relevant HSE communications, such as HSE Alerts and industry learnings, with Stanwell.

10.0 Facilities and Amenities

The PC must provide and maintain adequate and accessible facilities in accordance with the *Qld Work Health and Safety Regulation 2011* and *Q Managing the Work Environment and Facilities Code of Practice 2021*, including but not limited to:

- drinking water;

- toilets;
- hand and face washing facilities; and
- dining facilities.

The PC must ensure that workers, including those who have particular needs or disabilities, have access to the facilities. All amenities are to be maintained in a hygienic, safe, and serviceable condition.

11.0 Site Security and Access

The PC must establish and implement processes to ensure that the project site is secured from authorised access, with consideration to:

- access authorisation processes;
- fencing;
- barricading and signage; and
- security monitoring.

12.0 Health and Wellbeing

12.1 Health Risk Assessment, Pre-Employment Medicals and Health Monitoring

The PC must manage any occupational health risks applicable to the project.

This may include the development of a Health Risk Assessment and establishment of processes for pre-employment medical assessments, occupational hygiene monitoring and periodic health monitoring, as determined to be relevant, in accordance with the *QLD Work Health and Safety Regulation 2011*.

12.2 Fitness for Work

The PC must ensure all workers, contractors and visitors attend site fit for duty and must have a fitness for work process that includes alcohol and other drugs management, and fatigue management.

12.2.1 Alcohol and Other Drugs

The PC must establish and implement procedures for the management of alcohol and other drugs. This may include the implementation of an alcohol and other drug testing regime.

12.2.2 Fatigue Management

The PC must have procedures and systems that demonstrate how it will manage fatigue in accordance with:

- *Qld Work Health and Safety Act 2011*;
- *Qld Work Health and Safety Regulation 2011*;
- *Heavy Vehicle National Law*;
- *Workplace Health and Safety Queensland – Preventing and Managing Fatigue Related Risk in the Workplace 2020*; and
- *Safe Work Australia – Guide for Managing the Risk of Fatigue at Work 2013*.

12.3 Psychosocial Safety

The PC must develop and implement processes for managing risks to workers' psychosocial health that may result from psychosocial hazards in accordance with the *Qld Managing the Risk of Psychosocial Hazards at Work Code of Practice 2022*.

The PC should consider undertaking a project specific Psychosocial Risk Assessment to identify appropriate control measures for managing the risk of relevant psychosocial hazards. The Psychosocial Risk Assessment should be reviewed regularly to ensure that it is up to date and captures changing or emerging risks in this space as the project progresses.

The PC should also ensure workers are aware of the wellbeing services available to them.

12.4 Rehabilitation and Return to Work

The PC must establish and implement rehabilitation and return to work processes in accordance with the:

- *Qld Workers Compensation and Rehabilitation Act 2003*; and
- *Qld Workers Compensation and Rehabilitation Regulation 2014*.

13.0 Personal Protective Equipment

The PC must determine Personal Protective Equipment (PPE) requirements for the project and enable the provision of PPE to workers in accordance with the *Qld Work Health and Safety Regulation 2011*.

The PC must provide workers with information, training, and instruction in the proper use, wearing, storage and maintenance of PPE.

Other persons, including visitors, to the project site must also be provided with PPE.

Where respiratory protective equipment (RPE) is required to control respiratory hazards, the PC must establish a RPE program including selection, fit testing, training, use and maintenance in accordance with *AS/NZS 1715:2009 – Selection, Use and Maintenance of Respiratory Protective Equipment*.

14.0 Incident Reporting and Investigation

The PC must establish and implement incident reporting and investigation procedures and incorporate the below requirements into their respective Management Plans.

14.1 Incident Reporting

The PC must notify Stanwell of any relevant HSE incidents immediately. These include, but are not limited to:

- incidents involving the death or serious injury or illness of its employees or those of its subcontractors;
- dangerous incidents or near miss events;
- dangerous or serious electrical incidents;
- high potential Incidents;
- worker exposure or potential exposure incidents;
- environmental incidents (e.g. spills, fauna injury/deaths, over-clearing etc.);
- notifiable incidents; and
- community complaints.

The PC must provide the following information with any incident notification to Stanwell:

- date, time and location of incident;
- description of events and actual/potential consequences;
- who was involved; and
- actions taken.

14.2 External Regulator Notification

In the event of a notifiable incident, the PC must notify the relevant regulatory authority (e.g. *Workplace Health and Safety Queensland (WHSQ)*, *Electrical Safety Office (ESO)*, *Department of Environment, Science and Innovation (DESI)*) in accordance with statutory timeframes. The PC must verbally notify Stanwell as soon as is reasonably practicable and provide a copy of the notification on the day that it is submitted.

The PC must provide Stanwell with a copy of any further Regulator correspondence in relation to the incident, including notices, infringements, penalties, etc. The PC must also provide evidence that the incident has been closed with the relevant Regulator.

If the notifiable incident relates to an environmental authority / approval / permit held by Stanwell, the PC must notify Stanwell who will undertake the notification to the relevant Regulator.

14.3 Investigation

The PC must undertake incident investigations in accordance with their investigation procedures and Management Plans.

The PC must provide a draft investigation in writing to Stanwell for review within seven days of the incident. The investigation must be finalised and closed out within 30 days of the incident. This timeline may change depending on the severity of the incident however will require approval from Stanwell.

Stanwell may conduct its own investigation into any incident and the PC must cooperate fully by providing prompt information about the incident and access to relevant documents and the PC's personnel.

15.0 Emergency Management

15.1 Emergency Management Plan

The PC must establish and implement an Emergency Management Plan for the project.

In developing the Emergency Management Plan, the PC must consider:

- the types of emergencies most likely to arise from their activities;
- identifying who must be contacted and notified in an emergency;
- evacuation locations;
- provision of emergency information to workers; and
- any necessary procedures for rescuing persons.

The Emergency Management Plan must include the following:

- an effective response to an emergency;
- evacuation procedures;
- identify key personnel with specific roles and responsibilities in emergency situations;
- notifying emergency service organisation and other relevant stakeholders at the earliest opportunity;
- medical treatment and assistance; and
- effective communication between the person authorised to coordinate the emergency response and persons at the workplace.

Where undertaking a project at a Stanwell generating site, the PC must also consider the Stanwell Emergency Management Plan and evacuation locations.

The PC must establish processes and a frequency for testing emergency procedures, including liaison with emergency services and other stakeholders, as appropriate. Learnings from

emergency drills, exercises and incidents must be documented, incorporated into revisions of the Emergency Response Plan and shared with workers and other relevant stakeholders.

The PC must also provide workers with information, training and instruction about implementing the Emergency Management Plan, including display of evacuation procedures on site.

15.2 First Aid

The PC must develop and implement processes for managing first aid for the project in accordance with the *Qld Work Health and Safety Regulation 2011* and *Qld First Aid in the Workplace Code of Practice 2021*.

16.0 Environmental Management

16.1 Environmental and Planning Approvals

The PC must establish and implement processes to ensure that the project is conducted in accordance with the relevant environmental and planning approvals, required by legislation, such as, but not limited to:

- *Environmental Protection and Biodiversity Conservation Act 1999;*
- *Qld Environmental Protection Act 1994 and Regulation 2019;*
- *Qld Vegetation Management Act 1999;*
- *Qld Nature Conservation Act 1992 and Regulations;*
- *Qld Aboriginal Cultural Heritage Act 2003;*
- *Qld Planning Act 2016 and Regulation 2017;*
- *Qld Land Act 1994;*
- *Qld Water Act 2000;*
- *Qld Fisheries Act 1994;*
- Development Codes, Development Approval;
- Local Laws; and
- Environmental Authority, where applicable.

The PC must ensure that all subcontractors and other applicable stakeholders have access to approval documentation.

The PC must ensure that the project CEMP outlines management and mitigation measures that will be implemented to ensure compliance with project's environmental and planning approvals and regulatory requirements.

16.2 Environmental Authority

The PC must ensure that the project is undertaken in accordance with the requirements of the Environmental Authority for the site, where applicable.

When undertaking projects at Stanwell generating sites with an existing Environmental Authority, the PC must review and comply with the *Stanwell Environmental Authority – Project Compliance Checklist (ENV-WI-20)* throughout all project phases.

16.3 Land and Vegetation Disturbance

The PC must establish and implement processes to ensure land and vegetation disturbance is managed in accordance with all environmental legislative requirements.

The PC must comply with the requirements of the *Stanwell Business Procedure: Land & Vegetation Disturbance (ENV-PROC-39)*, where relevant to the project.

All activities that classify as land and/or vegetation disturbance must have an approved *Stanwell Land and Vegetation Disturbance Permit (LVDP) (T-1985)* prior to the commencement. A LVDP request is required to be submitted a minimum of 10 working days prior to disturbance activities being undertaken.

The PC must ensure that all workers review and sign onto the LVDP and comply with any conditions and controls for land and vegetation disturbance.

The PC must also implement processes to ensure compliance with specific landowner access arrangements and requirements.

16.4 Species Management Program

A Species Management Program (SMP) is required where an animal breeding place, as defined under Section 335 of the *Qld Nature Conservation (Animals) Regulation 2020*, has been identified and activities are proposed that would tamper with the breeding place.

The PC must ensure that the project is undertaken in accordance with the requirements of the approved SMP for the project site, where applicable.

16.5 Emissions Reporting

The PC must establish and implement processes for emissions reporting as required by the *National Greenhouse and Energy Reporting Act 2007* and *Qld Environmental Protection Regulation 2019*. Where Stanwell has operational control of the project site location, the PC will be required to collect emissions data in line with the *National Greenhouse and Stanwell Energy Reporting System - Contractor Reporting Form (T-1779)* and provide to Stanwell to fulfil reporting obligations.

16.6 Waste Reporting

The PC must establish and implement processes for waste reporting and regulated waste tracking as required by the *Qld Waste Reduction and Recycling Act 2011* and *Qld Environmental Protection Regulation 2019*.

16.7 Sustainability

The PC should consider, where applicable, opportunities and contributions to the achievement of Stanwell's Sustainability Commitments throughout the lifecycle of the contract, including design and construction phases.

Stanwell's Sustainability Commitments include:

- reduce portfolio emissions and help ensure security of energy supply;
- safeguard the flora and fauna, land, and waterways around our sites;
- work with suppliers who help achieve our sustainability commitments;
- create transformative economic and social opportunity for our host communities as well as First Nations people; and
- ensure our people realise opportunities from the energy transition; and
- ensure our workplace is safe, inclusive, and diverse.

16.8 Cultural Heritage

The PC must ensure all project works are undertaken in accordance with relevant legislation including the *Aboriginal Cultural Heritage Act 2003*, *Qld Heritage Act 1992*, and *Torres Strait Islander Cultural Heritage Act 2003*.

A Cultural Heritage Management Plan (CHMP) must be in place or prepared and approved, prior to commencement of any ground disturbance works.

The PC must ensure that construction activities are managed to maintain cultural heritage values of sites, place, and values within and adjacent to the project site. If during any activities

undertaken at the project site an item or object of potential Cultural Heritage significance is discovered, work shall cease immediately, an exclusion zone established, and the finding reported to Stanwell.

17.0 HSE Performance Reporting

The PC must establish HSE objectives and targets for the project, including a mix of 'leading' and 'lagging' indicators, including but not limited to:

Leading Metrics	Target	Measure
Critical Control Verifications (CCVs)	100% PC to advise number of CCVs planned per month.	% of CCVs performed against planned (target) during the reporting period.
Leadership site visits / interactions	100% PC to advise monthly target.	% of leadership site visits performed against planned (target) during the reporting period.
HSE Corrective Action Completion	Actions to be closed in agreed timeframe.	% HSE Corrective Actions completed (for closed event investigations and/or HSE Audit Reports)
Lagging Metrics	Target	Measure
The number of Serious Injury &/or Fatality (SIF) (Actual Impact) events	0	The number of Serious Injury &/or Fatality (SIF) (Actual Impact) events against target. Further information required – refer below.
The number of Serious Injury &/or Fatality (SIF) (Potential Impact) events	0	The number of Serious Injury &/or Fatality (SIF) (Potential Impact) events against target. Further information required – refer below.
The number of Events Notifiable to a Regulator (HS and E)	0	The number of Events Notifiable to a Regulator (HS and E) against target. Further information required – refer below.
Health, Safety and Environmental Enforcement Actions (Moderate Level 3 Compliance/Legal impact) or greater.	0	The number of HSE Enforcement Actions (Moderate Level 3 or greater Compliance / Legal) against target. Further information required – refer below.
Number of First Aid Injuries	N/A	Report number of first aid injuries.
Number of Medical Treatment Injuries	N/A	Report number of Medical Treatment Injuries. Further information required – refer below.
Number of Lost Time Injuries	N/A	Report number of Lost Time Injuries. Further information required – refer below.
Number of Regulatory Notices Received	N/A	Report number of Regulatory Notices Received. Further information required – refer below.

For applicable events (as indicated in the above table), the PC must provide the following HSE reporting information to Stanwell on a monthly basis (emailed by close of business by the second working day of the month):

- Notifiable Incidents: provide the following details for all health, safety and environmental notifiable incidents (e. g. where environmental harm has occurred, or might occur; and/or breaches to the conditions of an Environmental Authority (EA) (where applicable) that were reported to a Regulator during the reporting period (or should have been reported in accordance with WHS, Electrical Safety or Environmental laws):
 - notifiable incident classification under the applicable law (e.g., WHS Act, Electrical Safety Act, Environmental Protection Act);
 - event description;
 - immediate actions taken;
 - investigation findings;
 - corrective actions; and
 - lessons learned and how these have been or will be incorporated into the Contractor's operational policies and procedures.
- Work-related fatalities and injuries:
 - Lost Time Injuries (LTI) – Provide number of LTI events for the reporting period; and event summary, investigation findings and corrective actions (where applicable);
 - Medical Treatment Injuries (MTI) – Provide number of MTI events for the reporting period; and event summary, investigation findings and corrective actions (where applicable); and
 - First Aid Injuries (FAI) – Provide number of FAI events for the reporting period.
- HSE Enforcement Actions and HSE Regulatory Notices received:
 - provide details of HSE Enforcement Actions and/or HSE Regulatory Notice received from a Regulator during the reporting period. Such information should include clear explanation of the contravention and details of any fines and/or corrective action taken.

18.0 Stanwell Governance and Assurance

Stanwell will undertake monitoring and assurance review activities throughout all phases of the project. The PC will be required to make available any copies of HSE documentation considered relevant to providing Stanwell with assurance that HSE is being managed satisfactorily and in line with legislative requirements.

Stanwell will undertake targeted HSE audits against the project Management Plans and relevant legislation to determine performance and compliance. The PC must make all relevant HSE records including those of subcontractors and suppliers available upon request and provide reasonable assistance during the audits.

19.0 Corrective Action Management

The PC must establish and implement processes for the management of corrective and preventive actions, resulting from activities such as:

- audits;
- inspections;
- observations / interactions;
- risk assessments; and
- incident Investigations.

The PC must maintain a Corrective Action Register (or similar) and identify a time frame for closure, nominated person responsible for implementing and monitoring the action and monitoring for the effectiveness of controls.

The PC must provide corrective action plans and evidence to Stanwell of closure, where requested.

20.0 Site Handover

At the completion of the project, the PC must provide all required HSE documentation and deliverables as required by the Contract, Scope of Work, this Business Procedure and as outlined within the *Stanwell Project Site Handover – HSE Documentation Checklist (T-3904)*.

21.0 Document and Records Management

The PC must establish and implement processes for the creation, review, approval, dissemination, retention and disposal of documents and records in accordance with relevant legislative requirements. The PC must provide records to Stanwell upon request.

22.0 Responsibilities

22.1 Project Teams

Stanwell Project Teams will be responsible for:

- providing this Business Procedure to Principal Contractors;
- obtaining relevant documentation and information required by this Business Procedure from Principal Contractors; and
- managing project and Principal Contractor compliance to this Business Procedure.

22.2 Health, Safety and Environment Team

The Health, Safety and Environment Team will be responsible for providing advice and support to Project Teams to implement the requirements of this Business Procedure, including:

- reviewing Principal Contractor documentation;
- participating in project risk management activities;
- issuing Land and Vegetation Disturbance Permits;
- facilitating HSE performance reporting;
- undertaking governance and assurance activities; and
- overseeing regulatory engagement and maintaining records.

22.3 Principal Contractors

Principal Contractors will be responsible for complying with all requirements of this Business Procedure.

23.0 Review, Consultation and Communication

Review:

This Document is required to be reviewed, as a minimum, every 5 years.

Consultation:

Consultation will occur in accordance with the *Stanwell Business Procedure: HSE Consultation and Participation (HSE-PROC-13)*.

Communication/Requirements after Update:

This Business Procedure will be communicated and available on the Stanwell Intranet and is to be made available to Principal Contractors via contractual documentation.

24.0 References

Legislation

- GOC State Archives – Public Records Act
- Qld Work Health and Safety Act 2011
- Qld Work Health and Safety Regulation 2011
- Qld Workers Compensation and Rehabilitation Act 2003
- Qld Workers Compensation and Rehabilitation 2014
- Heavy Vehicle National Law
- Qld Electrical Safety Act 2002
- Qld Electrical Safety Regulation 2013
- Qld Environmental Protection Act 1994
- Qld Environmental Protection Regulation 2019
- Qld Environmental Protection (Air) Policy 2019
- Qld Environmental Protection (Noise) Policy 2019
- Qld Environmental Protection (Water and Wetland Biodiversity) Policy 2019
- Environmental Protection and Biodiversity Conservation Act 1999
- Qld Aboriginal Cultural Heritage Act 2003
- Torres Strait Islander Cultural Heritage Act 2003
- Qld Planning Act 2016
- Qld Regulation 2017
- Qld Land Act 1994
- Qld Nature Conservation Act 1992
- Qld Nature Conservation (Animals) Regulation 2020
- Qld Fisheries Act 1994
- Qld Water Act 2000
- National Greenhouse and Energy Reporting Act 2007

Standards & Guidelines

- AS/NZS ISO 45001:2018 Occupational Health and Safety Management Systems
- AS/NZS ISO 14001:2016 Environmental Management Systems
- AS/NZS 1715:2009 – Selection, Use and Maintenance of Respiratory Protective Equipment
- Workplace Health and Safety Queensland – Preventing and Managing Fatigue Related Risk in the Workplace 2020

- Safe Work Australia – Guide for Managing the Risk of Fatigue at Work 2013
- AS/NZS 3012:2019 Electrical Installations – Construction and Demolition Sites

Business Procedures

Document No	Document Title
GOV-POL-38	Stanwell Risk Appetite Statement
GOV-STD-11	Stanwell's Risk Evaluation Matrix
ENV-PROC-39	Land & Vegetation Disturbance
HSE-PROC-13	HSE Consultation & Participation

Tools

T-3913	Mobilisation Readiness Checklist
ENV-WI-20	Environmental Authority – Project Compliance Checklist
T-1985	Land & Vegetation Disturbance Permit
T-3904	Project Site Handover – HSE Documentation Checklist

25.0 Definitions

Word / Abbreviation	Definition
Construction Project	Same meaning as the QLD Work Health and Safety Regulation 2011, Section 292. A project that involves construction work where the cost of the construction work is \$250,000 or more.
Construction Work	Same meaning as the QLD Work Health and Safety Regulation 2011, Section 289. Any work carried out in connection with the construction, alteration, conversion, fitting-out, commissioning, renovation, repair, maintenance, refurbishment, demolition, decommissioning or dismantling of a structure.
Critical Controls	A highly relied upon control that is crucial to preventing the occurrence of an unwanted event or mitigating the consequences of the unwanted event if it did occur. The absence or failure of a critical control would significantly increase the risk of environmental harm, serious injury or fatality (SIF) despite the existence of the other controls.
Critical Control Verification	Critical Control Verification (CCV) is a systematic and proactive approach to auditing and identifying critical controls that are potential precursors to SIF exposure.
Hazard	A situation or thing that has the potential to harm a person.

High Risk Construction Work	Construction work that: a) involves a risk of a person falling more than 2m; or b) is carried out on a telecommunication tower; or c) involves demolition of an element of a structure that is load-bearing or otherwise related to the physical integrity of the structure; or d) involves, or is likely to involve, the disturbance of asbestos; or e) involves structural alterations or repairs that require temporary support to prevent collapse; or f) is carried out in or near a confined space; or g) is carried out in or near— (i) a shaft or trench with an excavated depth greater than 1.5m; or (ii) a tunnel; or h) involves the use of explosives; or i) is carried out on or near pressurised gas distribution mains or piping; or j) is carried out on or near chemical, fuel or refrigerant lines; or k) is carried out on or near energised electrical installations or services; or l) is carried out in an area that may have a contaminated or flammable atmosphere; or m) involves tilt-up or precast concrete; or n) is carried out on, in or adjacent to a road, railway, shipping lane or other traffic corridor that is in use by traffic other than pedestrians; or o) is carried out in an area at a workplace in which there is any movement of powered mobile plant; or p) is carried out in an area in which there are artificial extremes of temperature; or q) is carried out in or near water or other liquid that involves a risk of drowning; or r) involves diving work.
HSE Corrective Action Completion	The percent of HSE Corrective Actions completed (for closed HSE event investigations and/or HSE Audits reports). The following formula applies: (Number of completed actions divided by Number of total actions) x 100.
HSE Enforcement Action (Moderate Level 3 impact or greater)	An incident involving a breach of legislative or regulatory obligation(s) resulting in moderate fines (or greater) and/or legal proceedings (instituted by an external body or Regulator). Note: This is in alignment with the Stanwell's Risk Evaluation Matrix (GOV-STD-11) for Moderate Level 3 (or greater) Compliance/Legal Risk category i.e. Breach, repeated breaches or ongoing breaches of legislative or regulatory obligation/s for which there are moderate fines (\$10,001 - \$100,000 or greater) issued or likely to be issued and/or administrative action taken by a regulator to prevent or rectify the breach/s (e.g. environmental evaluation).
HSE Notifiable Incident	Any incident reported to a state-based regulator as per the requirements outlined in that state's work health and safety and/or environmental legislation.

Land and Vegetation Disturbance	Land and vegetation disturbance includes the following: • Ground Disturbance – any activity that will break the ground surface or the surface rock layer of the ground, including but not limited to tracked vehicle movements (bulldozer, excavator), post hole digging, excavation works, stockpiling activity (e.g., of soil or vegetation), grading, ripping, ploughing, dredging, blasting, drilling, placing of fill etc. Includes movement of soil from one location to another location. Excludes rubber tyre vehicle movements; • Vegetation Disturbance – pruning, thinning, trimming, clearing, burning etc. of vegetation; and • Work in the beds or banks of a watercourse, lake or spring - work along a watercourse bed or bank refers to the land that is within the line along the outer limits of the defined channel of the watercourse (i.e. that following the highest points of land in the channel that are covered by the watercourse water, whether permanently or intermittently); Excludes carrying out weed spraying, monitoring, surveying or inspections.
Leadership site visits / HSE interactions:	Planned site visits by leaders / managers which include observation of work activities being undertaken and/or HSE interactions with the workforce. A HSE Interaction is a proactive way to discuss expectations, behaviours and values. It may also be used to discuss aspects of the activity that deserve positive recognition or indicate opportunities to improve.
Licenced Construction Area (LCA)	A designated area of a construction project established only where the construction work meets the Queensland Building and Construction Commission (QBCC) licenced building work threshold and is carried out by a QBCC-licenced contractor.
Principal Contractor	Same meaning as the QLD Work Health and Safety Regulation 2011, Section 293. The person engaged as principal or main contractor for a Construction Project in accordance with the WHS legislation.
Reasonably Practicable	Same meaning as the QLD Work Health and Safety Act 2011, Section 18. In relation to a duty to ensure health and safety, means that which is, or was at a particular time, reasonably able to be done in relation to ensuring health and safety, taking into account and weighing up all relevant matters including— (a) the likelihood of the hazard or the risk concerned occurring; and (b) the degree of harm that might result from the hazard or the risk; and (c) what the person concerned knows, or ought reasonably to know, about— (i) the hazard or the risk; and (ii) ways of eliminating or minimising the risk; and (d) the availability and suitability of ways to eliminate or minimise the risk; and (e) after assessing the extent of the risk and the available ways of eliminating or minimising the risk, the cost associated with available

	ways of eliminating or minimising the risk, including whether the cost is grossly disproportionate to the risk.
Risk	Combination of the likelihood of occurrence of an event and the severity that can be caused by the event.
Safe Work Method Statement	Same meaning as the QLD Work Health and Safety Act 2011, Section 299. A safe work method statement must— (a) identify the work that is high risk construction work; and (b) state hazards relating to the high risk construction work and risks to health and safety associated with those hazards; and (c) describe the measures to be implemented to control the risks; and (d) describe how the control measures are to be implemented, monitored, and reviewed.
Serious Injury or Fatality (SIF)	A work-related injury that results in: • Fatality; or • Life-Threatening Injury - An injury that, if not immediately treated, is likely to lead to the death of the affected individual, and will usually require the intervention of internal and/or external emergency response personnel to provide life-sustaining support; or • Life-altering injury - An injury that results in permanent or long-term impairment; or loss of use of an internal organ, body function, or body part.
Worker	Same meaning as the QLD Work Health and Safety Act 2011, Section 7.

26.0 Revision History

Rev. No.	Rev. Date	Revision Description	Author	Endorse/Check	Approved By
0	21.08.2024	Procedure created to outline minimum requirements for Principal Contractors undertaking Construction Projects for Stanwell	Whitney Tobin / Jayde Smith	Shane Lubbe / Carel Rothman	Kriss Ussher
	19.08.2025	MINOR CHANGE – Minor change made to ensure the procedural deliverables and hold-points required are applicable to either a 'Project Site' or an 'LCA', depending on the Project. No increase to Rev No or Date as noted by Jayde Smith	Jayde Smith		

17.0 Appendix D – Hazardous Building Materials Register

Hazardous Building Materials Register

Project Building
Stanwell Power Station
Switchyard Road,
Stanwell QLD 4702



Status of hazardous materials at Stanwell Power Station - Project Building



WARNING: Hazardous materials identified at the Site.

Refer to the report in its entirety for details of identified hazardous materials and the associated limitations (e.g. areas unable to be assessed).



Question today *Imagine tomorrow* Create for the future

Hazardous Building Materials Register
Project Building
Stanwell Power Station
Switchyard Road
Stanwell QLD 4702
STANWELL CORPORATION LTD

WSP
Level 12
900 Ann Street
Fortitude Valley
Brisbane QLD 4000
Australia
wsp.com

Rev	Date	Details
001	19 March 2026	First Issue

	Name	Date	Signature
Prepared by:	Brett Kriewaldt	16 March 2026	
Reviewed by:	Sam Martin	16 March 2026	
Approved by:	Gavin Dingle	19 March 2026	

This document may contain confidential and legally privileged information, neither of which are intended to be waived, and must be used only for its intended purpose. Any unauthorised copying, dissemination or use in any form or by any means other than by the addressee, is strictly prohibited. If you have received this document in error or by any means other than as authorised addressee, please notify us immediately and we will arrange for its return to us.



Table of contents

Glossary	iii
Abbreviations	vi
Executive Summary	1
1 Introduction	2
1.1 Purpose and Objective.....	2
1.2 Scope of Work	2
1.3 Survey Type	2
2 Site Information	4
2.1 Building Description	4
3 Survey Methodology	5
3.1 Preliminary	5
3.2 Site Inspection	5
3.3 Identification and Sample Analysis	5
3.3.1 Asbestos Containing Materials (ACM)	5
3.3.2 Lead-based Paints	5
3.3.3 Synthetic Mineral Fibres (SMF) Materials	6
3.3.4 Polychlorinated Biphenyls (PCBs)	6
3.3.5 Ozone Depleting Substances (ODS)	6
3.4 Collection of Data	7
3.5 Non-destructive survey limitations	7
3.5.1 Site specific inaccessible areas	7
4 Survey Results	8
5 Survey Recommendations	9
5.1 Site specific recommendations	9
5.2 Ongoing management recommendations	9
5.3 Asbestos General Management Guidelines	10
5.4 General Lead Paint / Dust Management.....	11
5.5 SMF Management Guidelines	11
5.6 PCB Management Guidelines	12
5.7 ODS Management Guideline	12

List of tables

Table 2.1	Building description	4
Table 3.2	PCB Concentration Classification.....	6
Table 3.3	Summary of site specific inaccessible areas at time of survey	7
Table 4.1	Summary of identified or assumed hazardous materials	8
Table 4.2	Items requiring remediation	8

List of appendices

Appendix A Hazardous Materials Register
Appendix B Site/Building Photographs
Appendix C Material Photographs
Appendix D Site Map/s
Appendix E NATA Laboratory Analytical Reports
Appendix F Risk Matrix
Appendix G Limitation
Appendix H References and Legislation
Appendix I General Information

Glossary

Report / Register – Risk Assessment Glossary

Primary Location/Room	The primary location description of the material described in the hazardous materials register (e.g. Main Office).
Secondary Location/Application	Means the use or application of the material described in the hazardous materials register (e.g. wall lining, floor covering, soffit lining, pipe lagging, etc.).
Material/Product Description	Refers to the type of known/suspected hazardous material (e.g. vinyl tile, fibre cement sheeting, fibrous insulation, etc.). Does not refer to the use or application of the material. This is covered in 'Secondary Location/Application'.
Friable (Asbestos)	Material that is in a powder form or that can be crumbled, pulverised or reduced to a powder by hand pressure when dry, and contains asbestos
Non-Friable (Bonded Asbestos)	Material containing asbestos that is not friable asbestos, includes materials containing asbestos fibres reinforced with a bonding compound.
Condition (Good)	Condition of a material where: — The material has no evidence of any significant damage/deterioration. — The material is in, or is close to, 'as new' condition.
Condition (Fair)	Condition of a material where: — There is some minor damage or wear throughout the extent of the material. — There is some obvious damage or significant wear but only in localised areas.
Condition (Poor)	Condition of a material where: — The material exhibits consistent damage or wear throughout the extent of the material. — Major or significant damage is evident, even if only in localised areas. — Any non-fixed material (e.g. debris).
Disturbance (Low)	The potential for disturbance is low when: — Activities in the area where the hazardous material is located are unlikely to result in damage or deterioration of the material. — The material is completely isolated from normal day to day activities. — The material is completely protected from nearby activities by an enclosure or encapsulation.
Disturbance (Medium)	The potential for disturbance is medium when: — Activities in the area have a potential to mildly impact upon the material and the activities are infrequent — The material is protected from activities by an enclosure or encapsulation; however the protection is not comprehensive.
Disturbance (High)	The potential for disturbance is high when: — Activities undertaken in the area are likely to result in immediate damage to identified hazardous materials — Activities in the area, whilst typically of low impact, happen on a regular basis and are likely to result in deterioration or damage to the material in the short to medium term.

Report Glossary

Airborne asbestos	Any fibres of asbestos small enough to be made airborne. For the purposes of monitoring airborne asbestos fibres, only respirable fibres are counted.
Asbestos	The asbestiform varieties of mineral silicates belonging to the serpentine or amphibole groups of rock-forming minerals, including actinolite asbestos, grunerite (or amosite) asbestos (brown), anthophyllite asbestos, chrysotile asbestos (white), crocidolite asbestos (blue) and tremolite asbestos.
Asbestos Cement (AC)	Products consisting of sand aggregate and cement reinforced with asbestos fibres (e.g. asbestos cement pipes and flat or corrugated asbestos cement sheets).
Asbestos containing material (ACM)	Any material, object, product or debris that contains asbestos.
Asbestos contaminated dust or debris (ACD)	Dust or debris that has settled within a workplace and is (or is assumed to be) contaminated with asbestos.
Asbestos fibre bundles	Asbestos fibres that are not part of a matrix or otherwise in a bonded form.
Asbestos removal work	Work involving the removal of asbestos or ACM, friable asbestos removal work or non-friable asbestos removal work.
Asbestos removalist	A person conducting a business or undertaking who carries out asbestos removal work.
Asbestos-related work	Asbestos-related work means work involving asbestos, other than asbestos removal work, that is permitted under the state regulation, such as, maintenance work that involves disturbing asbestos..
Assumed asbestos	Item status is based on a visual assessment.
Competent person	A person possessing adequate qualifications, such as suitable training and sufficient knowledge, experience and skill, for the safe performance of specific work.
Estimated quantity	All quantities of materials are an approximate measurement; an independent qualified surveyor / estimator should be engaged to quantify the quantities.
Hazard	Anything in the workplace that has the potential to harm people and the environment.
Inaccessible areas	Areas that are difficult to access, such as wall cavities and the interiors of plant and equipment. Refer to body of report for information on inaccessible areas.
In-situ asbestos	Asbestos or ACM fixed or installed in a structure, equipment or plant but does not include naturally occurring asbestos.
Lead dust	Dust or debris that has settled within a workplace and is (or is assumed to be) contaminated with lead.
Lead paint	Paint which has been assumed or confirmed to contain lead.
NATA-accredited laboratory	A testing laboratory accredited by the National Association of Testing Authorities (NATA), Australia, or recognised by NATA either solely or with someone else.
Ozone depleting substances (ODS)	Ozone depleting substances (ODSs) refer to those substances which deplete the ozone layer and are widely used in refrigerators, air conditioners, fire extinguishers, dry cleaning, cleaning solvents, electronic equipment, and as agricultural fumigants.
Person conducting a business or undertaking (PCBU)	A person conducts a business or undertaking is one who meets the definition outlined in Section 5 of the WHS Act.
Person with control	In relation to premises, a person who has control of premises used as a workplace. The person with control may be: — The owner of the premises — A person who has, under any control or lease, an obligation to maintain or repair the premises — A person who is occupying the premises — A person who can make decisions about work undertaken at the premises.

Polychlorinated Biphenyls (PCBs)	PCBs are chlorinated aromatic hydrocarbons, which can be found as an oily substance in capacitors and transformers used for electrical light fittings, electric motors, ceiling fans and dish washers. PCBs were commonly used for their fire resistant and electrical insulating properties, chemical inertness and stability
Respirable asbestos	An asbestos fibre that: — Is less than 3 microns (µm) wide — Is more than 5 µm long — Has a length to width ratio of more than 3:1.
Risk	Refers to the level of risk posed by the ACM based on its condition, friability, potential for disturbance (accessibility) and other factors such as proposed demolition/refurbishment works.
Sealed	Refers to whether the ACM is encapsulated with a sealant (such as paint, wallpaper, etc.), concealing its exposed surfaces.
Similar to	Refers to when a material is similar to a material that has been sampled.
Synthetic Mineral Fibre (SMF)	Synthetic mineral fibres are fibrous inorganic substances. These fibres are classified into three general groups: fiberglass (glass wool and glass filament), mineral wool (rock wool and slag wool), and refractory ceramic fibres (RCF).

Abbreviations

A	Amosite Asbestos (brown Asbestos)
AC	Asbestos cement (Asbestos-containing fibrous cement material)
ACD	Asbestos contaminated dust or debris
ACM	Asbestos-containing material
ALARA	As low as reasonably achievable
AMP	Asbestos management plan
ARCP	Asbestos removal control plan
ASCC	Australian Safety & Compensation Council
C	Crocidolite Asbestos (blue Asbestos)
CH	Chrysotile Asbestos (white Asbestos)
EPA	Environment Protection Authority
FC	Fibre cement (usually sheeting)
LAA	Licensed asbestos assessor
LARC	Licensed asbestos removal contractor
LBP	Lead based paint
LD	Lead in dust
NAD	No Asbestos Detected
NATA	National Association of Testing Authorities, Australia
NOHSC	National Occupational Health and Safety Commission
OH&S	Occupational health and safety
ODS	Ozone depleting substances
PCBU	Person conducting a business or undertaking
PCB	Polychlorinated biphenyls
PPE	Personal protective equipment
RPE	Respiratory protective equipment
SMF	Synthetic mineral fibre
SWMS	Safe work method statement
WH&S	Workplace health and safety

Executive Summary

WSP Australia Pty Ltd (WSP) was engaged by Stanwell Corporation LTD (referred to as the 'Client') to undertake a hazardous materials survey of Stanwell Power Station Project Building, located at Switchyard Road, Stanwell QLD 4702 (referred to as the 'Site'). This report presents the findings of the inspection conducted by Brett Kriewaldt of WSP on 02 March 2026.

WSPs scope was to undertake a hazardous building materials survey of nominated buildings located at Stanwell Power Station, Switchyard Road, Stanwell QLD 4702 to ascertain the location, extent, type and condition of asbestos, lead paint, synthetic mineral fibres (SMF) materials, polychlorinated biphenyls (PCBs), and ozone depleting substances (ODS).

The following buildings / structures were surveyed as part of the agreed scope of works:

- Project Building

Findings

The following table summarises hazardous materials identified during the site survey.

Stanwell Power Station - Project Building					
Material	Identified	Number of items	Risk Range		
Asbestos					
Friable ACM	No	-	-	to	-
Non-friable ACM	Yes	3	Low	to	Low
Synthetic Mineral Fibres					
Synthetic Mineral Fibres	Yes	3	Low	to	Low
Lead Paint / Lead Dust					
Lead Based Paints	Yes	2	Low	to	Low
Polychlorinated biphenyls (PCBs)					
PCBs	Yes	1	Low	to	Low
Ozone Depleting Substances (ODS)					
ODS	Yes	3	Low	to	Low

Items requiring remediation are summarised below

Primary Location	Secondary Location	Material	Condition	Result	Risk Rating	Recommended Management Measures
No high risk items identified during the Site inspection.						

Refer to Section 5 for further recommendations.

Refer to Section 3.5.1 for site specific inaccessible locations.

Refer to Appendix A for the hazardous materials register and Appendix C for photographs.

1 Introduction

WSP Australia Pty Ltd (WSP) was engaged by Stanwell Corporation LTD (referred to as the 'Client') to undertake a hazardous materials survey of the Project Building, located at Switchyard Road, Stanwell QLD 4702 (referred to as the 'Site').

This report presents the findings of the survey conducted by Brett Kriewaldt of WSP on 02 March 2026.

No one section or part of a section of this report should be taken as giving an overall idea of this report. Each section must be read in conjunction with the whole of this report, including the hazardous materials register and sample results.

1.1 Purpose and Objective

The Client's objective is to comply with applicable legislative requirements, ensuring all accessible hazardous materials have been identified and located in the site buildings so that they can be appropriately managed, removed and/or disposed of as required.

1.2 Scope of Work

WSP's completed scope of work is summarised below:

- Undertake a non-destructive survey of the site to identify and assess hazardous materials present within the building, specifically the Project Building.
 - Attend site to inspect, sample and record all accessible areas for hazardous materials.
 - The hazardous materials include:
 - Asbestos
 - Lead paint
 - Synthetic mineral fibres (SMF) Materials
 - Polychlorinated biphenyls (PCBs), and
 - Ozone depleting substances (ODS)
 - Inspected the Site and collected representative samples using non-destructive techniques to:
 - Confirm the presence/absence of hazardous materials
 - Assess the condition and potential for disturbance of hazardous materials encountered; and
 - Determine the extent and quantities of hazardous materials
 - Prepare a hazardous materials register for the site.
 - Provide a semi-quantitative risk assessment of the hazardous materials identified or assumed.
 - Provide a hazardous materials survey report, which contains a hazardous materials register and recommendations for the ongoing management of the identified or assumed hazardous materials.
-

1.3 Survey Type

The survey was undertaken by visual inspection and through non-destructive sampling and analysis of those areas of the site that were nominated for inspection and were accessible at the time of the survey.

This type of survey aims to identify materials from readily accessible areas without major destruction, dismantling or damage to building aesthetics. This type of survey cannot access all construction materials and as such cannot identify hazardous materials that are present in inaccessible areas.

The survey is also limited by what can be safely accessed without the need for specialist equipment or training.

This report is not normally suitable for demolition or refurbishment purposes.

2 Site Information

2.1 Building Description

The survey was restricted to buildings owned and managed by the Client. Details of the buildings included in this inspection are presented below:

Table 2.1 Building description

Building	Building Description	Approximate Building Age
Project Building	The Project Building is a single storey building constructed from multiple demountable sections constructed of structural insulated panel with external aluminium sheet and a plywood internal sheet. Interior walls are constructed of plywood and plasterboard. Interior ceilings are plywood. Floors are constructed of chipboard.	1990's

The survey was not destructive and was limited to the building(s) listed above, hazardous materials located in inaccessible areas or located in areas that posed an unacceptable risk to health and safety (e.g. live electrical areas, confined spaces, etc.), were not inspected or sampled during the survey.

3 Survey Methodology

3.1 Preliminary

Prior to attendance at the site, a desktop review of existing asbestos registers or related materials and relevant management plans and asbestos or other materials abatement/removal or treatment records, where available, was undertaken.

3.2 Site Inspection

The site inspection was undertaken by a competent person and involved a thorough and systematic walkthrough of the structures and plant. Access was made only where safe access by solid floors, decking, walkways, protected catwalks or ladders was available. Minimal to no disturbance of any equipment was undertaken as part of the survey as all plant, electrical installations, pipe-work and associated equipment were considered live at the time of the survey.

The identification of hazardous materials involved a combination of visual inspection of the accessible areas of the building/structure and the collection of small representative samples, where required. Suspect materials are submitted for analytical confirmation. Where identical suspect materials were detected at different locations, visual confirmation only may have been made rather than additional sample collection.

Where appropriate or required by legislation, observations recorded for known and suspected hazardous materials included details of the:

- Product type
 - Location
 - Condition and extent of damage/deterioration
 - Surface coating/type/treatment
 - Potential for disturbance/accessibility
 - Friability
 - Estimated quantity/amount
-

3.3 Identification and Sample Analysis

3.3.1 *Asbestos Containing Materials (ACM)*

Representative samples of materials suspected to contain asbestos were collected and analysed at WSP Australia's NATA Accredited Laboratory. The identification of asbestos fibres is based on using Polarised Light Microscopy supplemented with Dispersion Staining techniques. This is detailed in Australian Standard 4964-2004 '*Method for the qualitative identification of asbestos in bulk samples*'. Asbestos samples were only collected for analysis where the safety of personnel would not be compromised. Sampling was conducted in accordance with the WSP Australia's in house survey guide.

3.3.2 *Lead-based Paints*

Representative samples of paint suspected to be lead based were collected and analysed at a NATA Accredited Laboratory. Laboratory analysis of lead based paints is used to achieve a reportable weight by weight percentage of lead throughout

the paint layers and is reported against AS/NZS 4361.2:2017, Guide to Hazardous Paint Management, Part 2: Lead paint in residential, public and commercial buildings lead containing paint system greater than 0.1% (w/w) of the dried film.

The analysis of the physical samples is achieved by digestion of the sample for determination of lead content by one of two methods, atomic absorption spectroscopy (AAS) or inductively coupled plasma emission spectrometry (ICP-AES). Collection of lead based paint samples was only conducted where the safety of personnel would not be compromised. Sampling was conducted in accordance with the WSP Australia's in house survey guide and AS/NZS 4361.2:2017, Guide to Hazardous Paint Management, Part 2: Lead paint in residential, public and commercial buildings.

Sampling methodology will consider the various paint coats and record these layers accordingly, these observations will be referred to alongside the analytical sample results to acknowledge that lead paint layers of varying lead content will affect the analytically observed lead weight concentration recorded from the sample. To this end, where multiple lead paint layers have been visually recorded but analytically determined lead percentage of the collective paint layers is below actionable limits, the paint undercoats may still be determined as hazardous due to its dilution in the sample by the non-lead topcoats. Sampling methodology may also consist of the use of a lead paint chemical colorimetric test reagent that can provide an instantaneous result of lead presence within specific layers. This testing will however be used in conjunction with a physical sample to determine the lead concentration as above.

3.3.3 Synthetic Mineral Fibres (SMF) Materials

Generally, our experienced surveyor visually identified and recorded the presence of synthetic mineral fibre products onsite. Where required representative samples of materials suspected to contain SMF were collected and analysed at WSP Australia's in-house NATA Accredited Laboratory. The identification of SMF fibres is based on using Polarised Light Microscopy supplemented with Dispersion Staining techniques.

3.3.4 Polychlorinated Biphenyls (PCBs)

Where access was available, and power was isolated representative examples of accessible light fitting, and other electronic equipment capacitors were recorded. The details of the brand, and model of each capacitor and capacity were recorded and checked against with the ANZECC database of known PCB capacitors and PCB free capacitors.

The Australian and New Zealand Environment Conservation Council 'Polychlorinated Biphenyls Management Plan, November 1996' outlines the National Strategy for the management of PCBs.

Australia banned the importation and the manufacturing of PCBs in the late 1970's.

The document defines PCB materials and wastes as follows:

Table 3.1 PCB Concentration Classification

PCB CONCENTRATION	WASTE CLASSIFICATION
<2 mg/kg	PCB free
2 mg/kg to <50 mg/kg	Non-scheduled PCB material or waste
>50 mg/kg	Scheduled PCB material or waste
>100,000 (10%)	Concentrated PCB material

3.3.5 Ozone Depleting Substances (ODS)

Where access is available items suspected of containing ODS (e.g. air conditioning units, refrigerators, chillers) will be visually inspected and included in the hazardous materials register.

3.4 Collection of Data

Following the hazardous materials inspection survey any subsequent sample analysis, all data collected was tabulated to form a hazardous materials register that includes risk ratings, location, and representative photos.

3.5 Non-destructive survey limitations

Hazardous materials located in inaccessible areas or located in areas that pose an unacceptable risk to health and safety (e.g. live electrical areas), were not inspected or sampled during the survey. Common building locations where access and sampling may be limited or missing are listed below:

- Inside set ceilings, wall cavities or other voids/areas (e.g. fire doors) concealed within a building structure that cannot be accessed without dismantling/demolition
- Roofs, ceiling spaces and other height restricted areas that cannot be accessed without specialised equipment
- Locations behind locked doors, keys/codes not provided by client
- Within confined spaces
- Beneath fixed floor (e.g. vinyl sheeting) coverings. where possible and accessible, carpets were lifted in representative areas.
- Energised services and mechanical plant/equipment, including gas, water and electrical, heater banks and obstructed areas.
- Areas where access would create an unacceptable risk and disruptions to building occupants and operations
- Stored equipment and obstructed areas
- Behind fire seal materials and within penetrations
- Within encased items where dismantling or demolition is required, i.e. fire doors, insulated services or reheat boxes
- To/behind waterproof membranes and sealants and construction joints

3.5.1 Site specific inaccessible areas

The following table summarises inaccessible areas identified during the Site survey.

Table 3.2 Summary of site specific inaccessible areas at time of survey

Inaccessible Areas	Details
No site-specific exclusions	

4 Survey Results

All data generated from the survey was used to create a hazardous materials register (Appendix A) with photographs of site structures and materials (Appendix B and Appendix C), and documented materials. A risk assessment was completed for known and suspected hazardous materials using the risk matrix presented (Appendix D).

This section summarises the findings from the survey.

Table 4.1 Summary of identified or assumed hazardous materials

Stanwell Power Station - Project Building					
Material	Identified	Number of items	Risk Range		
Asbestos					
Friable ACM	No	-	-	to	-
Non-friable ACM	Yes	3	Low	to	Low
Synthetic Mineral Fibres					
Synthetic Mineral Fibres	Yes	3	Low	to	Low
Lead Paint / Lead Dust					
Lead Based Paints	Yes	2	Low	to	Low
Polychlorinated biphenyls (PCBs)					
PCBs	Yes	1	Low	to	Low
Ozone Depleting Substances (ODS)					
ODS	Yes	3	Low	to	Low

Table 4.2 Items requiring remediation

Primary Location	Secondary Location	Material	Condition	Result	Risk Rating	Recommended Management Measures
No high risk items requiring remediation						

5 Survey Recommendations

To ensure that identified hazardous materials are appropriately managed, WSP recommends the following:

5.1 Site specific recommendations

- Recommended management measures for all items identified as requiring immediate action should be actioned as soon as possible. Refer to [Table 4.2](#) for list of all items requiring immediate action.
 - Consider encapsulating yellow paint with lead-free paint to prevent deterioration.
-

5.2 Ongoing management recommendations

- Refer to the asbestos/hazardous materials register and specific management actions to remove/maintain identified hazardous materials to ensure that health and environmental risks are appropriately managed.
- The survey was undertaken using non-destructive methods. There may remain a potential for hazardous materials to be concealed within the building structure(s) and / or plant and equipment, for example fire doors, gaskets, millboard lining to heater banks. Should any suspected hazardous materials be identified onsite a sample of these materials should be collected and tested in a NATA registered laboratory for the presence of hazardous materials.
- Prior to renovation or demolition works a refurbishment/demolition building materials survey should be undertaken by a suitable qualified and experience consultancy, such as WSP. A Refurbishment and/or Demolition Survey is required under the *AS2601 (2001): The Demolition of Structures*.
- Assumed hazardous materials should be treated as hazardous and all requirements for managing and or removing the assumed materials must be followed, until proven otherwise and testing has confirmed that it is not or does not contain a hazardous substance.
- Inaccessible areas should be assumed to contain hazardous materials and managed accordingly until such time that this can be assessed by a competent person.
- Activities near hazardous materials should be restricted to minimise the potential for damaging hazardous materials.
- Ensure a current copy of the hazardous materials register is kept on Site, and readily available to personnel, employees and any contractors likely to encounter hazardous materials.
- Apply asbestos warning labels to ACM to ensure ACM is readily identifiable and the risks appropriately managed.
- Review the hazardous materials register as per state specific regulatory requirement, or whenever:
 - Hazardous materials are removed from, disturbed, sealed/enclosed at the workplace,
 - the register is no longer adequate for managing hazardous material risks,
 - requested by a representative of the Client.
- Preparation of a Hazardous materials/Asbestos management plan to be implemented and monitored to ensure identified hazardous materials are being managed effectively. It is a legislative requirement to have an Asbestos Management Plan (AMP), this report does not satisfy the requirements of an AMP.
 - The Hazardous material management plan should include information regarding - Roles and responsibilities, Prohibitions, Management plan and register reviews, Labelling, Demolition and refurbishment works, Remediation works, Incidents and emergencies, and Record keepings.

- Ensure that appropriately qualified contractors are engaged to perform any works associated with ACM, including maintenance, repairs and removal works. For removal works, contractors must be appropriately licenced and complete the works in accordance with relevant legislation and National Codes of Practice (Appendix H).
- **Prior to demolition or refurbishment works**, engage a competent person to undertake a destructive hazardous materials survey of the premises as per relevant Legislation, Codes of Practice and Australian Standards.
- **Provide Awareness training** to staff and site personnel to inform them of how to work safely alongside the identified hazardous building materials in accordance with the requirements of relevant Legislation and Codes of Practice.
- All quantities of materials are approximate measurements. An independent qualified surveyor/estimator should be engaged to quantify the quantities provided prior to any refurbishment or demolition works. It is the responsibility of third parties to fully investigate and ensure that any information and/or reports prepared by WSP are suitable for their specific objectives.
- If required WSP can facilitate and assist with any of the above.

5.3 Asbestos General Management Guidelines

WSP Australia has provided the following recommendations as a general guide for the safe removal of asbestos containing materials in accordance with the legislative requirements.

If friable asbestos is identified the following is recommended:

- Access be restricted to areas where friable asbestos is present, and a management plan be implemented to control the risk of human exposure. Where practicable, positively identified asbestos containing materials should be labelled to indicate the presence of asbestos.
- Any persons wishing to access areas where presumed friable asbestos exists are to undertake a suitable and sufficient Risk Assessment prior to doing so, the results of which may include the use of appropriate Personal Protective Equipment (PPE) such as disposable coveralls and respiratory protection.
- Consideration should be given to engaging a qualified and experienced asbestos consultant to conduct a program of asbestos air monitoring in/around area containing friable asbestos to document airborne asbestos levels and help assess the exposure risk to occupants.
- Consideration should be given to engaging a qualified and experienced asbestos consultant to conduct a program of settled dust sampling/analysis to more accurately assess the extent of asbestos contamination that may be present.

If non-friable asbestos such as fibre cement sheeting (flat and corrugated), pipes and visually identified electrical distribution boards are identified, the following is recommended:

- All damaged / poor condition ACM should have access restricted and make safe works conducted to seal exposed damaged areas. A management plan is to be implemented to control the risk of human exposure to damaged asbestos materials. Where practicable, positively identified asbestos containing materials should be labelled to indicate the presence of asbestos.
- All non-friable ACM in an in-tact condition may remain in-situ provided they are not drilled, ground or otherwise disturbed. If damaged, broken pieces are to be removed as soon as practicable. As part of good ongoing management we recommend regular inspections of ACM left in-situ to check the condition of these materials.
- Any areas of the workplace that contain ACM including plant, equipment and components should be signposted with appropriate warning signs to ensure that asbestos is not unknowingly disturbed without the correct precautions being taken. These signs should be placed at all the main entrances to the work areas where asbestos is present and should conform with *Australian Standard 1319-1994 Safety Signs for the Occupational Environment*.
- All removal work and asbestos disposal should be carried out in accordance with the applicable legislation (Appendix H).

- All fibre air monitoring shall be carried out by a competent person or licenced asbestos assessor with NATA accreditation in accordance with National Occupational Health and Safety Commission (NOHSC), Guidance Note on the Membrane Filter Method for Estimating Airborne Asbestos Fibres [NOHSC:3003(2005)], NOHSC, Australia.
- A clearance inspection of the work area shall be undertaken at the completion of the asbestos removal works by a licenced asbestos assessor.

5.4 General Lead Paint / Dust Management

If lead containing paints and / or lead in dust are identified the following management controls are recommended:

- Lead paint in poor, flaking condition must be remediated as soon as reasonably practicable.
- Paint in good condition may remain in situ provided it is not disturbed and maintained in a good condition.

All lead paint removal/stabilisation must be undertaken in accordance with AS/NZS 4361.2:2017, *Guide to Hazardous Paint Management, Part 2: Lead paint in residential, public and commercial buildings*. It should be noted that this document does not replace AS/NZS 4361.2:2017. Rather it provides general advice to assist with the creation of a site-specific document to facilitate the safe removal/stabilisation of lead paint works.

This document provides general guidance for the removal of lead based paint systems via various methods commonly employed such as the use of a chemical strippers and the stabilisation of flaking lead based paints via scraping and wet sanding. Reference is made to a particular brand name of chemical stripper; however, this advice does not replace information provided by the manufacturer and one should always refer to the products guidance and relevant Australian legislation, standards, SDS and guidance material.

In addition, it provides guidance for decontamination procedures. Disposal requirements and provisions for lead air monitoring and clearance inspections.

While it may not be practicable to remove lead based paints, it is important to ensure they are appropriately managed to minimise risks. To achieve this WSP recommends the following management measures be implemented in relation to the handling of any suspected lead based paints:

- Do not disturb lead based paints. If activities are likely to disturb lead based paints, their use should only be permitted with appropriate controls in place.
- Keep children and pets away from lead based paints and make sure they don't eat or play with paint debris.
- Do not burn lead paint or timber that is coated with paint containing lead.
- Ensure staff are aware of the safety issues associated with lead and encourage good hygiene practices.
- Air monitoring can be considered to provide assurance to regulators and personnel that activities are not generating airborne lead dust.

Should any lead exposure be suspected, health surveillance monitoring can be undertaken. If this is necessary, having baseline health surveillance results (blood lead testing) for comparison purposes would be beneficial and this should be considered in consultation with the occupational hygienist prior to commencing any refurbishment / demolition activities.

5.5 SMF Management Guidelines

All SMF removal should be done in accordance with the National Occupational Health and Safety Commission *National Code of Practice for the Safe Use of Synthetic Mineral Fibres* [NOHSC: 2006 (1990)]. Some of the practices recommended are as follows:

- The work area should be designated by using barricade tape and signs where workable. Persons not involved in the removal should not be within 3 metres of the designated area.
- Waste shall be placed in plastic bags or other containers which prevent fibre and/or dust emission and disposed of in accordance with local waste disposal authority requirements.

- PPE including goggles, half-face P2 respirator, gloves, long sleeve and loose fitting clothing should be worn.
-

5.6 PCB Management Guidelines

To manage the potential risks associated with PCBs should any be identified, WSP recommends the following:

- A certified and experienced electrician, aware of the hazards associated with PCBs and able to identify suspect PCB containing materials, should be used to isolate electricity and advise on the removal requirements.
 - If any suspect PCB containing materials are suspected, the presence of PCBs should be further assessed against the 1997 ANZECC *Identification of PCB-Containing Capacitors* information Booklet to identify PCB-containing capacitors.
 - If PCB containing materials are confirmed to exist and works are to occur within the vicinity which will may result in disturbance of the PCB, the appropriate PPE (disposable suits, nitrile gloves, full face shield and hair protection) should be worn in case materials (e.g. capacitors) are damaged and potentially leaking PCBs.
 - Any leaking or damaged PCB containing materials pose an increased risk to human health, consultation should be sought for suitable control measures.
-

5.7 ODS Management Guideline

- Identified ODS units will require disposal by a licensed contractor, which is to be in accordance with the Ozone Protection and Synthetic Greenhouse Gas Management Amendment Regulation 2024.

Appendix A

Hazardous Materials Register



A1 Hazardous Materials Register

A1.1 Asbestos containing Materials

Project Building														
Item No.	Primary location / room	Application / specific location in room	Material	Sample number	Result	Estimated quantity	Labelled	Surface treatment	Friability	Condition	Disturbance potential	Overall risk rating	Comments / management recommendations	Photo reference
1.	Level 1 - West Male Toilet	Urinal noise dampening sheet	Bituminous material	Visual Observation	Asbestos Presumed	2 m²	No	Scaled	Non-Friable	Good	Low	Low	Leave in situ and manage. Further investigation required before removal.	260589
2.	Level 1 - East Male Toilet	Urinal noise dampening sheet	Bituminous material	Visual Observation	Asbestos Presumed	2 m²	No	Scaled	Non-Friable	Good	Low	Low	Leave in situ and manage. Further investigation required before removal.	260591
3.	Level 1 - East Female Toilet	Urinal noise dampening sheet behind infill.	Bituminous material	Visual Observation	Asbestos Presumed	2 m²	No	Scaled	Non-Friable	Good	Low	Low	Leave in situ and manage. Further investigation required before removal.	260592
4.	Level 1 - West and East Male, and East Female Toilets	Floor lining	Vinyl sheeting	WSP-367493	Not Detected	5.5 m²	-	-	-	-	-	No Asbestos	No Action Required	260598
5.	Level 1 - West Male Toilet - Shower	Wall & ceiling linings	Fibre cement sheeting	WSP-367492	Not Detected	20 m²	-	-	-	-	-	No Asbestos	No Action Required	260622
6.	Level 1 - All external	Window Sealant	Mastic	WSP-367490	Not Detected	20	-	-	-	-	-	No Asbestos	No Action Required	260612
7.	Level 1 - Training Room West	East elevation wall	Fibre cement sheeting	Ref: WSP-367495	Not Detected	14 m²	-	-	-	-	-	No Asbestos	No Action Required	260585

Project Building														
Item No.	Primary location / room	Application / specific location in room	Material	Sample number	Result	Estimated quantity	Labelled	Surface treatment	Friability	Condition	Disturbance potential	Overall risk rating	Comments / management recommendations	Photo reference
8.	Level 1 - Training Room West	North elevation wall	Fibre cement sheeting	WSP-367495	Not Detected	21 m²	-	-	-	-	-	No Asbestos	No Action Required	260590
9.	Level 1 - South Office	West elevation wall	Fibre cement sheeting	Ref: WSP-367495	Not Detected	14 m²	-	-	-	-	-	No Asbestos	No Action Required	260593
10.	Level 1 - Stakeholder Engagement	Sout elevation wall	Fibre cement sheeting	Ref: WSP-367495	Not Detected	21 m²	-	-	-	-	-	No Asbestos	No Action Required	260594
11.	Level 1 - Ramp access	Skirting	Fibre cement sheeting	WSP-367499	Not Detected	10 m²	-	-	-	-	-	No Asbestos	No Action Required	260595

A1.2 Lead Paint

Project Building											
Item No.	Primary location / room	Application / specific location in room	Paint Colour if appropriate	Sample number	Result	Estimated quantity	Condition	Disturbance potential	Overall risk rating	Comments / management recommendations	Photo reference
1.	Level 1 - Throughout	External and bathroom doors	Yellow	Lead Paint Sample 367494	LBP Detected 4.2%w/w	15 items	Good	Low	Low Risk	Leave in situ and manage.	LBP-40236
2.	Level 1 - External frame	Steel support beams	Cream	Lead Paint Sample 367497	LBP Detected 0.43%w/w	~100 ln m	Fair	Low	Low Risk	Leave in situ and manage.	LBP-40237

Project Building											
Item No.	Primary location / room	Application / specific location in room	Paint Colour if appropriate	Sample number	Result	Estimated quantity	Condition	Disturbance potential	Overall risk rating	Comments / management recommendations	Photo reference
3.	Level 1 - Breakout	Internal Wall	White	Lead Paint Sample 367489	LBP Not Detected <0.01%w/w	Unknown	-	-	-	-	LBP-40234
4.	Level 1 - Office	Internal Wall	White	Lead Paint Sample 367491	LBP Not Detected <0.01%w/w	Unknown	-	-	-	-	LBP-40235
5.	Level 1 - Conference	Internal Wall	White	Lead Paint Sample 367496	LBP Not Detected <0.01%w/w	Unknown	-	-	-	-	LBP-40238
6.	Level 1 - External AHUs	Air Handling Units	Brown	Lead Paint Sample 367498	LBP Not Detected <0.01%w/w	Unknown	-	-	-	-	LBP-40239

A1.3 Synthetic Mineral Fibre

Project Building										
Item No.	Primary location / room	Application / specific location in room	Sample number	Result	Estimated quantity	Condition	Disturbance potential	Overall risk rating	Comments / management recommendations	Photo reference
1.	Level 1 - Throughout	Supply air ductwork	Visual Observation	Presumed	<100 lin m	Good	Low	Low Risk	Leave in situ and manage.	SMF-40477
2.	Level 1 - External	Air handling units	Visual Observation	Presumed	8 units	Good	Low	Low Risk	Leave in situ and manage.	SMF-40478

Project Building										
Item No.	Primary location / room	Application / specific location in room	Sample number	Result	Estimated quantity	Condition	Disturbance potential	Overall risk rating	Comments / management recommendations	Photo reference
3.	Level 1 - Throughout	Hot water systems	Visual Observation	Presumed	6 units	Good	Low	Low Risk	Leave in situ and manage.	SMF-40479

A1.4 Polychlorinated Biphenyls (PCB)

Project Building										
Item No.	Primary location / room	Application/ unit description (make/brand/Type Serial number)	Sample number	Result	Estimated quantity	Condition	Disturbance potential	Overall risk rating	Comments / management recommendations	Photo reference
1.	Level 1 - Throughout	Interior fluorescent light fitting - capacitor	Visual Observation	Non-scheduled PCB material or waste	>100 fittings	Good	Low	Low Risk	Further investigation required before disposal.	PCB-29946

A1.5 Ozone Depleting Substances (ODS)

Project Building										
Item No.	Primary location / room	Application / specific location in room	Sample number	Result	Estimated quantity	Condition	Disturbance potential	Overall risk rating	Comments / management recommendations	Photo reference
1.	Level 1 - External	Air handling units... R-134a 1,1,1,1,2-Tetrafluoroethane	Visual Observation	Presumed	8 units	Good	Low	Low Risk	Leave and maintain in a good and stable condition. Remove and dispose of appropriately prior to demolition / refurbishment.	ODS-29373
2.	Level 1 - Throughout	Refrigerators... R-134a 1,1,1,1,2-Tetrafluoroethane	Visual Observation	Presumed	6 units	Good	Low	Low Risk	Leave and maintain in a good and stable condition. Remove and dispose of appropriately prior to demolition / refurbishment.	ODS-29374
3.	Level 1 - Throughout	Split system & Room AC... R-134a 1,1,1,1,2-Tetrafluoroethane	Visual Observation	Presumed	3 units	Good	Low	Low Risk	Leave and maintain in a good and stable condition. Remove and dispose of appropriately prior to demolition / refurbishment.	ODS-29370

Notes:
 Surveyor Name: Brett Kriewaldt
 Date survey undertaken: 02 March 2026

Appendix B

Site/Building Photographs



B1 Site/ Building Photographs

Project Building



Appendix C

Material Photographs



C1 Photographs

C1.1 Asbestos Containing Materials

ASBESTOS - Assumed			
Photo Ref	260589	Sample No	Visual Observation
Building	Project Building		
Level	Level 1		
Room	West Male Toilet		
Application	Urinal noise dampening sheet		
Material	Bituminous material		
Risk Rating	Low		



ASBESTOS - Assumed			
Photo Ref	260591	Sample No	Visual Observation
Building	Project Building		
Level	Level 1		
Room	East Male Toilet		
Application	Urinal noise dampening sheet		
Material	Bituminous material		
Risk Rating	Low		




ASBESTOS - Assumed			
Photo Ref	260592	Sample No	Visual Observation
Building	Project Building		
Level	Level 1		
Room	East Female Toilet		
Application	Urinal noise dampening sheet		
Material	Bituminous material		
Risk Rating	Low		




C1.2 Non-Asbestos Containing materials


NON-ASBESTOS CONTAINING MATERIAL			
Photo Ref	260585	Sample No	Ref: WSP-367495
Building	Project Building		
Level	Level 1		
Room	Training Room West		
Application	East elevation wall		
Material	Fibre cement sheeting		
Risk Rating	No Asbestos		



NON-ASBESTOS CONTAINING MATERIAL			
Photo Ref	260590	Sample No	WSP-367495
Building	Project Building		
Level	Level 1		
Room	Training Room West		
Application	North elevation wall		
Material	Fibre cement sheeting		
Risk Rating	No Asbestos		



NON-ASBESTOS CONTAINING MATERIAL			
Photo Ref	260593	Sample No	Ref: WSP-367495
Building	Project Building		
Level	Level 1		
Room	Sout Office		
Application	West elevation wall		
Material	Fibre cement sheeting		
Risk Rating	No Asbestos		



NON-ASBESTOS CONTAINING MATERIAL			
Photo Ref	260594	Sample No	Ref: WSP-367495
Building	Project Building		
Level	Level 1		
Room	Stakeholder Engagement		
Application	South elevation wall		
Material	Fibre cement sheeting		
Risk Rating	No Asbestos		



NON-ASBESTOS CONTAINING MATERIAL			
Photo Ref	260595	Sample No	WSP-367499
Building	Project Building		
Level	Level 1		
Room	External ramp access		
Application	Skirting		
Material	Fibre cement sheeting		
Risk Rating	No Asbestos		





NON-ASBESTOS CONTAINING MATERIAL			
Photo Ref	260598	Sample No	WSP-367493
Building	Project Building		
Level	Level 1		
Room	Male & Female Bathrooms		
Application	Floor lining		
Material	Vinyl sheeting		
Risk Rating	No Asbestos		






NON-ASBESTOS CONTAINING MATERIAL			
Photo Ref	260612	Sample No	WSP-367490
Building	Project Building		
Level	Level 1		
Room	External windows		
Application	Window Sealant		
Material	Mastic		
Risk Rating	No Asbestos		





NON-ASBESTOS CONTAINING MATERIAL			
Photo Ref	260622	Sample No	WSP-367492
Building	Project Building		
Level	Level 1		
Room	West Male Toilet - Shower		
Application	Wall lining		
Material	Fibre cement sheeting		
Risk Rating	No Asbestos		





C1.3 Lead Based Paints

LBP DETECTED			
Photo Ref	LBP-40236	Sample No	Lead Paint Sample 367494
Building	Project Building		
Level	Level 1		
Room	Throughout		
Application	Yellow Doors		
Risk Rating	Low Risk		




LBP DETECTED			
Photo Ref	LBP-40237	Sample No	Lead Paint Sample 367497
Building	Project Building		
Level	Level 1		
Room	External		
Application	Steel frame		
Risk Rating	Low Risk		




LBP NOT DETECTED			
Photo Ref	LBP-40234	Sample No	Lead Paint Sample 367489
Building	Project Building		
Level	Level 1		
Room	Breakout		
Application	Internal Wall		
Risk Rating	-		



LBP NOT DETECTED			
Photo Ref	LBP-40235	Sample No	Lead Paint Sample 367491
Building	Project Building		
Level	Level 1		
Room	Office		
Application	Internal Wall		
Risk Rating	-		



LBP NOT DETECTED			
Photo Ref	LBP-40238	Sample No	Lead Paint Sample 367496
Building	Project Building		
Level	Level 1		
Room	Office		
Application	Internal Wall		
Risk Rating	-		





LBP NOT DETECTED			
Photo Ref	LBP-40239	Sample No	Lead Paint Sample 367498
Building	Project Building		
Level	Level 1		
Room	External		
Application	Air Handling Units		
Risk Rating	-		





C1.4 Synthetic Mineral Fibres

SYNTHETIC MINERAL FIBRE			
Photo Ref	SMF-40479	Sample No	Visual Observation
Building	Project Building		
Level	Level 1		
Room	Throughout		
Application	Hot water systems		
Risk Rating	Low Risk		






SYNTHETIC MINERAL FIBRE			
Photo Ref	SMF-40478	Sample No	Visual Observation
Building	Project Building		
Level	Level 1		
Room	External		
Application	Air handling unit		
Risk Rating	Low Risk		






SYNTHETIC MINERAL FIBRE			
Photo Ref	SMF-40477	Sample No	Visual Observation
Building	Project Building		
Level	Level 1		
Room	Throughout		
Application	Supply air ductwork		
Risk Rating	Low Risk		





C1.5 Polychlorinated Biphenyls

NON-SCHEDULED PCB MATERIAL OR WASTE			
Photo Ref	PCB-29946	Sample No	Visual Observation
Building	Project Building		
Room	Throughout		
Application	Interior fluorescent light fitting - capacitor		
Material	Light Fixture		
Risk Rating	Low Risk		





C1.6 Ozone Depleting Substances

ODS			
Photo Ref	ODS-29374	Sample No	Visual Observation
Building	Project Building		
Room	Throughout		
Application	Refrigerators		
Material	R-134a 1,1,1,1,2-Tetrafluoroethane		
Risk Rating	Low Risk		





ODS			
Photo Ref	ODS- 29373	Sample No	Visual Observation
Building	Project Building		
Room	External		
Application	Air handling units		
Material	R-134a 1,1,1,1,2-Tetrafluoroethane		
Risk Rating	Low Risk		



ODS			
<i>Photo Ref</i>	ODS-29370	<i>Sample No</i>	Visual Observation
<i>Building</i>	Project Building		
<i>Room</i>	Throughout		
<i>Application</i>	Split system and room AC		
<i>Material</i>	R-134a 1,1,1,1,2-Tetrafluoroethane		
<i>Risk Rating</i>	Low Risk		




Appendix D

Site Map/s







Figure 1: Sample Location Plan

Site Location: Project Building		Project Number: PS232156	
Client: Stanwell Corporation LTD		Date: 3/2/2026	
Prepared By: Brett Kriewaldt		Reviewed By: Brett Kriewaldt	
AU0067565.2156-WSP-BNE-OHH-REP-001 RevA			

Legend:

Not to Scale – A4 Print Size



Source: Stanwell Corporation LTD



Appendix E

NATA Laboratory Analytical Reports





Certificate of Analysis

Accredited for compliance with
ISO/IEC:17025 (No. 17199)

Client: Brenton Jensen

Stanwell Corporation Limited
brenton.jensen@stanwell.com
Tarong Power Station
PO Box 15
Nanango QLD 4615

Our Ref: BRI-PS232156-205906

Client Ref: PS232156

Location: Switchyard Road Stanwell QLD 4702

Sampled: Brett Kriewaldt on 2 March 2026

Received: 4 March 2026

Methodology: Qualitative identification of asbestos fibres in bulk and soil samples by polarised light microscopy, including dispersion staining and trace analysis, in accordance with AS 4964 (2004) Method for the qualitative identification of asbestos in bulk samples, and in-house procedure LP3.

Lab No.	Sample ID	Location	Description	Approximate Size	Identification Type
001	WSP-367490	Internal Ground - Window - Mastic	Mastic	<1 g	NAD
002	WSP-367492	Internal Ground - South Male Toilet - Showers - Fibre Cement Sheet	Mastic	1 g	OF, NAD
003	WSP-367493	Internal Ground - South Male Toilet - Vinyl Sheet	Vinyl Sheet	<1 g	NAD
004	WSP-367495	Internal Ground - Training - Fibre Cement Sheet	Fibre Cement Sheet	1 g	OF, NAD
005	WSP-367499	External Ground - Ramp - Fibre Cement Sheet	Fibre Cement Sheet	7 g	OF, NAD

Analysed by: Melanie Reed
9 March 2026

Analysed at: WSP Sydney Laboratory
Level 28, 680 George Street Sydney NSW 2000

Legend:

- NAD - No Asbestos Detected
- CH - Chrysotile Asbestos Detected
- A - Amosite Asbestos Detected
- C - Crocidolite Asbestos Detected
- OF - Organic Fibres Detected

Approved by: Holly Kitamura

9 March 2026

Notes:

If no asbestos is detected in vinyl tiles, mastics, sealants, epoxy resins and ore samples, then confirmation by another independent analytical technique is advised due to the nature of the samples.

The results contained within this report relate only to the sample(s) analysed.

Sampling is not covered by the scope of accreditation.

Limitations:

WSP has prepared the Certificate of Analysis solely for the benefit of the Client. WSP is not obliged to update the Certificate after its issue to the Client, regardless of any new event, change in standards or circumstance. To the fullest extent permitted by law, WSP, its related bodies corporate, officers, employees, agents and affiliates will not be liable for any kind of loss, cost, expense or damage whatsoever, suffered on incurred or likely to be suffered and incurred by a third party, including, economic loss, loss of profit or revenue, loss of opportunity to earn profit, loss of production, loss of contract, increased operational costs, loss of business opportunity, site depredation costs, business interruption, of any kind.

WSP Australia P/L QLD
900 Ann Street
Fortitude Valley
QLD 4006



NATA Accredited
Accreditation Number 1261
Site Number 18217

Accredited for compliance with ISO/IEC 17025 – Testing
NATA is a signatory to the ILAC Mutual Recognition
Arrangement for the mutual recognition of the
equivalence of testing, medical testing, calibration,
inspection, proficiency testing scheme providers and
reference materials producers reports and certificates.

Attention: **Brett Kriewaldt**

Report **1331169-S**
Project name **PS232156**
Received Date **Mar 05, 2026**

Client Sample ID			367489	367491	367494	367496
Sample Matrix			Paint	Paint	Paint	Paint
Eurofins Sample No.			B26- Ma0014617	B26- Ma0014618	B26- Ma0014619	B26- Ma0014620
Date Sampled			Mar 02, 2026	Mar 02, 2026	Mar 02, 2026	Mar 02, 2026
Test/Reference	LOR	Unit				
Lead (% w/w)	0.01	%	< 0.01	< 0.01	4.2	< 0.01

Client Sample ID			367497	367498
Sample Matrix			Paint	Paint
Eurofins Sample No.			B26- Ma0014621	B26- Ma0014622
Date Sampled			Mar 02, 2026	Mar 02, 2026
Test/Reference	LOR	Unit		
Lead (% w/w)	0.01	%	0.43	< 0.01

Sample History

Where samples are submitted/analysed over several days, the last date of extraction is reported.

If the date and time of sampling are not provided, the Laboratory will not be responsible for compromised results should testing be performed outside the recommended holding time.

Description

Lead (% w/w)

Testing Site

Sydney

Extracted

Mar 05, 2026

Holding Time

6 Months

- Method: LTM-MET-3040 Metals in Waters Soils & Sediments by ICP-MS



web: www.eurofins.com.au
email: EnviroSales@eurofinsanz.com

Melbourne
6 Monterey Road
Dandenong South
VIC 3175
+61 3 8564 5000
NATA# 1261
Site# 1254

Geelong
19/8 Lewalan Street
Grovedale
VIC 3216
+61 3 8564 5000
NATA# 1261
Site# 25403

Sydney
179 Magowar Road
Girraween
NSW 2145
+61 2 9900 8400
NATA# 1261
Site# 18217

Newcastle
1/2 Frost Drive
Mayfield West
NSW 2304
+61 2 4968 8448
NATA# 1261
Site# 25079

Canberra
Unit 1,2 Dacre Street
Mitchell
ACT 2911
+61 2 6113 8091
NATA# 1261
Site# 25466

Brisbane
1/21 Smallwood Place
Murarrie
QLD 4172
+61 7 3902 4600
NATA# 1261
Site# 20794 & 2780

Hobart
282A Argyle Street
North Hobart
TAS 7000
+61 3 8564 5000
NATA# 1261
Site# 1254

Perth
46-48 Banksia Road
Welshpool
WA 6106
+61 8 6253 4444
NATA# 2377
Site# 2370 & 2554

Company Name: WSP Australia P/L QLD
Address: 900 Ann Street
Fortitude Valley
QLD 4006

Project Name: PS232156

Order No.: PS232156-101
Report #: 1331169
Phone: 07 3218 2222
Fax: 07 3831 4223

Received: Mar 5, 2026 11:50 AM
Due: Mar 12, 2026
Priority: 5 Day
Contact Name: Brett Kriewaldt

Eurofins Analytical Services Manager : Ryan Gilbert

Sample Detail

Lead (% w/w)

Sydney Laboratory - NATA # 1261 Site # 18217

X

External Laboratory

No	Sample ID	Sample Date	Sampling Time	Matrix	LAB ID	
1	367489	Mar 02, 2026		Paint	B26-Ma0014617	X
2	367491	Mar 02, 2026		Paint	B26-Ma0014618	X
3	367494	Mar 02, 2026		Paint	B26-Ma0014619	X
4	367496	Mar 02, 2026		Paint	B26-Ma0014620	X
5	367497	Mar 02, 2026		Paint	B26-Ma0014621	X
6	367498	Mar 02, 2026		Paint	B26-Ma0014622	X

Test Counts

6

Internal Quality Control Review and Glossary

General

1. Laboratory QC results for Method Blanks, Duplicates, Matrix Spikes, and Laboratory Control Samples follow guidelines delineated in the National Environment Protection (Assessment of Site Contamination) Measure 1999, as amended May 2013. They are included in this QC report where applicable. Additional QC data may be available on request.
2. Unless otherwise stated, all soil/sediment/solid results are reported on a dry weight basis.
3. Unless otherwise stated, all biota/food results are reported on a wet weight basis on the edible portion.
4. For CEC results where the sample's origin is unknown or environmentally contaminated, the results should be used advisedly.
5. Actual LORs are matrix dependent. Quoted LORs may be raised where sample extracts are diluted due to interferences.
6. Results are uncorrected for matrix spikes or surrogate recoveries except for PFAS compounds where annotated.
7. SVOC analysis on waters is performed on homogenised, unfiltered samples unless noted otherwise.
8. Samples were analysed on an 'as received' basis.
9. Information identified in this report with **blue** colour indicates data provided by customers that may have an impact on the results.
10. This report replaces any interim results previously issued.

Holding Times

Please refer to the 'Sample Preservation and Container Guide' for holding times (QS3001).

For samples received on the last day of holding time, notification of testing requirements should have been received at least 6 hours before sample receipt deadlines as stated on the SRA.

If the Laboratory did not receive the information in the required timeframe, and despite any other integrity issues, suitably qualified results may still be reported.

Holding times apply from the sampling date; therefore, compliance with these may be outside the laboratory's control.

For VOCs containing vinyl chloride, styrene and 2-chloroethyl vinyl ether, the holding time is seven days; however, for all other VOCs, such as BTEX or C6-10 TRH, the holding time is 14 days.

Units

mg/kg: milligrams per kilogram	mg/L: milligrams per litre	ppm: parts per million
µg/L: micrograms per litre	ppb: parts per billion	%: Percentage
org/100 mL: Organisms per 100 millilitres	NTU: Nephelometric Turbidity Units	MPN/100 mL: Most Probable Number of organisms per 100 millilitres
CFU: Colony Forming Unit	Colour: Pt-Co Units (CU)	

Terms

APHA	American Public Health Association
CEC	Cation Exchange Capacity
COC	Chain of Custody
CP	Client Parent - QC was performed on samples pertaining to this report
CRM	Certified Reference Material (ISO17034) - reported as percent recovery.
Dry	Where moisture has been determined on a solid sample, the result is expressed on a dry weight basis.
Duplicate	A second piece of analysis from the same sample and reported in the same units as the result to show comparison.
LOR	Limit of Reporting.
LCS	Laboratory Control Sample - reported as percent recovery.
Method Blank	In the case of solid samples, these are performed on laboratory-certified clean sands and in the case of water samples, these are performed on de-ionised water.
NCP	Non-Client Parent - QC performed on samples not pertaining to this report, QC represents the sequence or batch that client samples were analysed within.
RPD	Relative Percent Difference between two Duplicate pieces of analysis.
SPIKE	Addition of the analyte to the sample and reported as percentage recovery.
SRA	Sample Receipt Advice
Surr - Surrogate	The addition of a similar compound to the analyte target is reported as percentage recovery. See below for acceptance criteria.
TBTO	Tributyltin oxide (<i>bis</i> -tributyltin oxide) - individual tributyltin compounds cannot be identified separately in the environment; however, free tributyltin was measured, and its values were converted stoichiometrically into tributyltin oxide for comparison with regulatory limits.
TCLP	Toxicity Characteristic Leaching Procedure
TEQ	Toxic Equivalency Quotient or Total Equivalence
QSM	US Department of Defense Quality Systems Manual Version 6.0
US EPA	United States Environmental Protection Agency
WA DWER	Sum of PFBA, PFPeA, PFHxA, PFHpA, PFOA, PFBS, PFHxS, PFOS, 6:2 FTSA, 8:2 FTSA

QC - Acceptance Criteria

The acceptance criteria should only be used as a guide and may be different when site-specific Sampling Analysis and Quality Plan (SAQP) have been implemented.

RPD Duplicates: Global RPD Duplicates Acceptance Criteria is ≤30%; however, the following acceptance guidelines are equally applicable:

Results <10 times the LOR:	No Limit
Results between 10-20 times the LOR:	RPD must lie between 0-50%
Results >20 times the LOR:	RPD must lie between 0-30%

NOTE: pH duplicates are reported as a range, not as RPD

Surrogate Recoveries: Recoveries must lie between 20-130% for Speciated Phenols & 50-150% for PFAS. SVOCs recoveries 20 – 150%, VOC recoveries 50 – 150%

PFAS field samples containing surrogate recoveries above the QC limit designated in QSM 6.0, where no positive PFAS results have been reported or reviewed, and no data was affected.

QC Data General Comments

1. Where a result is reported as less than (<), higher than the nominated LOR, this is due to either matrix interference, extract dilution required due to interferences or contaminant levels within the sample, high moisture content or insufficient sample provided.
2. Duplicate data shown within this report that states the word "BATCH" is a Batch Duplicate from outside of your sample batch but within the laboratory sample batch at a 1:10 ratio. The Parent and Duplicate data shown are not data from your samples.
3. pH and Free Chlorine analysed in the laboratory - Analysis on this test must begin within 30 minutes of sampling. Therefore, laboratory analysis is unlikely to be completed within holding time. Analysis will begin as soon as possible after sample receipt.
4. Recovery Data (Spikes & Surrogates) - where chromatographic interference does not allow the determination of recovery, the term "INT" appears against that analyte.
5. For Matrix Spikes and LCS results, a dash "-" in the report means that the specific analyte was not added to the QC sample.
6. Duplicate RPDs are calculated from raw analytical data; thus, it is possible to have two sets of data.

Quality Control Results

Test	Units	Result 1			Acceptance Limits	Pass Limits	Qualifying Code
Method Blank							
Lead (% w/w)	%	< 0.01			0.01	Pass	

Comments

Sample Integrity

Custody Seals Intact (if used)	N/A
Attempt to Chill was evident	N/A
Sample correctly preserved	Yes
Appropriate sample containers have been used	Yes
Sample containers for volatile analysis received with minimal headspace	Yes
Samples received within HoldingTime	Yes
Some samples have been subcontracted	No

Authorised by:

Jacinta Baker
Mickael Ros

Analytical Services Manager
Senior Analyst-Metal



Glenn Jackson
Managing Director

Final Report – this report replaces any previously issued Report

- Indicates Not Requested

* Indicates NATA accreditation does not cover the performance of this service

Measurement uncertainty of test data is available on request or please [click here](#).

Eurofins shall not be liable for loss, cost, damages or expenses incurred by the client, or any other person or company, resulting from the use of any information or interpretation given in this report. In no case shall Eurofins be liable for consequential damages including, but not limited to, lost profits, damages for failure to meet deadlines and lost production arising from this report. This document shall not be reproduced except in full and relates only to the items tested. Unless indicated otherwise, the tests were performed on the samples as received.

Appendix F

Risk Matrix



F1 Risk Matrix

The asbestos risk assessment looks at elements of the material to assess the ability to release fibres and exposure potential, to provide some guidance on action for managing.

POTENTIAL TO BE DISTURBED

This assessment considers the likelihood the material may be disturbed during typical occupancy, and work practices such as maintenance works, and as well the proximity of the material to occupants. An understanding of the work practices at the workplace are normally required for detailed assessment.

Score	Potential to be disturbed
High (3)	High level of or repeated disturbance potential and or easily disturbed/accessible.
Medium (2)	Periodic disturbance potential and, or occasionally likely to be disturbed/accessible
Low (1)	Rare or low disturbance potential, usually inaccessible and, or unlikely to be disturbed/accessible

CONDITION

This assesses the extent of damage or deterioration.

Score	Condition description
Poor (3)	High damaged or delamination of materials. Obvious damage or deterioration, dust/contamination. Friable asbestos not encapsulated.
Fair (2)	Medium damage or minor damage or deterioration, not sealed/encapsulated.
Good (1)	No obvious damage or deterioration, secured in place, sealed/encapsulated.
Unknown (1)	No access to assess condition.

FRIABILITY

Classification of the asbestos material.

Score	Friability Descriptor
Friable (1)	Material that; (A) is in a powder form or that can be crumbled, pulverised or reduced to powder by hand pressure when dry, and (B) contains asbestos.
Non-friable (0)	Material containing asbestos that is not friable asbestos, including material containing asbestos fibres reinforced with a bonding compound.

SURFACE TREATMENT

The surface type of the material

Type	Description
Sealed/Encapsulated (1)	Painted, overcoat
Unsealed (1-3 dependant on material)	Exposed "raw" material
Enclosed (1)	Boxed or covered (physical barrier)
Composite Materials (0)	Reinforced, resins and floor tiles
Unknown (3)	No access to assess surface treatment

RISK MATRIX TABLE

Overall likelihood of airborne fibres and exposure

Material Condition	Disturbance Potential		
	High (3)	Medium (2)	Low (1)
Poor (3)	>6	5	4
Fair (2)	5	4	3
Good / Unknown (1)	4	3	2

Notes

- Friable asbestos containing materials also assigned a score of one (1).
- Add the surface treatment score to the calculated number from the table to obtain the final risk score.

Legend

>6	High Risk	Materials that pose a high exposure risk in current state. Immediate action should be taken for these materials to be removed under controlled conditions by a licensed asbestos contractor. Restrict access and isolate the area to authorised and trained personnel only until the material is removed. Periodic asbestos air monitoring should also be considered until removed
4–5	Medium Risk	Materials that pose a medium risk of exposure in current state. Action should be undertaken as soon as practicable to remove/remediate under controlled conditions by a licensed asbestos contractor. Restrict access in the interim. Non-friable material may be repaired by hierarchy of control measures.
2–3	Low Risk	Materials that pose a low risk of exposure in current state and may remain in-situ if left undisturbed and managed appropriately. Where planned maintenance, refurbishment or demolition works will disturb these materials, removal by a licensed asbestos contractor should be undertaken prior.

Appendix G

Limitation



G1 Limitation Statement

This Report is provided by WSP Australia Pty Limited (*WSP*) for Stanwell Corporation LTD (*Client*) in response to specific instructions from the Client and in accordance with WSP's proposal and agreement with the Client (*Agreement*).

PERMITTED PURPOSE

This Report is provided by WSP for the purpose described in the Agreement and no responsibility is accepted by WSP for the use of the Report in whole or in part, for any other purpose (*Permitted Purpose*).

QUALIFICATIONS AND ASSUMPTIONS

The services undertaken by WSP in preparing this Report were limited to those specifically detailed in the Report and are subject to the scope, qualifications, assumptions and limitations set out in the Report or otherwise communicated to the Client.

Except as otherwise stated in the Report and to the extent that statements, opinions, facts, conclusion and / or recommendations in the Report (*Conclusions*) are based in whole or in part on information provided by the Client and other parties identified in the report (*Information*), those Conclusions are based on assumptions by WSP of the reliability, adequacy, accuracy and completeness of the Information and have not been verified. WSP accepts no responsibility for the Information.

Where the survey identifies that hazardous materials are on Site, the Conclusions are indicative of the presence of hazardous materials and cannot be regarded as absolute without further extensive sampling, outside the scope of the services set out in the Agreement. Site conditions, including the extent and visibility of hazardous materials, can change with time. On all sites, varying degrees of non-uniformity of conditions are encountered and the presence of hazardous materials which are not visually apparent at the time of inspection, may not be detected. No monitoring, common testing or sampling technique provides results that are totally representative of the presence or non-presence of hazardous materials at the Site. Site conditions, including subsurface conditions can change with time due to natural and anthropogenic causes.

Only material that was physically accessible at the time of inspection was sampled. Consequently, not all hazardous material may have been located at the Site. The survey identifying hazardous materials on Site should be reviewed prior to demolition or refurbishment as a more detailed destructive survey may be required prior to demolition or refurbishment works. Care should be taken during normal Site works, refurbishment or demolition works when entering previously inaccessible areas. If suspect material is encountered, works should cease in the area until samples have been collected and analysed by competent personnel.

It is impossible to locate all hazardous materials during an inspection. This is due to such factors as (without limitation):

- Time, budget and constraints requested by the Client;
- Access restrictions;
- The need to avoid causing physical damage to fixtures or structures on the Site;
- The need to minimise hazardous materials exposures to building occupants;
- The need to minimise inconvenience when the Site is in use (e.g. occupied) whilst an inspection is being conducted; and / or
- The availability of relevant building / plant construction plans.

Hazardous materials that could be routinely encountered in the normal day-to-day activities occurring on the Site have been identified and assessed, however there is no guarantee that the Site is free of hazardous materials, since future activities may reveal hazardous materials in areas inaccessible or unknown to WSP.

Within the limitations referred to above, the preparation of this Report has been undertaken and performed in a professional manner in accordance with generally accepted practices, using a degree of skill and care ordinarily exercised by reputable consultants. No other warranty, expressed or implied, is made.

WSP has prepared the Report without regard to any special interest of any person other than the Client when undertaking the services described in the Agreement or in preparing the Report.

USE AND RELIANCE

This Report should be read in its entirety and must not be copied, distributed or referred to in part only. The Report must not be reproduced without the written approval of WSP. WSP will not be responsible for interpretations or conclusions drawn. This Report (or sections of the Report) should not be used as part of a specification for a project or for incorporation into any other document without the prior agreement of WSP.

WSP is not (and will not be) obliged to provide an update of this Report to include any event, circumstance, revised Information or any matter coming to WSP's attention after the date of this Report, unless this has been agreed with the Client. The passage of time; manifestations of latent conditions; or the impact of future events (including (without limitation) changes in policy, legislation, guidelines, scientific knowledge; and changes in interpretation of policy by statutory authorities); may require further investigation or subsequent re-evaluation of the Conclusions.

This Report can only be relied upon for the Permitted Purpose and may not be relied upon for any other purpose. The Report does not purport to recommend or induce a decision to make (or not make) any purchase, disposal, investment, divestment, financial commitment or otherwise. It is the responsibility of the Client to accept (if the Client so chooses) the Conclusions and implement any recommendations in an appropriate, suitable and timely manner. WSP does not (and will not) accept liability arising out of or in connection with any health or safety risks associated with hazardous materials.

In the absence of express written consent of WSP, no responsibility is accepted by WSP for the use of the Report in whole or in part by any party other than the Client for any purpose whatsoever. Without the express written consent of WSP, any use which a third party makes of this Report or any reliance on (or decisions to be made) based on this Report is at the sole risk of those third parties without recourse to WSP. Third parties should make their own enquiries, rely on the results of their own site inspections, and / or obtain independent advice in relation to any matter dealt with or conclusions expressed in the Report.

All quantities of materials are an approximate measurement, an independent Qualified Surveyor/Estimator should be engaged to quantify the quantities provided prior to any refurbishment / demolition works. It is the responsibility of third parties to investigate fully to their satisfaction if any information and/or report(s) prepared by WSP is suitable for a specific objective.

DISCLAIMER

No warranty, undertaking or guarantee whether expressed or implied, is made with respect to the data reported or the conclusions drawn. To the fullest extent permitted at law, WSP, its related bodies corporate and its officers, employees and agents assumes no responsibility and will not be liable to any third party for, or in relation to any losses, damages or expenses (including any indirect, consequential or punitive losses or damages or any amounts for loss of profit, loss of revenue, loss of opportunity to earn profit, loss of production, loss of contract, increased operational costs, loss of business opportunity, site depredation costs, business interruption or economic loss) of any kind whatsoever, suffered or incurred by a third party

Appendix H

References and Legislation



H1 References and legislation

QLD Code of Practice How to safely remove asbestos 2021

QLD Code of Practice - How to manage and control asbestos in the workplace 2021

QLD Work Health and Safety Regulation 2011

Guidance Note on the Membrane Filter Method for Estimating Airborne Asbestos Fibres 2nd Edition [National Occupational Health and Safety Commission: 3003 (2005)]

NOHSC. (April 2005a). Guidance Note on the Membrane Filter Method for Estimating Airborne Asbestos Fibres 2nd Edition. National Occupational Health & Safety Commission, Australian Government.

Standards Australia. (April 1994). Safety Signs for the Occupational Environment. Australian Standard.

Standards Australia. (February 2009). Selection, use and maintenance of respiratory protective equipment.

Standards Australia. (February 2012). Respiratory protective devices. Australian / New Zealand Standard, Joint Technical Committee QR-011.

Standards Australia. (September 2001). Demolition of structures. Australian Standard, Committee BD-059

Standards Australia (AS4361.2:2017) *Guide to hazardous paint management Part 2: Lead paint in residential, public and commercial buildings*

National Code of Practice for the Safe Use of Synthetic Mineral Fibres [NOHSC:2006(1990)]

ANZECC Identification of PCB Containing Capacitors database (1997)

Ozone Protection and Synthetic Greenhouse Gas Management Amendment Regulation 2024

Appendix I

General Information



I1 Background

Asbestos is the generic term for a group of naturally occurring mineral fibres with high tensile strength, flexibility, and resistance to thermal, chemical and electrical conditions. On account of these properties, asbestos has been used in many products for strength, heat, friction resistance and as insulation.

There are six types of the fibrous asbestos minerals, in two groups as described below:

- The serpentine asbestos is chrysotile (or white) asbestos. Chrysotile has been the most commonly used form of asbestos.
- Amphibole asbestiform of which amosite (brown asbestos) and crocidolite (blue asbestos), were the most common types of amphibole asbestos used in building products.

Asbestos fibres enter the body by the inhalation and/or ingestion of airborne particles that can become embedded in tissues of the respiratory or digestive systems. International agencies and national authorities now recognise asbestos to be a human carcinogen. This designation was based on an observation of an increased incidence of lung cancer, mesotheliomas and gastrointestinal cancer in occupationally exposed workers, being consistent across investigators and study populations. Information from animal studies on the inhalation of fibres support these findings, although evidence for carcinogenicity via ingestion is limited.

In recognition of the above-mentioned issues, every effort should be made to eliminate the use of asbestos materials in buildings.

I2 Use of asbestos products

Asbestos was used extensively in structures such as buildings, processing plants, ships, trains and motor vehicles in the 1950s, 1960s and 1970s. Asbestos cement products are commonplace in building materials and buildings constructed prior to 1990.

Asbestos has been used in hundreds of different building materials. Some of the common building materials include:

- Adhesive sealants and paints.
- Electrical backing boards and internal linings.
- Vinyl floor tiles and vinyl sheets.
- Fibro-cement sheets in wall, ceiling and eave linings (internal & external).
- Fibro-cement internal flues and downpipes
- Bitumen-based waterproofing such as malthoid (typically on roofs).

Whilst these materials are known to commonly contain asbestos, not all will. Confirmation must be made by detailed visual inspections coupled with laboratory analysis.

Generally, ACM consists of asbestos fibres bound in a cement matrix. The degree of fibre release and the risk posed by the asbestos will depend on the type of material (e.g. friable or non-friable), its condition and the potential for disturbance. As a result, it is necessary to have in place safe systems of work when working with or near asbestos.

I3 Legislative Requirements

State and Territory governments around Australia have generally adopted a consistent approach to asbestos management within workplaces. Whilst some minor differences are present from state to state, the following general requirements apply within workplaces:

- The owner of a workplace must determine if ACM are present in the workplace. This is usually undertaken through a visual inspection of the property.
- Upon identifying ACM, a risk assessment must be undertaken and must consider the following:
 - Friability
 - Condition
 - Location
 - Surrounding activities that could disturb the asbestos
- Where ACM is identified, it should be removed if removal is reasonably practicable. Where it is not reasonably practicable to remove, it must, depending on the level of risk, be either repaired, maintained and/or protected from future damage.
- ACM that is to remain in use (i.e. *in-situ*) must, when reasonably practicable, be labelled. An example of a warning label is shown below:

Figure I.1 Example asbestos warning label



- If ACM is found to be damaged or is in a position where it is likely to be damaged, steps must be taken to prevent it being or becoming an unacceptable risk.
- If the risk of the ACM is found to be elevated, then steps must be taken to minimise the risk to employees / workers and other personnel who attend the workplace.

14 Health Impacts

As ACM is no longer used in Australia, most worker exposures now occur during the removal of asbestos and the renovation and maintenance of buildings and structures containing asbestos; particularly when asbestos is disturbed during activities such as handling, sawing, sanding, grinding, drilling, turning or similar.

The presence of asbestos may constitute a potential hazard; however, risk to health is based on the likelihood that respirable asbestos fibres are inhaled in significant quantities.

The level of risk posed by asbestos is linked to the size and shape of the fibres and the ability of it to penetrate deep into the lungs and become lodged. Fibres that measure less than three (3) microns wide and greater than five (5) microns long are referred to as respirable fibres and may enter the deepest part of the lungs. Larger fibres are deposited in the nose and major airways and can generally be cleared by normal physiological processes.

Once asbestos fibres have been inhaled (particularly respirable fibres) they can become lodged and are harder for our bodies to destroy, breakdown or remove. This is when they pose the greatest potential to cause disease and the likelihood of disease increases as the number of asbestos fibres inhaled increases.

Significant health risks may arise from the inhalation of airborne asbestos fibres, and their passage into the lungs. The risk of cancer increases as fibres diameter decreases and with increased exposure. Cigarette smoking greatly increases the risk of lung cancer in people heavily exposed to asbestos but has no known association with mesothelioma.

Crocidolite and amosite have the most potent documented effects in producing the highly malignant mesothelioma tumour.

Asbestos fibres reaching the alveoli are handled in different ways. Some are carried out of the lung through the lymphatic system (part of the immune system). Of those fibres that remain some do not cause health effects whilst some may lead to lung changes such those outlined below:

Asbestosis	A form of fibrosis (scarring) of the lungs, which results in breathlessness. Asbestosis is a serious, chronic, non-cancerous respiratory disease. Asbestosis can take between 20 to 40 or longer years to develop.
Lung Cancer	Lung cancer is a disease which consists of uncontrolled cell growth in tissues of the lung. The incidence of lung cancer in people who are directly involved in the mining, milling, manufacturing and use of asbestos and its products is much higher than those who weren't involved in those industries.
Mesothelioma	Mesothelioma is a cancer of the outer covering of the lung (the pleura) or the abdominal cavity (the peritoneum). It is usually fatal. Mesothelioma is caused by the inhalation of needle-like asbestos fibres deep into the lungs where they can damage mesothelial cells, potentially resulting in cancer. The latency period is generally between 35 and 40 years, but it may be longer, and the disease is very difficult to detect prior to the onset of illness. Mesothelioma was once rare, but its incidence is increasing throughout the industrial world because of past exposures to asbestos. Australia has the highest incidence rate in the world.

The primary objective in any asbestos management plan is to eliminate, where possible, exposure to airborne asbestos fibres, or as a minimum, ensure workers are not exposed to fibre concentrations greater than the National Occupational Health and Safety Commission's occupational exposure standards for asbestos. It should be noted, that in situations where asbestos has been incorporated into a stable matrix and airborne dust is not generated, the asbestos-related health risk is negligible.

15 Lead Paint

In the past lead was added to paint as a pigment and to assist with drying, improve durability, resist moisture and retain a fresh appearance. Lead carbonate (white lead) was once the principal white pigment in paints for houses and public buildings. Paint with lead pigment was manufactured up until the late 1960s, and in 1969 the National Health and Medical Research Council's Uniform Paint Standard was amended to restrict the lead content in domestic paint. The use of lead in paint as a significant component was phased out in Australia by the early 1980s.

Many older Australian buildings still contain lead-based paint, even though it may be covered with layers of more recent paint. Lead-based paint was used mainly on exterior surfaces, and to a lesser degree on interior doors and door and window architraves, especially in undercoats and primers, where concentrations of up to 20 percent lead content were used. Interior walls were not commonly painted with paint containing white lead pigment, although some colours did contain red, orange and yellow lead pigments.

Other areas that may contain lead include lead flashing and lead backing in electrical components. Lead in any form is toxic to humans when ingested or inhaled, with repeated transmission of particles cumulating in lead poisoning. Lead paint removal poses two potential avenues of transmission. Firstly, by inhalation or ingestion by workers and public near the works, and secondly by the deposition of particles on nearby footpaths, streets or soil where they may be re-suspended, tracked into houses or buildings where it can be inhaled or ingested.

Lead based paints are to be managed in accordance with the Australian Standard Guide to hazardous paint management Part 2: Lead paint in residential, public and commercial buildings (AS4361.2:2017).

16 Synthetic Mineral Fibres

Synthetic Mineral Fibres (SMF) are a group of amorphous substances, including Glasswool, Rockwool and Ceramic fibre that have been fiberised by mechanical means, such as spinning or blowing during manufacturing. SMFs are commonly found in false ceiling panels and insulation and are typically identified by visual observation or by Optical Microscope techniques.

In the late 1980s the International Agency for Research on Cancer (IARC) evaluated certain SMF materials as being possibly carcinogenic to humans. The similarity in application and appearance to asbestos has resulted in some community concern regarding the health effects associated with exposure to SMF.

Reference information on SMF and their management is provided in the rescinded National Code of Practice for the Safe Use of Synthetic Mineral Fibres [NOHSC:2006(1990)].

17 Polychlorinated Biphenyls (PCBs)

Polychlorinated biphenyl (PCBs) compounds are synthetic organic compounds that were used in transformer oils, capacitor oils, hydraulic and heat-exchange fluids, lubricating oils, cutting oils, fluorescent light fittings, ceiling fans, dishwashers, clothes dryers, vacuum pumps, electric motors and washing machines. PCBs are highly stable chemicals with good insulating properties; they do not degrade appreciably over time or with exposure to high temperatures, acids or alkalis. It is these properties that made PCBs attractive for use in electrical devices. They were first used in about 1929 and were commonly used from the 1950s to the 1970s.

Fluorescent light-fittings containing capacitors can be compared with details contained in the ANZECC Identification of PCB Containing Capacitors database (1997).

It is considered that Australian electrical equipment manufactured since 1970 is unlikely to contain PCBs. Imports of PCBs to Australia were banned since 1976 once it became known that PCBs could harm human health and contaminate the environment.

I8 Ozone Depleting Substances (ODS)

Australia is a signatory of the Montreal Protocol which details banned ozone depleting substances. This is legislated through the Commonwealth's Ozone Protection Act, 1989.

Ozone depleting substances (ODSs) are those substances which deplete the ozone layer and are widely used in refrigerators, air conditioners, fire extinguishers, in dry cleaning, as solvents for cleaning, electronic equipment and as agricultural fumigants.

Ozone depleting substances controlled by Montreal Protocol include:

- Chlorofluorocarbons (CFCs)
- Halon
- Carbon tetrachloride (CCl₄), Methyl chloroform (CH₃CCl₃)
- Hydrobromofluorocarbons (HBFCs)
- Hydrochlorofluorocarbons (HCFCs)
- Methyl bromide (CH₃Br)
- Bromochloromethane (CH₂BrCl)