


	A	B	C	D	E	F	G	H	I	J
	SECTION 1 - GENERAL REQUIREMENTS									
1	1.01 DEFINITIONS - DRAWINGS - HYDRAULIC SERVICES DRAWINGS, ARCHITECTURAL, CIVIL, STRUCTURAL, ELECTRICAL AND OTHER SERVICES DRAWINGS ASSOCIATED TO AND WITH THIS PROJECT. - LOCAL AUTHORITY - THE RELEVANT AUTHORITY HAVING JURISDICTION OVER THESE WORKS. - PROVIDE - THE COMPLETE SUPPLY, INSTALLATION, TESTING, COMMISSIONING, SERVICE AND CERTIFY ALL MATERIALS AND COMPONENTS REQUIRED FOR THE PROJECT. - SUPERINTENDENT - THE CLIENT'S REPRESENTATIVE ON SITE. - MAIN CONTRACTOR - THE BUILDER OVER SEEING THE ENTIRE WORKS. - INTERPRETATION - UNLESS THE CONTEXT OTHERWISE REQUIRES, THE FOLLOWING DEFINITIONS APPLY: - SUPPLY - "SUPPLY", "FURNISH" AND SIMILAR EXPRESSIONS MEAN "SUPPLY ONLY". - PROVIDE - "PROVIDE" AND SIMILAR EXPRESSIONS MEAN "SUPPLY AND INSTALL". - APPROVED - "APPROVED", "REVIEWED", "DIRECTED", "REJECTED", "ENDORSED" AND SIMILAR EXPRESSIONS MEAN "APPROVED (REVIEWED, DIRECTED, REJECTED, ENDORSED) IN WRITING BY THE CONTRACT ADMINISTRATOR". "CONSULTANT" SHALL MEAN JHA CONSULTING ENGINEERS.									
2	1.02 GENERAL 1.02.01 ALL WORK SHALL BE CARRIED OUT BY AND UNDER THE SUPERVISION OF A LICENSED PLUMBER IN STRICT CONFORMITY WITH THE ARCHITECTURAL PLANS, HYDRAULIC SERVICES DRAWINGS AND SPECIFICATIONS. 1.02.02 ALL WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF RELEVANT CODES INCLUDING, BUT NOT LIMITED TO: - NATIONAL CONSTRUCTION CODE OF AUSTRALIA 2022 (NCC 22 VOL 1 & 3) - LOCAL COUNCIL REQUIREMENTS) - LOCAL WATER AND SEWER AUTHORITIES' REQUIREMENTS - SEWER AND WATER CODES OF AUSTRALIA - QUEENSLAND FIRE AND EMERGENCY SERVICES REQUIREMENTS & GUIDELINES, - AS 3500 SERIES 1 – 4: 2021 - PLUMBING AND DRAINAGE - AS 2419-2021 - FIRE HYDRANT INSTALLATIONS - AS 1345-1995 - IDENTIFICATION OF THE CONTENTS OF PIPE - AS 1428-2010 - DESIGN FOR ACCESS AND MOBILITY - AS 1595-2014 (A1) – THE STORAGE AND HANDLING OF LP GAS - QLD BUILDING ACT 1975 - QLD PLUMBING & DRAINAGE REGULATION 2019 - QLD PLUMBING & DRAINAGE ACT 2018 - QLD PLUMBING & WASTEWATER CODE V1 2019 - OTHER RELEVANT CODES AND AUSTRALIAN STANDARDS NOT LISTED ABOVE. 1.02.03 ALL WORKS SHALL BE CARRIED OUT TO THE SATISFACTION OF THE SUPERINTENDENT. 1.02.03 ALL WORKS SHALL BE CARRIED OUT TO THE SATISFACTION OF THE SUPERINTENDENT.									
3	1.03 SCOPE OF WORKS 1.03.01 ALLOW TO PROVIDE ALL MATERIALS AND LABOUR NECESSARY TO PROVIDE A COMPLETE, WORKING AND SERVICEABLE INSTALLATION BASED ON THE DRAWINGS, SPECIFICATION, ARCHITECTURAL DOCUMENTS, RELEVANT CODES AND AUSTRALIAN STANDARDS. 1.03.02 THE HYDRAULICS CONTRACTOR IS TO VISIT THE SITE PRIOR TO SUBMISSION OF THE QUOTATION. ALL QUERIES AND WHERE THERE IS AMBIGUITY IN THE TENDER DRAWINGS, THE HYDRAULICS CONTRACTOR IS TO BRING THIS TO THE ATTENTION OF THE CONSULTANT BEFORE THE CLOSE OF TENDER, NO ADDITIONAL COST WILL BE APPROVED THOUGH FAILURE OF THE CONTRACTOR TO INSPECT THE SITE. 1.03.03 EXISTING SERVICES INDICATED ON THESE DRAWING ARE OF APPROXIMATE LOCATIONS ONLY. HYDRAULIC CONTRACTOR RESPONSIBLE TO CONFIRM LOCATION OF THESE EXISTING SERVICES AND COORDINATE EXISTING WITH NEW SERVICES BEFORE COMMENCEMENT OF WORKS ON SITE. 1.03.04 HYDRAULIC CONTRACTOR TO ALLOW TO CHECK ALL INVERT LEVELS, PIPE COVER, PIPE LOCATION PRIOR TO COMMENCING ANY WORKS ON SITE. HYDRAULIC CONTRACTOR THEN SHALL CONFIRM INSTALLATIONS WITH THE INFORMATION COLLECTED ON SITE IN RELATION WITH THE DESIGN. 1.03.05 ANY CONCERNS MUST BE SUBMITTED TO THE SUPERINTENDENT AS SOON AS POSSIBLE WITH POSSIBLE SOLUTION IN FORM OF WRITTEN APPLICATION OF SKETCHES (SKETCHES MUST HAVE LEVELS TO INDICATE EVIDENCE OF CO-ORDINATION ON SITE). 1.03.06 ALLOW TO PROVIDE AND INSTALL THE HYDRAULIC SERVICES SHOWN ON THESE DRAWINGS, ALLOW TO COORDINATE WITH OTHER SERVICES, BUILDERS SCHEDULE AND OPERATION REQUIREMENTS BEFORE COMMENCING WORK ON SITE. CONTRACTOR MUST CONFIRM ALL PIPE SIZES INDICATED ON THESE DRAWINGS. IF PIPE SIZES ARE INCORRECT ITS THE HYDRAULIC CONTRACTORS RESPONSIBILITY TO LOCATE THE CORRECT SIZE PIPEWORK AND MAKE ALL CHANGES TO CONNECT TO THESE SERVICES. THE CONTRACTOR IS RESPONSIBLE TO LOCATE AND EXTEND ALL SERVICES FROM EXISTING TO NEW FITTINGS. 1.03.07 PRIOR TO COMMENCING AND EXCAVATION WORK, CONTACT DIAL BEFORE YOU DIG' TO OBTAIN ALL AVAILABLE INFORMATION ON EXISTING AUTHORITIES SERVICES AND MAKE EVERY EFFORT TO AVOID DISTURBING THESE SERVICES. 1.03.08 CONFIRM LOCATION AND SIZE OF ALL SERVICES REQUIRED FOR USE BY OTHER TRADES. THIS INCLUDES BUT NOT LIMITED TO: - DRAINAGE POINTS AND WATER SUPPLY POINTS. - EXAMPLE OF MAIN CONTRACTOR: MECHANICAL CONTRACTOR, FIRE CONTRACTOR AND POOL CONTRACTOR. SPARE ALLOWANCES SHALL BE ALLOWED IN LINE WITH THE ADDITIONAL CAPACITY TABLE. 1.03.09 THE CONTRACTOR SHALL ALLOW TO PROVIDE FOR ALL REQUIRED ACCESS, EQUIPMENT, LADDERS, SCAFFOLD AND THE LIKE TO COMPLETE AND SERVICE THE PROJECT. 1.03.10 THE HYDRAULIC CONTRACTOR TO PROVIDE TENDER PRICES AND BREAKDOWN TO SUPERINTENDENT AND CONSULTANT.									
4	1.04 DEMOLITION 1.04.01 ALLOW FOR THE DISCONNECTION AND REMOVAL OF ALL REDUNDANT FIXTURES AND ASSOCIATED PIPEWORK AS REQUIRED BY THE CONTRACT WORKS, ALLOW TO CUT & SEAL ALL REDUNDANT HYDRAULIC PIPING AT POINT OF ORIGIN. 1.04.02 ALL DEMOLITION WORKS SHALL BE CARRIED OUT IN A WORKMANLIKE MANNER TO SUIT THE REQUIREMENT OF ALL CODES, REGULATIONS AND OHS REQUIREMENTS 1.04.03 COORDINATE DEMOLITION / DISCONNECTION / RELOCATION OF SERVICES TO ENSURE MINIMAL DISRUPTION OCCURS. 1.04.04 CUT AND SEAL EXISTING DISUSED AND REDUNDANT WATER SUPPLIES IN AN WATER TIGHT MANNER AS REQUIRED BY AUTHORITY AND AS INDICATED ON HYDRAULIC DRAWINGS. PLUG ALL PIPE ENDS AND CARRY ALL WORKS DOWNSTREAM OF ISOLATION VALVES THAT SHALL REMAIN IN PLACE FOR FUTURE EXTENSION. 1.04.05 WHEN SEALING EXISTING WASTES AND VENTS, CUT AND SEAL THE DISUSED PIPE AT STACK OR RELIEF BRANCH LEAVING A SEALED WASTES OR VENT FOR FUTURE CONNECTION. 1.04.06 ENSURE THE CONTINUOUS OPERATION OF EXISTING HYDRAULIC SERVICES TO SERVICE OTHER FLOORS AND AREAS DURING THE DEMOLITION AND CONSTRUCTION STAGES OF WORKS. 1.04.07 ANY EXISTING HYDRAULIC SERVICES THAT ARE ALTERED/REMOVED OUTSIDE THE SPECIFIED SCOPE SHALL BE RENESTATED BY THE HYDRAULIC CONTRACTOR AT THEIR EXPENSE. 1.04.08 THE CONTRACTOR SHALL VERIFY ALL ITEMS TO BE DECOMMISSIONED AND REMOVED WITH THE CLIENTS APPROVED REPRESENTATIVE PRIOR TO ANY DEMOLITION WORK TAKING PLACE. 1.04.09 THIS DRAWING SHALL BE READ IN CONJUNCTION WITH THE ARCHITECT'S DRAWINGS FOR BUILDING DEMOLITION STAGES OF WORKS. 1.04.10 ALL REDUNDANT PIPE WORK SHALL BE REMOVED FROM SITE. 1.04.11 SANITARY PLUMBING, DRAINAGE AND VENTS TO BE CAPPED USING PROPRIETARY FITTINGS. 1.04.12 CAP REDUNDANT WATER SERVICES BACK TO BRANCH TO ELIMINATE DEADLEGS IN PIPEWORK.									
5	1.05 DIMENSIONS THESE DRAWINGS ARE INDICATIVE ONLY. ALL DIMENSIONS MUST BE CONFIRMED ON SITE AND WITH CURRENT ARCHITECTURAL DRAWING, TEMPLATES AND DETAILS BEFORE ANY SITE WORK OR OFF-SITE FABRICATION TAKEN PLACE. 1.06 MATERIALS 1.06.01 ALL MATERIALS USED IN THE WORK SHALL BE NEW AND OF THE BEST QUALITY AND TYPE AVAILABLE TO CONFORM WITH THE RELEVANT AUSTRALIAN STANDARDS AND BEAR THE REQUIRED STANDARDS MARK AND AUSTRALIAN WATERMARK APPROVAL. 1.06.02 EXCEPT WHERE SPECIFICALLY SHOWN OTHERWISE ALL SERVICES SHALL BE FREE OF EACH OTHER AND EASILY REPLACEABLE FOR THEIR FULL LENGTH. 1.06.03 WHERE POSSIBLE PIPES SHALL BE RUN PARALLEL, WITH WALLS AND SLABS AND WITH EACH OTHER, MINIMISE CROSSOVERS AND UNSIGHTLY GROUPINGS. ALL PIPE WORK SHALL BE ACCURATELY SET OUT AND FULLY COORDINATED WITH OTHER SERVICES PRIOR TO COMMENCING OR FABRICATING AND INSTALLING ON SITE. 1.06.04 DURING EARLY WORK AND CONSTRUCTION LEAVE ALL UNFINISHED WORK IN A SAFE CONDITION, PROTECTING THE WORKS AGAINST DAMAGE OR LOSS THROUGH ANY CAUSE WHAT SO EVER, SEAL OFF OPEN-END PIPE WORK IN SUCH A MANNER AS TO PREVENT ENTRY OF FOREIGN MATTER INTO PIPE WORK, UNTIL WORK HAS BEEN COMPLETED OR HANDED OVER ON COMPLETION.									
6	1.07 FEES AND PERMITS 1.07.01 TENDERS SHALL MAKE ALL APPLICATIONS TO THE WATER, SEWER AUTHORITIES, GAS AUTHORITIES AND LOCAL COUNCIL.									
	A	B	C	D	E	F	G	H	I	J
	Autodesk Docs://Q250128 Stanwell Office/Q250128_R24_S0_MEH.rvt									



All dimensions to be verified on site/s prior to commencement of on-site work and/or off-site prefabrication. Figured dimension to be taken in preference to scaled dimensions. This drawing is copyright and remains the property of JHA Consulting Engineers. Reproduction in whole or part of these drawings without written consent constitutes an infringement of copyright.

REVISIONS / AMENDMENTS

Rev	Date	Description	Verified
A	18.12.2025	TENDER ISSUE	H.R.
B	14.01.2026	ISSUE FOR COUNCIL APPROVAL	H.R.

PERMIT APPLICATION REF: _____

DESIGNER: HARRISON RALPH
QBCC Lic No. 15125080
SOIL CLASSIFICATION: H1

SECTION 6 - STORMWATER, DOWNPIPES AND RAINWATER OUTLETS

6.01 STANDARDS

THE INSTALLATION IS TO BE DONE IN ACCORDANCE WITH AS3500.3, THE BUILDING CODE OF AUSTRALIA AND LOCAL AUTHORITY REQUIREMENTS.

6.02 PIPEWORK MATERIAL

REFER TO PIPE MATERIAL SCHEDULE.

SECTION 7 - FIRE HYDRANT SERVICES

7.01 STANDARDS

THE INSTALLATION IS TO BE IN ACCORDANCE WITH AS2419.1, AS2419.3, BUILDING CODE OF AUSTRALIA AND LOCAL FIRE BRIGADE REQUIREMENTS.

7.02 PIPEWORK MATERIAL

REFER TO PIPE MATERIAL SCHEDULE.

7.03 BLOCK PLAN

ALLOW TO UPGRADE ALL EXISTING BLOCK PLANS ON SITE INDICATING NEW HYDRANT LOCATION AND REQUIREMENTS, OR ALLOW TO PROVIDE NEW IN ACCORDANCE WITH AS 2419 ON METAL OR PERSPEX PLATE IN ACCORDANCE WITH LOCAL FIRE BRIGADE REQUIREMENTS.

7.04 LANDING VALVES

7.04.01 LANDING VALVES TO BE BRONZE LOCATED MINIMUM 750mm AND A MAXIMUM OF 1200mm ABOVE GROUND LEVEL AND ALLOW TO PROVIDE AND INSTALL QRT (QUEENSLAND ROUND THREAD) TO ALL NEW HYDRANT IN ACCORDANCE WITH QUEENSLAND FIRE BRIGADES' (QFBSF) REQUIREMENTS.

7.04.02 VALVE OUTLET TO BE FITTED WITH A BRASS CAP AND CHAIN, WHICH IS TO BE ATTACHED TO THE CAP AND VALVE BODY.

7.04.03 ALLOW FOR INSTALLATION OF PROTECTIVE COVERS FOR ALL EXTERNAL FIRE HYDRANT VALVES.

7.04.04 ALLOW FOR INSTALLATION OF PROTECTIVE BOLLARDS FOR ALL EXTERNAL FIRE HYDRANT VALVES WERE LOCATED IN AREAS WITH VEHICULAR TRAVEL.

SECTION 8 - SANITARY WARE AND TAPWARE

THROUGHOUT THE PROJECT ALL SANITARY WARE, FIXTURES, FITTINGS AND FINISHED SURFACES SHALL BE ADEQUATELY PROTECTED AGAINST DAMAGE WITH SUITABLE MATERIALS AS REQUIRE.

REFER TO ARCHITECTS SANITARY FITTING, FIXTURE AND TAPWARE SCHEDULE.

REAL PROPERTY DESCRIPTION:

LOT/PLAN 44SP140243

OWNERS NAME:

STANWELL CORPORATION
LIMITED; BRENTON JENSON

CLIENT



ARCHITECT

brian hooperarchitect
m3architecture

CONSULTANT



PROJECT

STANWELL NEW PROJECTS
OFFICE

397/ POWER STATION ROAD,
STANWELL, QLD 4702

TITLE

HYDRAULIC SERVICES
NOTES

APPROVAL ISSUE

NOT TO BE USED FOR CONSTRUCTION

DRAWN	J.P.	SCALE @ A1 NTS
CHECKED	H.R.	
APPROVED	H.R.	
CREATED	DEC 25	
JOB No.	DRAWING No.	REV
Q250128	H0002	B