



TECHNICAL ADVICE NOTE

TO: PEDDLE THORP
FROM: Tony Pereira
PROJECT NR: PS229518
PROJECT NAME: CQU Rockhampton
SERVICE: Electrical
SUBJECT: Additional 3 phase power supplies
FILE NAME/NUMBER: TAN-01 ROK 3 Phase Power
OUR REF: PS229518-06-Electrical-Addenda Rev-B
DATE: 10 March 2026
AUTHOR: WSP **CHECKED:** TAP **APPROVED:**

1. INTRODUCTION

The purpose of this Technical Advice Note is to provide additional information to the prospective tenderers to allow for the supply and installation of additional 3 phase supplies shown below. All isolators and outlets are to be industrial type Clipsal IP66 or equal approved.

Tenderers shall provide a price for each nominated 3-phase supply and incorporate these amounts into the final tender submission. Should the client elect not to proceed with the installation of any specified supplies, the contractor shall credit the corresponding amounts, as detailed in this TAN, back to the client.

Please note that tenderers are also to allow for the flexible connections between isolators and respective equipment via a flexible metal conduit.

AREA	EQUIPMENT	SUPPLY	QUANTITY	COST PER ITEM	TOTAL COST
Building - 21A	Isolator	10Amps 3Phase	2		
Building - 21A	Isolator	32Amps 3Phase	8		
Building - 21A	Isolator	50Amps 3Phase	1		
Building - 21A	Isolator	63Amps 3Phase	1		
Building – 21A New Shed	Electrical Load Centre	63Amps 3phase from B21A MSB	1		
Building – 21A New Shed	Isolator (ceiling Fans)	10Amps 3 phase	2		

Level 12, 900 Ann Street
Fortitude Valley QLD 4006
GPO Box 2907
Brisbane QLD 4001

Tel: +61 7 3854 6200
Fax: +61 7 3854 6500
www.wsp.com



Building – 21A New Shed	Lighting	Surface mounted linear LED locally switched	6		
Building – 21A New Shed	Isolator	20Amps 3phase	4		
Building – 21A New Shed	Outlet	15Amp 1phase	4		
Building – 21A New Shed	Outlet	Double 10Amps 1phase	10		

AREA	EQUIPMENT	SUPPLY	QUANTITY	COST PER ITEM	TOTAL COST
Building - 36	Isolator	25Amps 3Phase	4		
Building - 36	Isolator	32Amps 3Phase	6		
Building - 36	Isolator	50Amps 3Phase	1		
Building - 36	Isolator	63Amps 3Phase	1		

AREA	EQUIPMENT	SUPPLY	QUANTITY	COST PER ITEM	TOTAL COST
Building – 92 Auto Trade	Isolator	20 Amps 3Phase	12		
Building – 92 Auto Trade	Isolator	32Amps 3Phase	5		
Building – 92 Auto Trade	Outlet	32Amps 3Phase	6		
Building – 92 Auto Trade	Isolator	40Amps 3Phase	1		
Building – 92 Auto Trade	Outlet	40Amps 3Phase	3		
Building – 92 Auto Trade	Outlet	50Amps 3Phase	1		

Building – 92 Auto Trade	Isolator	63Amps 3 Phase	1		
Building – 92 F&M Workshop	Emergency Stop Buttons	Size to suit respective contactor	4		
Building – 92 F&M Workshop	Isolator mounted on a floor to ceiling SHS	32Amp 3 Phase	43		
Building – 92 F&M Workshop	Isolator	6Amps 3Phase	4		
Building – 92 F&M Workshop	Isolator	10Amps 3Phase	3		
Building – 92 F&M Workshop	Outlet	10Amps 3Phase	1		
Building – 92 F&M Workshop	Isolator	16Amps 3Phase	6		
Building – 92 F&M Workshop	Isolator	20Amp 3Phase	5		
Building – 92 F&M Workshop	Outlet	20Amp 3Phase	10		
Building – 92 F&M Workshop	Isolator	32Amp 3Phase	1		
Building – 92 F&M Workshop	Isolator	40Amp 3Phase	1		
Building – 92 F&M Workshop	Isolator	50Amp 3 phase	1		
Building – 92 F&M Workshop	Outlet	50Amp 3Phase	1		
Building – 92 F&M Workshop	Isolator	63Amp 3 phase	1		



Building – 92 Metal Fabrication Workshop	Isolator	32Amps 3Phase	14		
Building – 92 Refrigeration	Isolator	20Amp 3Phase	1		
Building – 92 Refrigeration	Isolator	20Amps 1Phase	5		
Building – 92 Refrigeration	Isolator	32Amps 3 phase	18		
Building – 92 Refrigeration	Outlet	20Amp 3Phase	4		
Building – 92 Refrigeration	Outlet	40A 3 Phase	2		