

**DIRECTORATE OF FACILITIES MANAGEMENT**

---

## **ADDENDUM #13 TO:**

---

### **Request for quotation**

**Project: ROK TAFE Consolidation Stg.2  
- Design and Construct**

**Number: CQURFQ-26-4-DFM  
Addendum Issue Date:  
15/04/2026**

**Note:** This Addendum, the Original Request for Quotation and any other documentation issued in relation to this Invitation should be retained by the Respondent for future reference.

## 1) Purpose of Addendum

The purpose of this Addendum is to provide additional information for intended Respondents with regard to CQUniversity RFQ, Reference: CQURFQ-26-4-DFM. The information has either become available post-issuance of the RFQ document or as a result of enquiries to date.

Note: The information provided under this Addendum must be interpreted in the context of the original RFQ document.

## 2) Clarifications

### **Question 1:**

Can you please confirm if the Building 76 Shed requires internal wall linings, ceilings and external soffits - there are currently none shown on the drawings.

### **Answer 1:**

Confirming that Building 76 Shed (Store) does not include internal wall linings, ceilings, external soffits. However, please include sarking and roof insulation secured by safety wire mesh to the entire roof of the shed.

### **Question 2:**

With regards to the refurbishment of Building 33, there will be a lot of new set down areas required into the top of the existing concrete slab for bathrooms and toilets etc. These will require a rebate to accommodate falls to a floor waste.

Have noticed that architectural sections do not show any set downs for these bathrooms.

Installing set downs to these existing suspended slabs, will be problematic, as it requires cutting through the top layer of reinforcement (will require adding stiffening beams under the slab, and the current structural drawings do not show any of this).

With the current architectural design and its development, have these set downs been considered and will they be required?

### **Answer 2:**

Following a review of the slab drawings, the Design team have identified some discrepancies. At this stage, the response is a "potential approach" noting that the final resolution will need to be developed further during the next design phase.

With regard to the wet areas in Building 33, the potential approach was as follows:

- No cutting or chasing of the existing slab's top layer was to be undertaken. While this option was queried, the structural engineer advised that this is not the preferred solution.
- New hobs were intended to be installed to all wet areas, as indicated in Detail 2 and Detail 4 on drawings CQU-ROK-033-01-ARC-23-01 and CQU-ROK-033-01-ARC-23-02.
  - o Note that Detail 2 requires amendment to indicate a cementitious topping with falls. Please refer to the attached markup.
  - o Drawing ARC-23-02 also requires amendment to highlight the wet area hobs (shown in yellow). Please refer to the attached markup.
- For dry areas, separation between internal and external spaces was to be provided via hobs, as shown in Detail 1 and Detail 3 on drawings CQU-ROK-033-01-ARC-23-01 and CQU-ROK-033-01-ARC-23-02.

For ease of reference, the relevant slab drawings are attached.

### **Question 3:**

Extension of Time Request

We would like to request an extension of time, proposing a new Tender Close date of Thurs 7th May. While we appreciate that

an extension has already been granted and the project is subject to Government Grant timelines, our subcontractors have advised us they will be unable to provide pricing in time for us to meet the current Tender Close date.

**Answer 3:**

CQU approves this extension of time request.

The new closing date is to be 9am, Thursday 7 May.

Whilst this extension has been provided, Contractors will still be assessed on their ability to meet the delivery timeframes stipulated in the tender documents.

**Question 4:**

Can you please clarify - in Addendum No. 11 (Question 11) - the answer indicated the original PC dates that were in the original Appendix A Scope or Requirements and Works. With the tender having now been extended by two (2) weeks from the 9th April to the 23rd April - can you please confirm that all the PC dates should all be extended by two (2) weeks.

**Answer 4:**

As mentioned in answer 3, whilst this extension has been provided, Contractors will still be assessed on their ability to meet the delivery timeframes stipulated in the tender documents.