

DIRECTORATE OF FACILITIES MANAGEMENT

ADDENDUM #6 TO:

Request for quotation

**Project: ROK TAFE Consolidation Stg.2
- Design and Construct**

**Number: CQURFQ-26-4-DFM
Addendum Issue Date:
19/03/2026**

Note: This Addendum, the Original Request for Quotation and any other documentation issued in relation to this Invitation should be retained by the Respondent for future reference.

1) Purpose of Addendum

The purpose of this Addendum is to provide additional information for intended Respondents with regard to CQUniversity RFQ, Reference: CQURFQ-26-4-DFM. The information has either become available post-issuance of the RFQ document or as a result of enquiries to date.

Note: The information provided under this Addendum must be interpreted in the context of the original RFQ document.

2) Clarifications

Question 1:

After the site inspection, in particular Building 19. Can you please confirm if we are to remove the concrete architraves from all the windows and square set the plasterboard into the window reveal. The current partition plan indicates that on the external walls have a 50mm batten and 13mm plasterboard. If this is butted up against the architrave it will sit proud, how would it be finished?

Please advise if we are to remove the concrete architrave or provide a finishing detail where the proposed wall lining abuts the architrave.

Answer 1:

This response relates to building 19 only.

The existing internal concrete architrave to windows is to be removed. Flush set plasterboard is to be provided to window head and jamb reveals. A 9mm cfc window sill is to be provided – with pencil round edges and a 10mm overhang. The jambs and head reveals are to be painted to match the adjacent wall. The sill is to be painted in a high gloss paint.

Question 2:

Please confirm specification for glass types GL1, GL2 & GL3 as we are not able to identify anything on the drawings.

Answer 2:

Building 92 (New Trades Building)

GL1 – Clear vision glass

Glass: Double glazed. Thickness to comply with JV3 & acoustic requirements

Colour: Clear

U-Value ≤ 5.7

SHGC ≤ 0.32

GL2 – Spandrel glass

Colour backed glass to match Aluminium frame. R2.0 Bulk insulation

GL3 – Clear internal glazing

Thickness to comply with acoustic performance requirements of partition.

Building 33

GL1 – Clear vision glass

Glass: Double glazed. Thickness to comply with JV3 & acoustic requirements
Colour: Clear
U-Value ≤ 4.1
SHGC ≤ 0.41

Building 36

GL1 – Clear vision glass

Glass: Double glazed. Thickness to comply with JV3 & acoustic requirements
Colour: Clear
U-Value ≤ 3.8
SHGC ≤ 0.39

Question 3:

Is there a signage schedule for the signs required for this project?

Answer 3:

A Signage schedule has not been developed as part of the 60% design. This will need to be developed in the next phase of the project. Refer to the CQU Design Standards Manual which contains details on CQU Signage guidelines. Contractor to allow for signage.

Question 4:

Is there a door hardware schedule available?

Answer 4:

A note has been included in the Architectural Design Report advising that CQU wishes to review the door schedule during the next design phase. For pricing related to door security, Tenderers are to allow for:

- Electronic swipe card access to all doors
- Doors with electronic security provisions must also be provided with a manual key-override. The override key must be keyed to CQU Bilock Keying system with specific key code to be approved by the Superintendent. Refer to Appendix O of the Design Standards Manual for details.
- Reed switches to roller doors

Please refer to item 3.6.5 in the Design Standards Manual for additional information on door requirements, together with Appendix O of the Design Standards Manual.

A hardware schedule will need to be developed in the next project phase. Contractor to allow for CQU consultation and review of these schedules.

Question 5:

We note that the product for the epoxy flooring has been specified as CCS; however, generally only APAS-approved products are permitted in government sites. Can you please confirm that the CCS product can be utilised?

Answer 5:

APAS-approved product is not required in this instance.

Question 6:

Can you please provide a mechanical services fan schedule - the fans are listed in the MSSB schedules and shown on the drawings so we are assuming WSP would have a fan schedule available?

Answer 6:

This has been requested from Engineers and will be provided to Tenderers by close of business Tuesday 24/3/26.

Question 7:

Within the room break-ups for Building 19 there is an item in the meeting rooms EP15H Rectangle Gable - can you please advise what this item is.

Answer 7:

Detail can be found in the Room Layout Sheet notes.

"ALLOW FOR STRUCTURAL PLY BACKING BEHIND PLASTERBOARD FOR FULL EXTENT OF WALLS WITH MOUNTED AUDIO VISUAL EQUIPMENT. REFER TO AUDIO VISUAL (VIDEOPRO) DOCUMENTATION FOR LOCATIONS OF WALL MOUNTED EQUIPMENT."

In the building 19 Revit model this was modelled as a ply backing board which has scheduled as an FFE item code EP15H. In all buildings where there are wall mounted AV screens – please allow for the structural ply as noted.

Item 8:

WAPs plans have been provided as part of the design package. Contractors are advised that the WAPs require power and 2 x data ports per WAP. Allowance is to be made for these services.