

KLAD

studio

Access Consulting | Architecture

Thomson Adsett

ROK TAFE Consolidation Stg.2

Project Number: CQURFQ-25-2-DFM

Access Report - 60% Issue - Revision 1
6 January 2026



studio

Access Consulting | Architecture

Revision	Date	Author	Reason
60% Issue	6 February 2026	K. Devitt	60% Issue
50% Issue V2	9 January 2026	K. Devitt	50% Revision 2
50% Issue V1	5 January 2026	K. Devitt	50% Issue - further revisions to be released as all drawings reviewed.
30% Issue	7 November 2025	K. Devitt	30% Issue

This report has been prepared by

Access Consultant
KLAD Studio

KLAD Studio

Access Consulting + Architecture

PO BOX 2206 Ashgrove Q 4060 T +61 419 730 934 katie@klad.com.au

Contents

1. Summary of Key Items at 60% Accessibility Review	4
All Buildings	4
ROK019 - Level 3 Fitout	5
ROK032 - Ground Floor Partial Fitout	5
ROK33 - Level 1 + Level 2	5
ROK34 - Ground Floor + Landscaping	5
ROK36 - Ground Floor + Level 1	6
ROK076 - New Horticulture Workshop	6
ROK092 - New Trades Building	6
2. Executive Summary of Project	7
3. Performance-Based Design Brief Signoff	8
4. Performance-Based Design Brief Summary	9
5. Overview of ROK TAFE Consolidation Stg.2 Project	11
6 Legislation	13
7. Documentation Assessed	15
Appendix A: Drawing Markup	21
Appendix B: Accessibility Checklist	44

1. Summary of Key Items at 60% Accessibility Review

All Buildings

As the Project is at 60% stage, the primary focus of this review was ensuring a Continuous Accessible Path of Travel through all spaces. However, if other items were able to be reviewed then they were additionally accessed.

Important points to note: -

1. A distance of 1765 mm between back to back desks appears to be the standard across the project. This is slightly less than I have seen on other projects and does expose the client to risk under the DDA.

At 1765 mm between desks there may be difficulty for someone using a mobility device to move between the chairs, if 2 people are seated in the chairs. Typically when a person is seated in a standard office chair, the chair impedes from 400 to 500 mm into the space behind. If two people are seated this may limit the space between the backs of the chairs to less than a metre. A metre is the minimum for an accessway when chairs are occupied. AS 1428.1 2021 Cl. 3.3.

In addition to making the seating feel cramped this will also increase the risk of injury caused by chairs bumping into the back of another when exiting the seat. As a precedent, I have found the Macquarie University in Sydney's Room and Space Planning guide at - https://www.property.mq.edu.au/general_design/room_and_space_planning. The guide states a minimum of 1.8 metres between desks in back-to-back arrangement. I would advise to increase to 1800mm as a minimum.

2. Please review all comments on the Markup pages in Appendix A. as only key items are included here in the summary. Check Markup pages in Appendix A for identified issues.

3. All buildings have rooms or spaces that will be inaccessible. Review and confirm these spaces for each building on the Markup pages in Appendix A.

4. It is usually easier for a person using a mobility device to move through a room where they can follow a path rather than having to do a 180 degree turn to leave the room. If a 180 degree turn is required then appropriate circulation space is needed. As a minimum this space is 2070mm in the direction of travel and 1540 mm wide (AS1428.1 2021 CL.3.5.4).

5. As the project is currently at 60%, there are a number of items that cannot be assessed. These will be assessed as the project progresses. These include:

- Fixtures, Fittings, Equipment and Material
- Door and Window Hardware
- Door Material
- Contrast
- Audio
- Floor Finishes
- Slip Resistance
- TGSIs
- Lumenance
- Hearing Augmentation

ROK019 - Level 3 Fitout

The critical items to be addressed for ROK019 are:

1. If a non-accessible shower is provided then an accessible shower is required. Therefore unless another shower is provided this shower must become accessible. NCC 2022 Volume1 F4D7

The requirements for an accessible shower are detailed in AS1428.1 Cl.10 and Cl.12

Critical requirements include:

1. No step or hob
2. Inward opening shower door needs to be operable or removable from outside in an emergency.
3. Appropriate grade - (Cl.12.5.2)
4. Grab Rails
5. Shower Seat
6. Shower Hose not rose
7. Soap Holder
7. Clothes Hanging Device.

Check the CAPT behind reception. There does not appear to allow for a CAPT (Continuous Accessible Path of Travel) which is a minimum of 1000mm wide, but preferably 1200mm. Refer to markups in Appendix A.

2. The furniture layout at multiple points across ROK019 do not appear to allow a CAPT. Refer to markups in Appendix A.

3. Confirm areas not accessible due to nature of activities:

- 3.09 Electrical Cupboard
- 3.16 Plant Room
- 3.21 Riser
- 3.27 Server
- 3.24 Plant Room

ROK032 - Ground Floor Partial Fitout

The critical item to be addressed for ROK032 are:

1. There needs to be an accessible path of travel from the renovated area to the footpath / accessible carpark.

ROK33 - Level 1 + Level 2

The critical items to be addressed for ROK033 are:

1. There are some rooms that are inaccessible that should be accessible.
These are: 2.30 / 2.33 Quiet Hot Desk and Quiet Rooms.

This will need to be rectified or a solution discussed with the Building Certifier in the next phase.

2. Due to the furniture arrangement in some classrooms, computer labs, open plan workstations areas and Meeting Rooms, there are parts of these spaces that are inaccessible. Refer to markups in Appendix A.

- 1.01 Educational Teaching
- 1.02 Educational Teaching
- 1.05 Bookable Classroom
- 1.26 Bookable Classroom 2
- 1.13 Computer Lab
- 1.22 Digital Design
- 1.08 Student Breakout
- 2.21 Alcove attached to Open Plan Workstation
- 2.21 / 2.32 / 2.03 Accessway through Open Plan Workstation
- 2.26 / 2.24 / 2.11 Meeting Rooms

3. Update Accessible Toilet with additional FFE to match Accessible Toilet design in Building 19. CQU-ROK-019-03-ARC-60-06

ROK33 - Level 1 + Level 2 continued

4. Confirm areas not accessible due to nature of activities:

- 1.06 Riser
- 1.07 Riser
- 1.12 Server
- 1.14 Server
- 1.18 Store
- 1.20 Riser
- 2.04 Riser
- 2.29 Server Room
- 2.40 Riser
- 2.41 Riser

ROK34 - Ground Floor + Landscaping

The critical items to be addressed for ROK034 are:

1. Adjust furniture on layout plan to ensure 1 metre accessway through the dining room.

ROK36 - Ground Floor + Level 1

The critical items to be addressed for ROK036 are:

1. Areas that are no accessible due to the arrangement of the furniture

See Markup in Appendix A.

- G.19 Restaurant
- 1.03 Beauty Studio

2. Sound System is planned for 1.13 Hairdresser, so a Hearing Loop is required.

3. Confirm areas not accessible due to nature of activities:

- G.20 Elec Risers
- G.21 Store
- G.28 Comms
- G.29 Server
- 1.05 Comms
- 1.06 Elec
- 1.18 Storage
- 1.19 Comms
- 1.20 Riser
- 1.21 Elec Risers

ROK076 - New Horticulture Workshop

1. Confirm areas not accessible due to nature of activities:

- G.02 Outdoor Planting
- G.12 Outdoor Planting
- G.08 Drop Off / Deliveries

2. Due to the furniture arrangement in the Student Lunch Area there are parts of these spaces that are inaccessible. Refer to markup in Appendix A.

ROK092 - New Trades Building

1. Confirm areas not accessible due to nature of activities:

- G.03 Services
- G.50 Storeroom
- G.51 Main Switchroom
- G.52 Gas Manifold
- G.57 Washdown
- G.68 Store
- G.71 Cleaner
- G.73 Comms
- G.80 DB Cupboard
- Metfab / GF / Arc Weld Bays
- Grind Bay
- 1.17 Flammable Gas Store
- 1.20 Services
- 1.11 Cleaner
- 1.16 Balcony

2. Areas that are not fully accessible due to the arrangement of the furniture

See Markup in Appendix A.

- G.05 Shared Theory Room
- G.06 Theory Room
- G.07 Class Room / Theory
- G.13 CAD Classroom
- G.62 Theory Room 1
- G.65 Theory Room 3
- G Circulation / Wait

2. Executive Summary of Project

- This 60% Design report summarises the review by KLAD Studio of the current sketch designs and sets out accessibility requirements and universal accessibility opportunities to inform further design work.
- A video conference was conducted on Monday 3 November 2025 between KLAD Studio (Katie Devitt) and key team members at Thomson Adsett and Peddle Thorp (Sally Snow, Brendan Sutton and Bonita Chau), where each Building and Level in the Project was explained and discussed in turn.
- This Report is Revision 1 of the 60% Report, there will be further revisions to complete the review of all the drawings.
- It is important to note that as this is the 60% Design Stage of the project it is not plausible to do a complete access audit at this time. However each building and level has been reviewed according to the sketch design and a markup of the drawings is in Appendix A. This is integral for accessible requirements to be incorporated early in the design process and to minimise rework.
- Appendix B contains the list of Accessibility requirements that will be audited for each building as the design progresses. This will be conducted for each building and each level included in the project. This list will be the basis of the accessibility review processes through subsequent phases. This list will be continually updated and will be the key to meeting accessibility standards.

3. Performance-Based Design Brief Signoff

This Performance-Based Design Brief was collaboratively formulated with essential stakeholders to showcase the steps and analyses conducted in addressing a design challenge while ensuring alignment with the applicable Performance Requirements.

The stakeholders have recently completed the initial phase of this Performance-Based Design Brief, which includes the Assessment Criteria. These criteria have been submitted to the appropriate authority, the building certifier, for approval.

By affixing their signature below, the Building Certifier has affirmed that the Acceptance Criteria outlined in this Performance-Oriented Design Brief serve as a suitable standard for verifying adherence to the relevant Performance Requirements of the NCC.

STAKEHOLDER	NAME	SIGNATURE	DATE
CLIENT Central Queensland University			
CERTIFIER Knisco			
ARCHITECT Thomson Adsett			

To be completed if Performance Solution Required

4. Performance-Based Design Brief Summary

Clause A2.2(4) of the NCC describes the process for developing Performance Solutions as:

Where a Performance Requirement is proposed to be satisfied by a Performance Solution, the following steps must be undertaken:

- a) Prepare a Performance-based Design Brief in consultation with relevant stakeholders.
- b) Carry out analysis, using one or more of the Assessment Method listed in (2), as proposed by the Performance-based Design Brief.
- c) Evaluate results from (b) against the acceptance criteria in the Performance-based Design Brief.
- d) Prepare a final report that includes—
 - i. all Performance Requirements and/or Deemed-to-Satisfy provisions identified through A2.2(3) or A2.4(3) as applicable; and
 - ii. identification of all Assessment Methods used; and
 - iii. details of steps (a) to (c); and
 - iv. confirmation that the Performance Requirement has been met; and
 - v. details of conditions or limitations, if any exist, regarding the Performance Solution.

To be completed if Performance Solution Required

Issue : To be determined

This portion of the report will be utilised to detail any performance solution that is required.

To be completed if Performance Solution Required

5. Overview of ROK TAFE Consolidation Stg.2 Project

KLAD Studio has reviewed the prepared 60% Documentation for the ROK TAFE Consolidation Stg.2 Project located at CQUniversity, Bruce Highway, North Rockhampton, Qld, 4702.

KLAD Studio understands that the purpose of this project is to relocate the remaining CQU TAFE services at the Rockhampton City Campus to the Rockhampton North Campus. The Stg. 2 Project role is to advance the design from 30% to 60%.

KLAD Studio acknowledges that the Key Project Outcomes are

- CQU's vision is to create a functional, modern, and agile campus which is conducive to providing a positive student experience that fosters learning, collaboration, and innovation now, and into the future.
- Built environment that encourages collaboration and creativity
- Improvements to student life on campus
- Improvements to staff life on campus
- Improving accessibility
- Improving on and maximising space utilisation
- Improving connectivity
- Aligning with CQU brand identity

KLAD Studio understands that the Buildings in Scope are:

Stage 1

- Building 33 – Teaching & Admin Refurbishment to two levels of an existing three level building
- Building 34 – Minor refurbishment and external works for the Student Recreation space
- New Horticulture sheds - Building 76

Stage 2

- Building 19 – whole top floor refurbishment for Admin staff
- New Trades Building – Relocation of TAFE Trades departments into new standalone building - Building 92

Stage 3

- Building 36 – Whole building refurbishment for specialised Tafe faculties with public facing services

Out of Scope

- KLAD Studio understands that the Buildings or Spaces that are out of scope include
- Temporary Engineering shed
- Library internal moves
- Building 32 internal moves

Within each of these Buildings and Spaces, KLAD Studio will analyse the accessibility of all areas both internal and external that require accessibility.

Internal Areas:

- Customer Service Areas
- Meeting Spaces
- Emergency Egress / Evacuation
- Hearing Augmentation
- Internal Accessways
- Kitchen / Kitchenette Areas
- Lifts
- Change / Shower Facilities
- Toilets
- Internal Ramps
- Internal Stairs

External Areas:

- Accessible Car Parking
- Kerb Ramps
- CAPT from Bus stop and Accessible Car parking to entrance
- External Ramps
- External Stairs
- 17. Landscaping

General Items addressed throughout:

- Tactile Ground Surface Indicators (TGSi)
- Entrances
- Signage
- Lighting
- Contrasts
- Floor / Ground Surfaces

In general, at this early stage of design, there are indications of functional and technical acknowledgement of the Access to Premises Standard, AS 1428 series and the Disability Discrimination Act (DDA). Pathways, entrances, circulation spaces and sanitary facilities show signs of considering accessibility.

This report highlights key recommendations and/or items for clarification that have been identified to ensure functional compliance to the Premises Standard, (Disability (Access to Premises – Buildings) Standards 2010) with the consideration of Universal Design.

6 Legislation

The Access to Premises Standards as detailed within the National Construction Code 2022 and highlights the minimum level compliance requirements for Accessibility or Deemed to Satisfy Provisions. The Standard references the technical requirements of the built environment through the Australian Standard 1428 series.

Achieving compliance to the Access to Premises Standard goes a significant way to achieving compliance with the requirements of the Disability Discrimination Act (DDA).

A registered Building Surveyor/PCA is required prior to issuing permits, to confirm compliance with the requirements. Where the Deemed to Satisfy provisions are unable to be met, the Registered Building Surveyor/PCA can seek a Performance Solution from a relevant expert to detail Performance Compliance Solutions. For existing buildings these are increasing important as the cost and structural constraints to modify an existing building could make the modification not viable.

- The key elements of the Access to Premises Standard include:
- Part D3 – Access for People with a Disability.
- Part E3 – Passenger Lifts
- Part F2 – Sanitary and other facilities 1.4 Other Applicable Standards & Legislation
- Disability Discrimination Act (DDA) 1992.
- National Construction Code 2016.
- AS1428.1 – 2009, Part 1: General Requirements for Access – New Building

Work.

- AS1428.2 – 1992, Part 2: Enhanced and Additional Requirements – Buildings and Facilities.
- AS1428.4.1 – 2009, Part 4.1: Means to Assist the Orientation of People with Vision Impairment – TGSI.
- Disability (Access to Premises – Buildings) Standards 2010 (DAPS 2010).
- AS2890.1 – 2004, Part 1: Off-Street Car Parking.
- AS2890.6 – 2009, Part 6: Off-Street Parking for People with Disabilities.
- AS1735.12 1999 Lift facilities for people with disabilities.
- Part D3 – Access for People with a Disability.
- Part E3 – Passenger Lifts
- Part F2 – Sanitary and other facilities 1.4 Other Applicable Standards & Legislation
- Disability Discrimination Act (DDA) 1992.
- National Construction Code 2016.
- AS1428.1 – 2021, Part 1: General Requirements for Access – New Building Work.
- AS1428.2 – 1992, Part 2: Enhanced and Additional Requirements – Buildings and Facilities.
- AS1428.4.1 – 2009, Part 4.1: Means to Assist the Orientation of People with Vision

Impairment – TGSI.

- Disability (Access to Premises – Buildings) Standards 2010 (DAPS 2010).
- AS2890.1 – 2004, Part 1: Off-Street Car Parking.
- AS2890.6 – 2009, Part 6: Off-Street Parking for People with Disabilities.
- AS1735.12 1999 Lift facilities for people with disabilities.

7. Documentation Assessed

This report is specific to the following:

1. Drawings issued by Thomson Adsett on 30 January 2026

Dated	No.	Title	Rev.
30/01/2026	CQU-ROK-00-PDF_00-10	Overall Site Context Plan - Proposed	1
30/01/2026	CQU-ROK-019-PDF_20-01	Floor Plan - Level 3 - Part 1 Demolition	4
30/01/2026	CQU-ROK-019-PDF_20-02	Floor Plan - Level 3 - Part 2 Demolition	4
30/01/2026	CQU-ROK-019-PDF_21-01	Floor Plan - Level 3 - Part 1 Proposed	6
30/01/2026	CQU-ROK-019-PDF_21-02	Floor Plan - Level 3 - Part 2 Proposed	6
30/01/2026	CQU-ROK-019-PDF_23-01	Slab Plan - Level 3 - Part 1	1
30/01/2026	CQU-ROK-019-PDF_23-02	Slab Plan - Level 3 - Part 2	1
30/01/2026	CQU-ROK-019-PDF_25-01	Partition Plan - Level 3 - Part 1 Proposed	1
30/01/2026	CQU-ROK-019-PDF_25-02	Partition Plan - Level 3 - Part 2 Proposed	1
30/01/2026	CQU-ROK-019-PDF_26-01	Ceiling Plan - Level 3 - Part 1 Proposed	6
30/01/2026	CQU-ROK-019-PDF_26-02	Ceiling Plan - Level 3 - Part 2 Proposed	6
30/01/2026	CQU-ROK-019-PDF_28-01	Floor & Wall Finishes Plan - Level 3	1
30/01/2026	CQU-ROK-019-PDF_60-01	Rls - Bld19-L3 - Open Plan - 33 Workstations, Print & Reception	2
30/01/2026	CQU-ROK-019-PDF_60-02	Rls - Bld19-L3 - Open Plan - 33 Workstations, Reception	2
30/01/2026	CQU-ROK-019-PDF_60-03	Rls - Bld19-L3 - Open Plan - 4 Work Stations, Wait, Office	2
30/01/2026	CQU-ROK-019-PDF_60-04	Rls - Bld19-L3 - Meeting Rooms	2
30/01/2026	CQU-ROK-019-PDF_60-05	Rls - Bld19-L3 - Staff Kitchenette & Lounge	2
30/01/2026	CQU-ROK-019-PDF_60-06	Rls - Bld19-L3 - Pwd, Toilets	2
30/01/2026	CQU-ROK-21A-PDF_20-01	Engineering Department Demolition Plan	1
30/01/2026	CQU-ROK-21A-PDF_21-00	Engineering Department Ga Plans	1
30/01/2026	CQU-ROK-21A-PDF_60-001	Rls - Refurbished Shed	1
30/01/2026	CQU-ROK-21A-PDF_60-002	Rls - Additional Shed	1
30/01/2026	CQU-ROK-032-PDF_03-02	Ground Floor	3
30/01/2026	CQU-ROK-032-PDF_60-10	Rls - Building 32 - Ground Level - Offices	2
30/01/2026	CQU-ROK-033-PDF_10-00	Site Context Plan - Building 33	1
30/01/2026	CQU-ROK-033-PDF_20-01	Floor Plan - Level 1 - Demolition	4
30/01/2026	CQU-ROK-033-PDF_20-02	Floor Plan - Level 2 - Demolition	4
30/01/2026	CQU-ROK-033-PDF_20-03	Floor Plan - Roof - Demolition	4
30/01/2026	CQU-ROK-033-PDF_21-00	Floor Plan - Ground - Proposed	2
30/01/2026	CQU-ROK-033-PDF_21-01	Floor Plan - Level 1 - Proposed	6
30/01/2026	CQU-ROK-033-PDF_21-02	Floor Plan - Level 2 - Proposed	6
30/01/2026	CQU-ROK-033-PDF_21-03	Floor Plan - Roof - Proposed	5
30/01/2026	CQU-ROK-033-PDF_23-01	Slab Plan - Level 1	1
30/01/2026	CQU-ROK-033-PDF_23-02	Slab Plan - Level 2	1
30/01/2026	CQU-ROK-033-PDF_25-01	Partition Plan - Level 1	1
30/01/2026	CQU-ROK-033-PDF_25-02	Partition Plan - Level 2	1
30/01/2026	CQU-ROK-033-PDF_26-01	Ceiling Plan - Level 1 Proposed	5
30/01/2026	CQU-ROK-033-PDF_26-02	Ceiling Plan - Level 2 Proposed	5
30/01/2026	CQU-ROK-033-PDF_28-01	Finishes Plan - Bld33-L1	1
30/01/2026	CQU-ROK-033-PDF_28-02	Finishes Plan - Bld33-L1	1

Dated	No.	Title	Rev.
30/01/2026	CQU-ROK-033-PDF_30-01	Building Elevations - Proposed	3
30/01/2026	CQU-ROK-033-PDF_30-02	Building Elevations - Proposed	3
30/01/2026	CQU-ROK-033-PDF_31-01	Building Sections - Proposed	2
30/01/2026	CQU-ROK-033-PDF_40-00	Construction Details	1
30/01/2026	CQU-ROK-033-PDF_40-01	Construction Details	1
30/01/2026	CQU-ROK-033-PDF_60-01	Rls - Bld33-L1 - Education Teaching 1 & 2	2
30/01/2026	CQU-ROK-033-PDF_60-02	Rls - Bld33-L1 - Bookable Classroom & General Store	2
30/01/2026	CQU-ROK-033-PDF_60-03	Rls - Bld33-L1 - Computer Lab	2
30/01/2026	CQU-ROK-033-PDF_60-04	Rls - Bld33-L1 - Dark Room, Store & Print Making	2
30/01/2026	CQU-ROK-033-PDF_60-05	Rls - Bld33-L1 - Open Workshop & Online Film	2
30/01/2026	CQU-ROK-033-PDF_60-06	Rls - Bld33-L1 - Digital Design, Jewellery & Student Breakout	2
30/01/2026	CQU-ROK-033-PDF_60-07	Rls - Bld33-L1 - Male & Female Toilets, Pwd	2
30/01/2026	CQU-ROK-033-PDF_60-20	Rls - Bld33-L2 - Open Plan Workstation - 36 Desks (Print) - Sheet 1	2
30/01/2026	CQU-ROK-033-PDF_60-21	Rls - Bld33-L2 - Open Plan Workstation - 36 Desks (Print) - Sheet 2	2
30/01/2026	CQU-ROK-033-PDF_60-22	Rls - Bld33-L2 - Open Plan Workstation - 6 & 10 Desks	2
30/01/2026	CQU-ROK-033-PDF_60-23	Rls - Bld33-L2 - Meeting Rooms	2
30/01/2026	CQU-ROK-033-PDF_60-24	Rls - Bld33-L2 - Quiet Rooms	2
30/01/2026	CQU-ROK-033-PDF_60-25	Rls - Bld33-L2 - Quiet Rooms, Memorabilia, Print & B32 Entry	2
30/01/2026	CQU-ROK-033-PDF_60-26	Rls - Bld33-L2 - 1px Offices	2
30/01/2026	CQU-ROK-033-PDF_60-27	Rls - Bld33-L2 - Staff Room & Outdoor Balcony	2
30/01/2026	CQU-ROK-033-PDF_60-28	Rls - Bld33-L2 - Male & Female Toilets, Pwd	2
30/01/2026	CQU-ROK-034-PDF_20-01	Floor Plan - Ground G.08 - Demolition	2
30/01/2026	CQU-ROK-034-PDF_21-01	Floor & Ceiling Plan - Ground G.08 - Proposed	2
30/01/2026	CQU-ROK-034-PDF_28-01	Finishes Plan - Bld34-Gl	1
30/01/2026	CQU-ROK-034-PDF_60-01	Rls - Bld34-Gl - Student Recreation (Dining	2
30/01/2026	CQU-ROK-036-PDF_10-00	Site Context Plan - Building 36	1
30/01/2026	CQU-ROK-036-PDF_20-01	Floor Plan - Ground Floor - Demolition	3
30/01/2026	CQU-ROK-036-PDF_20-02	Floor Plan - Level 1 - Demolition	3
30/01/2026	CQU-ROK-036-PDF_21-01	Floor Plan - Ground Floor - Proposed	4
30/01/2026	CQU-ROK-036-PDF_21-02	Floor Plan - Level 1 - Proposed	4
30/01/2026	CQU-ROK-036-PDF_21-03	Floor Plan - Roof Plan_Proposed	3
30/01/2026	CQU-ROK-036-PDF_23-01	Slab Plan - Ground Floor	1
30/01/2026	CQU-ROK-036-PDF_23-02	Slab Plan - Level 1	1
30/01/2026	CQU-ROK-036-PDF_26-01	Partition Plan - Ground Floor	1
30/01/2026	CQU-ROK-036-PDF_26-02	Partition Plan - Level 1	1
30/01/2026	CQU-ROK-036-PDF_27-01	Ceiling Plan - Ground Floor	4
30/01/2026	CQU-ROK-036-PDF_27-02	Ceiling Plan - Level 1	4
30/01/2026	CQU-ROK-036-PDF_28-01	Ground Level - Finishes Plan	2
30/01/2026	CQU-ROK-036-PDF_28-02	Level 1 - Finishes Plan	2
30/01/2026	CQU-ROK-036-PDF_30-01	Building Elevations - Proposed	2

Dated	No.	Title	Rev.
30/01/2026	CQU-ROK-036-PDF_30-02	Building Elevations - Proposed	2
30/01/2026	CQU-ROK-036-PDF_31-01	Building Sections - Proposed	2
30/01/2026	CQU-ROK-036-PDF_40-00	Construction Details	1
30/01/2026	CQU-ROK-036-PDF_40-01	Construction Details	1
30/01/2026	CQU-ROK-036-PDF_60-01	Rls - Restaurant Zone	2
30/01/2026	CQU-ROK-036-PDF_60-02	Rls - Restaurant Zone	2
30/01/2026	CQU-ROK-036-PDF_60-03	Rls - Store & Bar (Hospitality)	2
30/01/2026	CQU-ROK-036-PDF_60-04	Rls - Laundry & Change Room	2
30/01/2026	CQU-ROK-036-PDF_60-05	Rls - Training Kitchen	2
30/01/2026	CQU-ROK-036-PDF_60-06	Rls - Training Kitchen - Elevations	2
30/01/2026	CQU-ROK-036-PDF_60-07	Rls - Pwd & Toilets	2
30/01/2026	CQU-ROK-036-PDF_60-10	Rls - Beauty Studio	1
30/01/2026	CQU-ROK-036-PDF_60-11	Rls - Sterilization, Office & Store Beauty Studio	2
30/01/2026	CQU-ROK-036-PDF_60-12	Rls - Combined Laundry	2
30/01/2026	CQU-ROK-036-PDF_60-13	Rls - Hairdressing General Plan	2
30/01/2026	CQU-ROK-036-PDF_60-14	Rls - Hairdressing, Colour Bar, Store, Office	2
30/01/2026	CQU-ROK-036-PDF_60-15	Rls - Toilets	2
30/01/2026	CQU-ROK-036-PDF_60-16	Rls - Pwd, Ambulant	2
30/01/2026	CQU-ROK-036-PDF_70-01	Key Joinery Intent - Restuarant Zone	2
30/01/2026	CQU-ROK-036-PDF_70-02	Key Joinery Intent - Hairdressing	1
30/01/2026	CQU-ROK-036-PDF_70-03	Key Joinery Intent - Beauty	2
30/01/2026	CQU-ROK-076-PDF_10-00	Horticulture Site Plan	2
30/01/2026	CQU-ROK-076-PDF_21-00	Horticulture Floor Plan	4
30/01/2026	CQU-ROK-076-PDF_21-20	Horticulture Roof Plan	3
30/01/2026	CQU-ROK-076-PDF_60-001	Rls - Horticulture Outdoor Planting	1
30/01/2026	CQU-ROK-076-PDF_60-002	Rls - Horticulture - Student Lunch Area	1
30/01/2026	CQU-ROK-076-PDF_60-003	Rls - Horticulture - Store	1
30/01/2026	CQU-ROK-076-PDF_60-004	Rls - Horticulture - Drop Off/Deliveries	1
30/01/2026	CQU-ROK-076-PDF_60-005	Rls - Horticulture - Covered Outdoor / Potting	1
30/01/2026	CQU-ROK-076-PDF_60-006	Rls - Horticulture - Propagation	1
30/01/2026	CQU-ROK-076-PDF_60-007	Rls - Horticulture - Shade Area / Greenhouse	1
30/01/2026	CQU-ROK-076-PDF_60-008	Rls - Horticulture - Greenhouse	1
30/01/2026	CQU-ROK-092-PDF_00-02	General Annotations	1
30/01/2026	CQU-ROK-092-PDF_10-00	Site Plan / External Works	2
30/01/2026	CQU-ROK-092-PDF_20-00	Site Plan - Demolition	2
30/01/2026	CQU-ROK-092-PDF_21-00	Ga Plan Ground Level	8
30/01/2026	CQU-ROK-092-PDF_21-01	Floor Plan Ground Level - Zone 1	3
30/01/2026	CQU-ROK-092-PDF_21-02	Floor Plan Ground Level - Zone 2	3
30/01/2026	CQU-ROK-092-PDF_21-03	Floor Plan Ground Level - Zone 3	3
30/01/2026	CQU-ROK-092-PDF_21-10	Ga Plan Level 01	8

Dated	No.	Title	Rev.
30/01/2026	CQU-ROK-092-PDF_21-11	Floor Plan Level 01 - Zone 1	3
30/01/2026	CQU-ROK-092-PDF_21-12	Floor Plan Level 01 - Zone 2	3
30/01/2026	CQU-ROK-092-PDF_21-20	Ga Plan Roof Level	4
30/01/2026	CQU-ROK-092-PDF_23-01	Structural Setout Ground Level - Zone 1	1
30/01/2026	CQU-ROK-092-PDF_23-02	Structural Setout Ground Level - Zone 2	1
30/01/2026	CQU-ROK-092-PDF_23-03	Structural Setout Ground Level - Zone 3	1
30/01/2026	CQU-ROK-092-PDF_23-11	Structural Setout Level 01 - Zone 1	1
30/01/2026	CQU-ROK-092-PDF_23-12	Structural Setout Level 01 - Zone 2	1
30/01/2026	CQU-ROK-092-PDF_26-01	Partition Plan Ground Level - Zone 1	1
30/01/2026	CQU-ROK-092-PDF_26-02	Partition Plan Ground Level - Zone 2	1
30/01/2026	CQU-ROK-092-PDF_26-03	Partition Plan Ground Level - Zone 3	1
30/01/2026	CQU-ROK-092-PDF_26-11	Partition Plan Level 01 - Zone 1	1
30/01/2026	CQU-ROK-092-PDF_26-12	Partition Plan Level 01 - Zone 2	1
30/01/2026	CQU-ROK-092-PDF_27-01	Reflected Ceiling Plan Ground Level - Zone 1	4
30/01/2026	CQU-ROK-092-PDF_27-02	Reflected Ceiling Plan Ground Level - Zone 2	3
30/01/2026	CQU-ROK-092-PDF_27-03	Reflected Ceiling Plan Ground Level - Zone 3	3
30/01/2026	CQU-ROK-092-PDF_27-11	Reflected Ceiling Plan Level 01 - Zone 1	4
30/01/2026	CQU-ROK-092-PDF_27-12	Reflected Ceiling Plan Level 01 - Zone 2	3
30/01/2026	CQU-ROK-092-PDF_28-01	Floor & Wall Finishes Plan Ground Level - Zone 1	1
30/01/2026	CQU-ROK-092-PDF_28-02	Floor & Wall Finishes Plan Ground Level - Zone 2	1
30/01/2026	CQU-ROK-092-PDF_28-03	Floor & Wall Finishes Plan Ground Level - Zone 3	1
30/01/2026	CQU-ROK-092-PDF_28-11	Floor & Wall Finish Plan Level 01 - Zone 1	1
30/01/2026	CQU-ROK-092-PDF_28-12	Floor & Wall Finish Plan Level 01 - Zone 2	1
30/01/2026	CQU-ROK-092-PDF_30-01	Ga Elevations Sheet 1	3
30/01/2026	CQU-ROK-092-PDF_30-02	Ga Elevations Sheet 2	3
30/01/2026	CQU-ROK-092-PDF_30-10	Building Elevations - North	1
30/01/2026	CQU-ROK-092-PDF_30-11	Building Elevations - South	1
30/01/2026	CQU-ROK-092-PDF_30-12	Building Elevations - East	1
30/01/2026	CQU-ROK-092-PDF_30-13	Building Elevations - West	1
30/01/2026	CQU-ROK-092-PDF_31-01	Ga Sections Sheet 1	2
30/01/2026	CQU-ROK-092-PDF_31-02	Ga Sections Sheet 2	2
30/01/2026	CQU-ROK-092-PDF_31-03	Building Sections - Sheet 1	1
30/01/2026	CQU-ROK-092-PDF_31-04	Building Sections - Sheet 2	1
30/01/2026	CQU-ROK-092-PDF_31-05	Building Sections - Sheet 3	1
30/01/2026	CQU-ROK-092-PDF_31-06	Building Sections - Sheet 4	1
30/01/2026	CQU-ROK-092-PDF_31-07	Building Sections - Sheet 5	1
30/01/2026	CQU-ROK-092-PDF_31-08	Building Sections - Sheet 6	1

Dated	No.	Title	Rev.
30/01/2026	CQU-ROK-092-PDF_42-01	Stair 01 - Details	1
30/01/2026	CQU-ROK-092-PDF_42-02	Stair 02 - Details	1
30/01/2026	CQU-ROK-092-PDF_42-03	Stair 03 - Details	1
30/01/2026	CQU-ROK-092-PDF_44-01	Screen Details	1
30/01/2026	CQU-ROK-092-PDF_44-02	Screen Details	1
30/01/2026	CQU-ROK-092-PDF_44-03	Screen Details	1
30/01/2026	CQU-ROK-092-PDF_44-04	Screen Details	1
30/01/2026	CQU-ROK-092-PDF_44-05	Screen Details	1
30/01/2026	CQU-ROK-092-PDF_52-01	External Glazing Elevations	1
30/01/2026	CQU-ROK-092-PDF_52-02	External Glazing Elevations	1
30/01/2026	CQU-ROK-092-PDF_52-03	Louvre Elevations	1
30/01/2026	CQU-ROK-092-PDF_52-11	Internal Glazing Elevations	1
30/01/2026	CQU-ROK-092-PDF_52-12	Internal Glazing Elevations	1
30/01/2026	CQU-ROK-092-PDF_60-001	Rls - Auto - Gf - Workshop	1
30/01/2026	CQU-ROK-092-PDF_60-002	Rls - Auto - Gf - Workshop	1
30/01/2026	CQU-ROK-092-PDF_60-003	Rls - Auto - Gf - Battery Store	1
30/01/2026	CQU-ROK-092-PDF_60-004	Rls - Auto - Gf - Store	1
30/01/2026	CQU-ROK-092-PDF_60-005	Rls - Auto - Gf - Chasis Dynamometer	1
30/01/2026	CQU-ROK-092-PDF_60-006	Rls - Auto - Gf - Washdown	1
30/01/2026	CQU-ROK-092-PDF_60-007	Rls - Auto - Gf - Online Teaching	1
30/01/2026	CQU-ROK-092-PDF_60-008	Rls - Auto - Gf - Theory Room 1	1
30/01/2026	CQU-ROK-092-PDF_60-009	Rls - Auto - Gf - Theory Room 3	1
30/01/2026	CQU-ROK-092-PDF_60-010	Rls - Auto - Gf - Outdoor Car Storage	1
30/01/2026	CQU-ROK-092-PDF_60-011	Rls - F&M - Gf - Workshop (Fitting & Machining)	1
30/01/2026	CQU-ROK-092-PDF_60-012	Rls - F&M - Gf - Workshop (Fitting & Machining)	1
30/01/2026	CQU-ROK-092-PDF_60-013	Rls - F&M - Gf - Workshop (Fitting & Machining)	1
30/01/2026	CQU-ROK-092-PDF_60-014	Rls - F&M - Gf - Cnc Room	1
30/01/2026	CQU-ROK-092-PDF_60-015	Rls - F&M - Gf - Heat Treatment Room	1
30/01/2026	CQU-ROK-092-PDF_60-016	Rls - F&M - Gf - Precision Measure	1
30/01/2026	CQU-ROK-092-PDF_60-017	Rls - F&M - Gf - Store Room	1
30/01/2026	CQU-ROK-092-PDF_60-018	Rls - F&M - Gf - Cad Classroom	1
30/01/2026	CQU-ROK-092-PDF_60-019	Rls - F&M - Gf - Class Room / Theory	1
30/01/2026	CQU-ROK-092-PDF_60-020	Rls - Metfab - Gf - Arc Welding / Metal Fabrication	1
30/01/2026	CQU-ROK-092-PDF_60-021	Rls - Metfab - Gf - Arc Welding / Metal Fabrication	1
30/01/2026	CQU-ROK-092-PDF_60-022	Rls - Metfab - Gf - Arc Welding / Metal Fabrication	1
30/01/2026	CQU-ROK-092-PDF_60-023	Rls - Metfab - Gf - Typical Arc Weld Bays	1
30/01/2026	CQU-ROK-092-PDF_60-024	Rls - Metfab - Gf - Grind	1
30/01/2026	CQU-ROK-092-PDF_60-025	Rls - Metfab - Gf - Demonstration	1
30/01/2026	CQU-ROK-092-PDF_60-026	Rls - Metfab - Gf - Store Room (Metal Fabrication)	1
30/01/2026	CQU-ROK-092-PDF_60-027	Rls - Metfab - Gf - Store	1

Dated	No.	Title	Rev.
30/01/2026	CQU-ROK-092-PDF_60-028	Rls - Metfab - Gf - Gas Manifold	1
30/01/2026	CQU-ROK-092-PDF_60-029	Rls - Metfab - Gf - Theory Room	1
30/01/2026	CQU-ROK-092-PDF_60-030	Rls - Shared - Gf - Shared Theory Room - G.05	1
30/01/2026	CQU-ROK-092-PDF_60-031	Rls - Shared - Gf - External Covered Hardstand	1
30/01/2026	CQU-ROK-092-PDF_60-032	Rls - Shared - Gf - Wall Mounted Storage	1
30/01/2026	CQU-ROK-092-PDF_60-033	Rls - Shared - Gf - Shared Theory Room - G.74	1
30/01/2026	CQU-ROK-092-PDF_60-034	Rls - Trades - Gf - Student Kitchenette / Lounge	1
30/01/2026	CQU-ROK-092-PDF_60-035	Rls - Trades - Gf - Student Kitchenette / Lounge	1
30/01/2026	CQU-ROK-092-PDF_60-036	Rls - Trades - Gf - Circulation / Wait	1
30/01/2026	CQU-ROK-092-PDF_60-037	Rls - Trades - Gf - Circulation / Wait	1
30/01/2026	CQU-ROK-092-PDF_60-038	Rls - Shared - Gf - Entry Foyer	1
30/01/2026	CQU-ROK-092-PDF_60-039	Rls - Refrig - L1 - Refrigeration Workshop	1
30/01/2026	CQU-ROK-092-PDF_60-040	Rls - Refrig - L1 - Refrigeration Workshop	1
30/01/2026	CQU-ROK-092-PDF_60-041	Rls - Refrig - L1 - Storage	1
30/01/2026	CQU-ROK-092-PDF_60-042	Rls - Refrig - L1 - Clean Workshop	1
30/01/2026	CQU-ROK-092-PDF_60-043	Rls - Refrig - L1 - Theory Room	1
30/01/2026	CQU-ROK-092-PDF_60-044	Rls - Trades - L1 - Circulation / Wait	1
30/01/2026	CQU-ROK-092-PDF_60-045	Rls - Staff - L1 - Teaching Staff Open Office	1
30/01/2026	CQU-ROK-092-PDF_60-046	Rls - Staff - L1 - Shared Meeting Room	1
30/01/2026	CQU-ROK-092-PDF_60-047	Rls - Staff - L1 - 1 Person Meeting Room	1
30/01/2026	CQU-ROK-092-PDF_60-048	Rls - Staff - L1 - Staff Kitchenette / Lounge	1
30/01/2026	CQU-ROK-092-PDF_60-049	Rls - Shared - L1 - Shared Theory Room	1
30/01/2026	CQU-ROK-092-PDF_60-130	Wet Area Layouts - Sheet 1	1
30/01/2026	CQU-ROK-092-PDF_60-131	Wet Area Layouts - Sheet 2	1
30/01/2026	CQU-ROK-092-PDF_60-132	Wet Area Layouts - Sheet 3	1
30/01/2026	CQU-ROK-092-PDF_70-00-1	Joinery Details Sheet 01	1

KLAD DIRECTOR | ARCHITECT | ACCESS CONSULTANT



Katie Devitt

QUALIFICATIONS

Registration 2019 BOAQ # 5495
 Certificate IV Access Consulting
 Master of Architecture, QUT
 Bachelor of Design, QUT
 Bachelor of Commerce, University of Queensland
 Bachelor of Economics, University of Queensland

AFFILIATIONS

Member of the Australian Institute of Architects
 Committee Member of Queensland Equity Diversity and Inclusion Committee of the RAIA QLD (QEDIC)
 Committee Member of Architecture with Pride QLD (AWP)
 Member of National Association of Women in Construction (NAWIC)

PROFESSIONAL EXPERIENCE

Katie has worked in a variety of roles throughout multiple stages of the project life cycle; from the project definition stage, conceptual design through to detailed design and construction documentation.

Highly proficient in a variety of 3D modelling and graphic design softwares including: Revit, AutoCAD, ArchiCAD, SketchUp, Photoshop, Indesign, Illustrator.

2023 - current Architect and Access Consultant - KLAD Studio

2023 - current Architect / Access Consultant (part-time) - Fulton Trotter Architects

2022 -2023 Architect: Guymer Bailey Architects (Brisbane)

2020 - 2022 Compliance Manager / Architect: HASSELL

2017 - 2019 Graduate Architect / Architect: JACOBS

2014 - 2015 Graduate Architect: HASSELL

2014 Student Architect: DWP SUTERS

2013 - 2014 Scholarship - Research Assistant - Centre for Subtropical Design

2013 -2014 Project Manager - RFDS

1996- 2002 + 2006-2007- IT Financial Manager - Accenture

PROJECTS

ACCESS CONSULTING

Boyne Tannum Aquatic Centre, Gladstone 2023 - Current.

Arthur Gorrie Correctional Centre Upgrade - 2023

Mt. Gravatt Tafe Upgrade to Amenities - 2024 - 2025.

CORRECTIONS & JUSTICE - ARCHITECTURE

Southern Queensland Correctional Precinct Stage 2, QLD 2020-2023 \$861m

Tauranga Monana Innovative Courthouse, Tauranga, NZ, 2021 - present, \$95m

HEALTH/AGED CARE/RETIREMENT - ARCHITECTURE

New Dunedin Hospital Project, Dunedin, New Zealand, 2019, \$NZ1.2b

Ipswich Hospital Redevelopment Project, 2018, \$162m

Nambour Hospital Redevelopment, 2017, \$86.2m

Documentation for GoldCoast Private Hospital Project, 2014, \$150m

Royal Flying Doctor Service Queensland Section (RFDS), 2013, \$7.5m

Appendices

APPENDIX A

MARKUP OF 60% DESIGN

APPENDIX B

ACCESSIBILITY AUDIT DETAIL AT 60% DESIGN

BUILDING

STATUS OF MARKUP

STATUS OF AUDIT

1	Building ROK-019
2	Building ROK-032
3	Building ROK-033 - Level 1
4.	Building ROK-033 - Level 2
5.	Building ROK-034
6.	Building ROK-036 - Ground
7.	Building ROK-036 - Level 1
8.	Building ROK-076
9.	Building ROK-092 - Ground
10.	Building ROK-092 - Level 1

60% Markup
60% Markup
60% Markup
60% Markup
60% Markup
60% Markup
60% Markup
60% Markup
60% Markup
60% Markup

60% Access Audit
60% Access Audit
60% Access Audit
60% Access Audit
60% Access Audit
60% Access Audit
60% Access Audit
60% Access Audit
60% Access Audit
60% Access Audit