

DO NOT SCALE



PAD FOOTING SCHEDULE			
MARK	DIMENSIONS		
	LENGTH	WIDTH	DEPTH
PF1	2200	2200	750
PF2	3500	3500	1000
PF3	1500	1500	800
PF4	1200	1200	600

STRIP FOOTING SCHEDULE			
MARK	DIMENSIONS		REINFORCEMENT
	WIDTH	DEPTH	
SF1	1200	600	
SF2	600	600	

FOUNDATION PLAN:

FOUNDATION NOTES:

- PROVIDE BLINDING CONCRETE AS REQUIRED TO FOUND PAD FOOTINGS INTO NATURAL VERY STIFF OR STRONGER SOILS OR WEATHERED ROCK WITH ALLOWABLE BEARING CAPACITY OF 250KPa. SUITABLY QUALIFIED GEOTECHNICAL ENGINEER TO INSPECT ALL EXCAVATION TO VERIFY ASSUMED BEARING CAPACITY.
- UNLESS NOTED OTHERWISE THE CENTROIDS OF ALL FOUNDATIONS ARE TO BE CONCENTRIC WITH THE CENTERLINES OF COLUMNS, WALLS AND BEAMS OVER.
- REFER ARCHITECT FOR ALL SETOUT

NOTES:

- THE CONTRACTOR WILL BE RESPONSIBLE FOR PROVING & PROTECTING ALL EXISTING IN-GROUND & ABOVE GROUND SERVICES. THE CONTRACTOR WILL MAKE SUITABLE ALLOWANCES FOR PERMANENT & TEMPORARY SERVICES DIVERSION IN CONJUNCTION WITH ADVICE FROM CIVIL & SERVICES ENGINEERS. ANY EXISTING SERVICES SHOWN ON THESE SECTIONS SHALL BE TAKEN AS INDICATIVE.
- IT WILL BE THE CONTRACTORS RESPONSIBILITY FOR SURVEYING AND PROVING LOCATIONS OF EXISTING IN-GROUND STRUCTURES. ANY EXISTING IN-GROUND STRUCTURES SHOWN ON THIS DRAWING SHALL BE TAKEN AS INDICATIVE. ANY RETENTION SHOWN AT EXISTING BUILDING LOCATIONS SHALL BE TAKEN AS INDICATIVE. THE CONTRACTOR SHALL PROVE ALL LOCATIONS, DEPTH & SETTING-OUT AND PROVIDE INFORMATION TO STRUCTURAL ENGINEER FOR FINALISATION OF RETENTION DESIGN.
- THE CONTRACTOR SHALL MAKE SUITABLE ALLOWANCES FOR EXISTING CONDITIONS.
- DILAPIDATION SURVEY TO BE UNDERTAKEN TO ADJOINING BUILDINGS PRIOR TO EXCAVATION & RETENTION WORKS. REFER GEOTECHNICAL REPORT FOR RECOMMENDATIONS REGARDING IN-GROUND INSTRUMENTATION & MONITORING TO ASSESS LATERAL PERFORMANCE OF BASEMENT CONDITION & EXISTING STRUCTURE.
- REFER GEOTECHNICAL REPORT FOR RECOMMENDATIONS REGARDING TEMPORARY DEWATERING AT EXCAVATIONS.
- LOCALISED EXCAVATIONS FOR PITS, SUMPS, GENERAL FOOTINGS, TRENCHES, IN-GROUND SERVICES (INCLUDING TANKS) NOT SHOWN.

CONCRETE REQ RATES:

STRIP FOOTINGS 80 kg/m³
PAD FOOTINGS 100 kg/m³
CORE RAFTS 130 kg/m³

INFORMATION REFLECTED ON THIS DRAWING REPRESENTS STRUCTURAL DESIGN DEVELOPED FOR D&C TENDER ADVICE ONLY, AND SHOULD NOT BE REGARDED AS COMPLETE. THE D&C CONTRACTOR SHOULD REFER TO ALL ASSOCIATED ARCHITECTURAL AND OTHER DISCIPLINE DRAWINGS, PROJECT BRIEFS AND CLIENT REQUIREMENTS AND MAKE ADEQUATE ALLOWANCES FOR ALL NECESSARY STRUCTURAL WORKS TO MEET THESE REQUIREMENTS, EQUIPMENT SCHEDULES AND COMPLIANCE WITH THE NCC & APPROPRIATE AUSTRALIAN STANDARDS

DRAWING STATUS:		DESIGN DEVELOPMENT	
A	12.02.2026	MSB	ISSUED FOR D&C TENDER
P1	30.03.2026	P3H	DRAFT 60% DD ISSUE FOR REVIEW
REV	DATE	BY	DESCRIPTION
		CHK	APP



http://www.wsp.com

CLIENT:



THOMSON ADSETT + PEDDLE THORP

PROJECT:

CQU ROCKHAMPTON TAFE
CONSOLIDATION - STAGE 2

TITLE:

BuildingName
LEVEL G - FOUNDATION ARRANGEMENT PLAN -
SHEET 01

SCALE @ A1:

1:100

CHECKED:

BM

APPROVED:

DG

PROJECT NUMBER:

PS2229518

DRAWN:

P3H

DATE:

14.01.2026

DRAWING No:

92-ST-DR-GDL-410-00-01

REV:

A

© WSP Australia Pty Ltd