

FOR CONTINUATION REFER DRAWING No. L01-510-00-01

SUSPENDED PLAN:

UNLESS NOTED OTHERWISE

CONCRETE GRADE:

ALL FLOOR ELEMENTS :

F_c = N40 MPa . U.N.O.

CONCRETE REO RATES:

POST TENSIONING REO RATE = 6 kg/m²

BAR REO RATE = 45 kg/m²

SLAB THICKNESS:

SLABS TO BE POST TENSIONED U.N.O.

SLAB THICKNESS AND REINFT. TYPE
PT = POST TENSIONED,
RC = TRADITIONAL RC
?? - N??? - ? - FORM WORK/MATERIAL
GRADE/REINFT. RATE/PT RATE

CONCRETE BEAMS:

BEAMS TO BE POST TENSIONED U.N.O.

???Dx???W-PT

?? - N??? - ? - FORM WORK/MATERIAL
GRADE/REINFT. RATE/PT RATE

STEEL COMPOSITE BEAMS:

???UB???

?? - ??? - ? - ROWS - SPACING/NO. OF
STUDS/PRE-CAMBER (mm)

DENOTES STEEL BEAMS WHERE SHEAR STUDS ARE
REQUIRED ALL STUDS TO BE 19mm DIAMETER SHEAR
STUDS U.N.O.

STRUCTURAL LEGEND:

- LOAD BEARING RC OVER
- LOAD BEARING PRECAST OVER
- LOAD BEARING MASONRY OVER
- STEEL
- LOAD BEARING RC UNDER
- LOAD BEARING PRECAST UNDER
- LOAD BEARING MASONRY UNDER
- CWxxx CORE WALL
- RCxxx REINFORCED CONCRETE WALL
- MWxxx MASONRY WALL
- PWxxx PRECAST WALL

PENETRATIONS AND SETDOWNS

- FORMED PENETRATION. EXACT
LOCATIONS & SIZES OF PENETRATIONS
TO BE CONFIRMED/COORDINATION
WITH SERVICES ENGINEER
- SETDOWN AREA
WET AREAS: XXXmm MAX.
MINIMUM SLAB DEPTH XXXmm

STRUCTURAL STEPS, FOLDS & HOBS:

APPROPRIATE ALLOWANCES TO BE MADE FOR HOBS
AND FOLDS IN STRUCTURE TO
ACCOMMODATE ARCHITECTURAL SETDOWNS.

LIGHTWEIGHT FACADE ELEMENTS:

ALL FACADE ELEMENTS TO BE LIGHTWEIGHT
UNLESS NOTED OTHERWISE ON PLAN.
i.e. NO ADDITIONAL NON LOAD BEARING PRECAST
OTHER THAN SHOWN AND CALLED UP ON PLAN.

R.C. WALLS / SHEAR WALLS:

REFER ARCHITECTS FOR WATERPROOFING AND
DRAINAGE OF WET AREAS.

CRANE LOADING:

GANTRY CRANE OF 3.2T SWL IS SUPPORTED BY
CRANE BEAMS DENOTED CB
WHEEL LOADS ASSUMED:
VERTICAL 40KN
LATERAL 7.2KN
BUFFER 40KN

INFORMATION REFLECTED ON THIS DRAWING REPRESENTS STRUCTURAL DESIGN
DEVELOPED FOR D&C TENDER ADVICE ONLY, AND SHOULD NOT BE REGARDED AS
COMPLETE. THE D&C CONTRACTOR SHOULD REFER TO ALL ASSOCIATED
ARCHITECTURAL AND OTHER DISCIPLINE DRAWINGS, PROJECT BRIEFS AND CLIENT
REQUIREMENTS AND MAKE ADEQUATE ALLOWANCES FOR ALL NECESSARY
STRUCTURAL WORKS TO MEET THESE REQUIREMENTS, EQUIPMENT SCHEDULES
AND COMPLIANCE WITH THE NCC & APPROPRIATE AUSTRALIAN STANDARDS

A	12.02.2026	MSB	ISSUED FOR DMC TENDER			BM	DG
P1	30.01.2026	PJH	DRAFT 60% DD ISSUE FOR REVIEW			BM	DG
REV	DATE	BY	DESCRIPTION			CHK	APP
DRAWING STATUS: DESIGN DEVELOPMENT							



<http://www.wsp.com>

CLIENT:

ARCHITECT:
THOMSON ADSETT + PEDDLE THORP

PROJECT:
CQU ROCKHAMPTON TAFE
CONSOLIDATION - STAGE 2
TITLE:
BuildingName
LEVEL 01 - GENERAL ARRANGEMENT PLAN - SHEET
02

SCALE @ A1: 1:100	CHECKED: BM	APPROVED: DG
PROJECT NUMBER: PS229518	DRAWN: PJH	DATE: 14.01.2026
DRAWING No: 92-ST-DR-L01-510-00-02		REV: A
© WSP Australia Pty Ltd		