SYMBOLS

SERVICE IDENTIFIER
- DIRECTION OF FLOW
- SYSTEM ABBREVIATION
- PIPEWORK SIZE / RISER NUMBER
- DIRECTION OF FLOW

CONTINUATION REFERENCE
- DRAWING NUMBER (VIEW NUMBER)
- CONTINUATION DIRECTION

SECTION MARKER
- VIEW DIRECTION
- VIEW NUMBER
- DRAWING NUMBER

CALLOUT MARKER
- VIEW DIRECTION
- VIEW NUMBER
- DRAWING NUMBER

GENERAL
- CAP
- CONTINUATION
- CHANGE IN SIZE / GRADE / MATERIAL
- CUT-IN / PIPE BREAK
- CONTROL PANEL
- FLOW DIRECTION
- RISER / DROPPER / TEE
- ACCESS PANEL
- VALVE BOX - IN-GROUND

WATER
- BALANCING VALVE
- ISOLATION VALVE
- CONTROL VALVE - FLOAT
- CONTROL VALVE - SOLENOID
- DOUBLE CHECK VALVE
- EMERGENCY EYEWASH
- EMERGENCY SHOWER
- EXPANSION CONTROL VALVE
- FILTER
- GAUGE - PRESSURE
- GAUGE - TEMPERATURE
- HOSE TAP
- HOT WATER UNIT
- PUMP
- PRESSURE REDUCTION VALVE
- REDUCED PRESSURE ZONE DEVICE
- SINGLE CHECK / NON RETURN VALVE
- STRAINER
- TEMPERATURE PRESSURE RELIEF VALVE
- TEMPERING VALVE
- THERMOSTATIC MIXING VALVE
- UNION
- WATER SUPPLY - COLD
- WATER SUPPLY - HOT
- WATER SUPPLY - HOT & COLD

GAS
- BAYONET POINT
- EXPANSION FITTING
- FILTER
- GAS METER (AUTHORITY)
- ISOLATION VALVE
- PRESSURE REGULATOR
- PRESSURE REGULATOR WITH OVER-PRESSURE PROTECTION
- SLAM SHUT BUTTON
- SLAM SHUT VALVE

DRAINAGE
- AIR ADMITTANCE VALVE
- REFLUX VALVE
- INSPECTION CHAMBER
- GRATED TRENCH DRAIN
- STORMWATER PIT
- FLOOR WASTE / GRATED OUTLET
- FLOOR WASTE - BASKET TRAP
- PLANTER DRAIN OUTLET
- OVERFLOW RELIEF GULLY / DISCONNECTOR GULLY
- INSPECTION OPENING TO SURFACE
- RAINWATER OUTLET
- TUNDISH / TRAPPED TUNDISH
- TUNDISH / TRAPPED TUNDISH - IN-WALL

HYDRAULIC SERVICES LEGEND - GENERAL

AAV	AIR ADMITTANCE VALVE
AC	AIR CONDITIONING
AFFL	ABOVE FINISHED FLOOR LEVEL
AP	ACCESS PANEL
ASSL	ABOVE STRUCTURAL SLAB LEVEL
B	BASIN / VANITY BASIN / HANDBASIN
BCWU	BOILING CHILLED WATER UNIT
BCHWU	BOILING CHILLED HOT WATER UNIT
BDO	BALCONY DRAIN OUTLET
BFW	BASKET FLOOR WASTE
BV	BALANCING VALVE
CD	CONDENSATE DRAIN
CHV	CHAMBER VENT
CI	CAST IRON
CIS	CAST IN SLAB
CP	CONTROL PANEL
CSK	CLEANERS SINK
CTE	CONNECT TO EXISTING
CV	CHECK VALVE
CW	COLD WATER
Ø	DIAMETER
DCHV	DOUBLE CHECK VALVE
DCW	DRINKING COLD WATER
DF	DRINKING FOUNTAIN
DG	DISCONNECTOR GULLY
DWG	DRAWING
DW	DISH WASHER
ECV	EXPANSION CONTROL VALVE
EJ	EXPANSION JOINT
EPD	ELEVATED PIPEWORK DROPPER
EEW	EMERGENCY EYE WASH
e	EXISTING
FA	FROM ABOVE
FB	FROM BELOW
FFL	FINISHED FLOOR LEVEL
FU	FIXTURE UNIT
FW	FLOOR WASTE
GCP	GAS CONTROL PANEL
GIT	GREASE INTERCEPTOR TRAP
GO	GRATED OUTLET
GSSB	GAS SLAM SHUT BUTTON
GTD	GRATED TRENCH DRAIN
HDPE	HIGH DENSITY POLYETHYLENE
HL	HIGH LEVEL
HP	HIGH POINT
HSW	HARVESTED STORMWATER
HT	HOSE TAP
HW	HOT WATER
HWCP	HOT WATER CIRCULATION PUMP(S)
HWF	HOT WATER FLOW
HWP	HOT WATER PLANT
HWR	HOT WATER RETURN
HWU	HOT WATER UNIT
IL	INVERT LEVEL
IO	INSPECTION OPENING
IOS	INSPECTION OPENING TO SURFACE
IV	ISOLATING VALVE
JU	JUMP UP
kPa	KILOPASCALS
kW	KILOWATTS
L	LITRES
LL	LOW LEVEL
LPS	LIFT PIT SUMP
L/S	LITRES PER SECOND
LT	LAUNDRY TUB
LU	LOADING UNIT
MJ/h	MEGA JOULES PER HOUR
m	METRES
M/H	METRES OF HEAD
m/s	METRES PER SECOND
mm	MILLIMETRES
ND	NON DRINKING
NDCW	NON DRINKING WATER
NP	NON POTABLE
OF	OVERFLOW
ORG	OVERFLOW RELIEF GULLY
OWS	OILWATER SEPARATOR
PCW	POTABLE COLD WATER
POO	PLANTER DRAIN OUTLET
PE	POLYETHYLENE
PEX	CROSS LINKED POLYETHYLENE
PFW	PLANT ROOM FLOOR WASTE
PPR	POLYPROPYLENE
PRV	PRESSURE REDUCTION VALVE
PVC	POLYVINYL CHLORIDE
PWD	PERSON WITH DISABILITIES
RCP	REINFORCED CONCRETE PIPE
RL	REDUCED LEVEL
RM	RISING MAIN
RPZD	REDUCED PRESSURE ZONE DEVICE
RWT	RAINWATER HARVESTING TANK
RWP	RAIN WATER PUMP(S)
RV	RELIEF VENT
SAC	SEWER ACCESS CHAMBER
SCVT	TESTABLE SINGLE CHECK VALVE
SD	SANITARY DRAINAGE
SDPS	SANITARY DRAINAGE PUMP STATION
SDRM	SANITARY DRAINAGE RISING MAIN
SHR	SHOWER
SK	SINK
SL	SURFACE LEVEL
S/S	STAINLESS STEEL
SSD	SUBSOIL DRAINAGE
SSHR	SAFETY SHOWER
SSL	STRUCTURAL SLAB LEVEL
ST	SANITARY STACK
SV	SLUICE VALVE
SW	STORMWATER
SWD	STORMWATER DROPPER
SWAC	STORMWATER ACCESS CHAMBER
SWGP	STORMWATER GULLY PIT
TA	TO ABOVE
TB	TO BELOW
TD	TUNDISH
TTD	TRAPPED TUNDISH
TMV	THERMOSTATIC MIXING VALVE
TPD	TRAP PRIMING DEVICE
TPRV	TEMPERATURE & PRESSURE RELIEF VALVE
TR	TROUGH
TV	TEMPERING VALVE
TW	TRADE WASTE
TWD	TRADE WASTE DROPPER
TWS	TRADE WASTE STACK
TWV	TRADE WASTE VENT
UR	URINAL
U/S	UNDERSIDE
U/G	UNDERGROUND
uPVC	UNPLASTISED POLYVINYL CHLORIDE
UTW	UNTRAPPED WASTE
VP	VENT PIPE
WC	WATER CLOSET
WM	WASHING MACHINE
WW	WARM WATER

INFORMATION REFLECTED ON THIS DRAWING REPRESENTS HYDRAULIC SERVICES DESIGN DEVELOPED FOR D&C TENDER ADVICE ONLY, AND SHOULD NOT BE REGARDED AS COMPLETE. THE D&C CONTRACTOR SHOULD REFER TO ALL ASSOCIATED ARCHITECTURAL AND OTHER DISCIPLINE DRAWINGS, PROJECT BRIEFS AND CLIENT REQUIREMENTS AND MAKE ADEQUATE ALLOWANCES FOR ALL NECESSARY HYDRAULIC SERVICES WORKS TO MEET THESE REQUIREMENTS, EQUIPMENT SCHEDULES AND COMPLIANCE WITH THE NCC & APPROPRIATE AUSTRALIAN STANDARDS

GENERAL NOTES

SERVICES IN GENERAL

1. CONCEALED WORK
ENCLOSED WORK SHALL NOT BE COVERED OR CONCEALED FROM VIEW UNTIL IT HAS BEEN TESTED AND INSPECTED BY THE RESPECTIVE AUTHORITIES INSPECTORS AND HAS BEEN APPROVED FOR CONCEALMENT BY THE SUPERINTENDENT.

NO WATER SERVICE PIPEWORK SHALL BE CONCEALED IN CONCRETE SLABS WITHOUT ADEQUATE PROVISION FOR MOVEMENT.

2. EXISTING SERVICES
EXISTING SERVICES SHOWN ON THE DRAWINGS ARE INDICATIVE ONLY AND MAY NOT BE COMPLETE. LOCATE AND CONFIRM ALL EXISTING SERVICES RELEVANT TO THE WORKS, PRIOR TO CARRYING OUT ANY WORK.

PRIOR TO COMMENCING ANY EXCAVATION WORK, CONTACT 'DIAL BEFORE YOU DIG', TO OBTAIN ALL AVAILABLE INFORMATION ON EXISTING AUTHORITIES SERVICES AND MAKE EVERY EFFORT TO AVOID DISTURBING THESE SERVICES.

EXISTING SERVICES SHOWN ON THE DRAWINGS ARE INDICATIVE ONLY AND MAY NOT BE COMPLETE

3. CIVIL SERVICES
CIVIL SERVICES SHOWN ARE INDICATIVE ONLY. ALL CIVIL SERVICES TO BE CONFIRMED WITH CIVIL ENGINEER AND ASSOCIATED DOCUMENTATION

SITE HAS BEEN CLASSIFIED WITH A GEOTECHNICAL SOIL REACTIVITY OF CLASS H1 AND UP TO 60mm OF MOVEMENT CAN BE EXPECTED. REFER GEOTECHNICAL INVESTIGATION REPORT BY CONSTRUCTION SCIENCES (REF: 21288.P.1108) DATED: 18, MARCH 2020

4. CO-ORDINATION WITH OTHER SERVICES
CO-ORDINATE AND CHECK FINAL LOCATIONS AND PROVISIONS WITH ALL OTHER SERVICES CONTRACTORS PRIOR TO INSTALLATION. THIS INCLUDES BUT IS NOT LIMITED TO; TUNDISH LOCATIONS, ACCESS PANELS, MECHANICAL WATER PROVISIONS, IRRIGATION WATER PROVISIONS, LANDSCAPE DRAINAGE REQUIREMENTS.

5. WORK IN EXISTING STRUCTURE
ALL PIPEWORK AND ASSOCIATED VALVES AND EQUIPMENT TO BE INSTALLED IN EXISTING BUILDINGS OR PENETRATING THROUGH EXISTING STRUCTURE IS TO BE APPROVED BY THE SUPERINTENDENT PRIOR TO COMMENCEMENT OF WORKS. ALL NEW CORE HOLES SHALL BE APPROVED BY A QUALIFIED STRUCTURAL ENGINEER PRIOR TO COMMENCEMENT

6. PIPEWORK AND FITTINGS
ALLOW FOR ALL NECESSARY CHANGES IN PIPE RUNS TO SUIT THE FINAL LAYOUT OF FIXTURES AND THE LIKE. PIPEWORK SHALL BE HIDDEN FROM VIEW BY INSTALLATION IN WALLS, CEILINGS OR BURYING IN GROUND. WHERE PIPEWORK CANNOT BE HIDDEN FROM VIEW, OBTAIN THE APPROVAL OF THE SUPERINTENDENT PRIOR TO INSTALLATION. ALL INTERNAL EXPOSED PIPEWORK INCLUDING TAPS SHALL BE CHROME PLATED. PROVIDE CHROME PLATED COVER PLATES WHERE PIPES PASS THROUGH WALLS. MAKE ALLOWANCES FOR EXPANSION AND CONTRACTION IN PIPEWORK AS REQUIRED. CONCEALED COMPRESSION FITTINGS ARE NOT PERMITTED.

7. CAST IN PIPEWORK
ALL CAST IN PVC PIPEWORK SHALL BE FULLY CONTAINED/WRAPPED IN MINIMUM 6mm THICK ABELFLEX OR EQUIVALENT TO ALLOW FOR THERMAL AND DIFFERENTIAL MOVEMENT

8. PIPEWORK PENETRATIONS
ALL PLUMBING AND DRAINAGE PENETRATIONS WITHIN OR UNDER THE BUILDINGS ARE TO HAVE AN APPROVED SLEEVE OR OPENING TO KEEP THE STRUCTURE A MINIMUM 6mm CLEAR OF PIPEWORK AND SEALED WITH AN APPROVED FLEXIBLE WATERPROOF SEALANT.

ALL SERVICES PASSING THROUGH A FIRE RATED STRUCTURE SHALL HAVE FIRE COLLARS (OR OTHER APPROVED FIRE PROTECTION METHOD) RATED TO THE MINIMUM FRL OF THE STRUCTURE IT IS PENETRATING.

9. PIPEWORK CHASED IN WALLS
WHERE PIPEWORK IS TO BE CHASED IN WALLS, CUT ALL CHASES WITH A MECHANICAL SAW. DO NOT CHASE STRUCTURAL MEMBERS UNLESS PRIOR APPROVAL IN WRITING IS OBTAINED FROM THE SUPERINTENDENT. PIPEWORK CHASED IN WALLS IS TO BE LAGGED WITH KEMILAG OR OTHER EQUIVALENT MATERIAL.

10. IDENTIFICATION OF PIPEWORK
EXPOSED PIPEWORK SHALL BE PAINTED AND LABELED WITH PIPE MARKERS IN ACCORDANCE WITH AS 1345. PIPEWORK IN GROUND SHALL BE PROVIDED WITH MARKING TAPE IN THE TRENCH INDICATING THE SERVICE AND DIRECTION OF FLOW IN ACCORDANCE WITH AS 2648.

11. TESTING
TEST ALL SYSTEMS AS REQUIRED BY THE LOCAL AUTHORITIES AND RELEVANT AUSTRALIAN STANDARDS.

SANITARY DRAINAGE

1. STANDARDS
THE INSTALLATION IS TO BE IN ACCORDANCE WITH AS/NZS 3500.2 AND LOCAL AUTHORITY REQUIREMENTS, UNLESS THIS SPECIFICATION NOMINATES OTHERWISE AND EXCEEDS THE MINIMUM STANDARD REQUIREMENT

2. PIPE SIZING
ALL DRAINAGE SHALL BE 100mm UNLESS NOTED OTHERWISE.

3. PIPE GRADES
100mm PIPEWORK SHALL BE LAID AT 1:100 GRADE MINIMUM UNLESS NOTED OTHERWISE. 100mm PIPEWORK SHALL BE LAID AT 1:60 GRADE MINIMUM UNLESS NOTED OTHERWISE. 65mm, 50mm, 40mm LAID AT 1:40 GRADE UNLESS NOTED OTHERWISE. PIPEWORK MAY BE LAID AT STEEPER GRADES AS REQUIRED TO MEET COVER REQUIREMENTS OR AS NOMINATED BY PIPEWORK INVERT LEVELS.

4. CONNECTION TO EXISTING DRAINAGE
CONFIRM LEVELS OF EXISTING DRAINAGE CONNECTIONS PRIOR TO COMMENCING WORK.

5. FLOOR WASTES
SHALL INCORPORATE PUDDLE FLANGES.

VINYL FLOOR WASTES (VFW) - SHALL BE PROVIDED WITH A DRESS FLANGE TO ENABLE THE VINYL TO TURN DOWN INTO THE FLOOR WASTE OUTLET.

KITCHEN FLOOR WASTES (KFW) - SHALL INCORPORATE A VERTICAL DEEP BODY WITH 200mm x 200mm POLISHED NICKEL BRONZE HINGED GRATE WITH STRAINER BUCKET AND SECONDARY STRAINER.

PLANTROOM FLOOR WASTES (PFW) - SHALL BE 200mm DIAMETER CAST IRON GRATE AND CAST IRON BODY WITH 100mm OUTLET AND TRAP. ALL PLANT ROOM FLOOR WASTES TO HAVE GRATE SEAL FLAP VALVES FITTED TO PREVENT TRAP ODOUR

ALL FLOOR WASTE GULLY TRAPS SHALL BE 100 (RISER) x 65 (OUTLET) TRAP BOTTOMS UNLESS NOTED OTHERWISE WITHIN THE SCHEMATIC/LAYOUT DRAWINGS.

6. INSPECTION OPENING TO SURFACE (IOS) AND INSPECTION OPENINGS (IO)
THE INSTALLATION IS TO BE IN ACCORDANCE WITH AS/NZS 3500.2, AND LOCAL AUTHORITY REQUIREMENTS.

WHERE AN IOS TERMINATES IN A VEHICULAR TRAFFICABLE PAVEMENT THE IOS IS TO BE BRASS OR CAST IRON.

WHERE AN IOS TERMINATES INSIDE A BUILDING THE IOS IS TO BE CHROME PLATED BRASS.

7. TESTING
TEST ALL SYSTEMS AS REQUIRED BY THE LOCAL AUTHORITIES AND RELEVANT AUSTRALIAN STANDARDS.

8. DEPTH OF SERVICES
CLEAR COVER OVER PIPEWORK TO BE IN ACCORDANCE WITH THE RELEVANT AUSTRALIAN STANDARD RELATING TO THE SERVICE.

SANITARY PLUMBING

1. STANDARDS
THE INSTALLATION IS TO BE IN ACCORDANCE WITH AS/NZS 3500.2 & LOCAL AUTHORITY REQUIREMENTS, UNLESS THIS SPECIFICATION NOMINATES OTHERWISE AND EXCEEDS THE MINIMUM STANDARD REQUIREMENT

2. PIPE SIZING
REFER "SANITARY DRAINAGE" SECTION

3. PIPE GRADES
REFER "SANITARY DRAINAGE" SECTION

4. ACOUSTIC TREATMENT
WRAP ALL PIPEWORK ABOVE HABITABLE AREAS WITH 'SOUNDLAG 4525C' ACOUSTIC INSULATION MANUFACTURED BY PYROTEK. INSULATION IS TO BE INSTALLED TO MANUFACTURER'S REQUIREMENTS.

5. FLOOR WASTES
REFER "SANITARY DRAINAGE" SECTION

6. INSPECTION OPENING TO SURFACE (IOS) AND INSPECTION OPENINGS (IO)
REFER "SANITARY DRAINAGE" SECTION

TRADE WASTE DRAINAGE

1. STANDARDS
THE INSTALLATION IS TO BE IN ACCORDANCE WITH AS/NZS 3500.2, LOCAL AUTHORITY TRADE WASTE REQUIREMENTS, AND STANDARD PLUMBING AND DRAINAGE REGULATION 2003UNLESS THIS SPECIFICATION NOMINATES OTHERWISE AND EXCEEDS THE MINIMUM STANDARD REQUIREMENT

2. PIPE SIZING
ALL DRAINAGE SHALL BE DN110 UNLESS NOTED OTHERWISE.

3. PIPE GRADES
DN110 PIPEWORK SHALL BE LAID AT 1:60 GRADE MINIMUM UNLESS NOTED OTHERWISE. DN63, DN50, DN40 LAID AT 1:40 GRADE UNLESS NOTED OTHERWISE. PIPEWORK MAY BE LAID AT STEEPER GRADES AS REQUIRED TO MEET COVER REQUIREMENTS OR AS NOMINATED BY PIPEWORK INVERT LEVELS.

4. TRADE WASTE PRETREATMENT DEVICES(S)
PRE TREATMENT DEVICE TO BE INSTALLED IN ACCORDANCE WITH LOCAL AUTHORITY TRADE WASTE LEGISLATION, AND STANDARD PLUMBING AND DRAINAGE REGULATION 2003.

5. INSPECTION OPENING TO SURFACE (IOS) AND INSPECTION OPENINGS (IO)
REFER "SANITARY DRAINAGE" SECTION

6. TESTING
TEST ALL SYSTEMS AS REQUIRED BY THE LOCAL AUTHORITIES AND RELEVANT AUSTRALIAN STANDARDS.

STORMWATER DRAINAGE

1. STANDARDS
THE INSTALLATION IS TO BE IN ACCORDANCE WITH AS/NZS 3500.3 & LOCAL AUTHORITY REQUIREMENTS, UNLESS THIS SPECIFICATION NOMINATES OTHERWISE AND EXCEEDS THE MINIMUM STANDARD REQUIREMENT

2. PIPE GRADES
100mm - 150mm SHALL BE LAID AT 1:100 MINIMUM GRADE UNLESS NOTED OTHERWISE.
225mm SHALL BE LAID AT 1:200 MINIMUM GRADE UNLESS NOTED OTHERWISE.
300mm SHALL BE LAID AT 1:250 MINIMUM GRADE UNLESS NOTED OTHERWISE.
>375mm SHALL BE LAID AT 1:300 MINIMUM GRADE UNLESS NOTED OTHERWISE.

PIPEWORK MAY BE LAID AT STEEPER GRADES AS REQUIRED TO MEET COVER REQUIREMENTS OR AS NOMINATED BY PIPEWORK INVERT LEVELS.

3. STORMWATER GULLY PITS (SWGP)
STORMWATER PITS AS SPECIFIED IN THE DRAWINGS SHALL BE INSTALLED IN ACCORDANCE WITH AS/NZS3500.3 AND MANUFACTURERS INSTRUCTIONS.

UNLESS NOTED OTHERWISE ALL GRATES TO BE CLASS A STAINLESS STEEL HEEL GUARD TYPE

4. ACOUSTIC TREATMENT
WRAP ALL PIPEWORK ABOVE HABITABLE AREAS WITH 'SOUNDLAG 4525C' ACOUSTIC INSULATION MANUFACTURED BY PYROTEK. INSULATION IS TO BE INSTALLED TO MANUFACTURER'S RECOMMENDATIONS.

5. CLEAROUTS
TO BE INSTALLED IN ACCORDANCE WITH AS/NZS 3500.3, AND LOCAL AUTHORITY REQUIREMENTS.

6. LONGITUDINAL TRENCH GRATES
SHALL BE AS NOMINATED AND WITH GRATES AS NOMINATED ON THE DRAWINGS.

7. SUBSOIL DRAINAGE
SHALL BE 110mm HOPE SLOTTED CORRUGATED PIPE WITH RTA FILTER SOCK. SURROUNDED WITH 10mm DIAMETER DRAINAGE GRAVEL WITH GEOTEXTILE FABRIC & 75mm OF BEDDING SAND UNDER PIPEWORK.

COLD WATER SERVICE

1. VALVE REQUIREMENTS
REFER TO SCHEMATICS FOR FULL EXTENT OF VALVE REQUIREMENTS

2. STANDARDS
THE INSTALLATION IS TO BE IN ACCORDANCE WITH AS/NZS3500.1, AND LOCAL AUTHORITY REQUIREMENTS, UNLESS THIS SPECIFICATION NOMINATES OTHERWISE AND EXCEEDS THE MINIMUM STANDARD REQUIREMENT

3. PIPE SIZING
PIPE SIZES NOMINATED ON THE DRAWINGS ARE FOR COPPER. EQUIVALENT PIPE SIZES SHALL BE USED IF AN ALTERNATIVE MATERIAL IS INSTALLED.

4. BACKFLOW PREVENTION DEVICES
INSTALL BACKFLOW PREVENTION DEVICES AS REQUIRED BY AS/NZS3500 AND AS NOMINATED ON THE DRAWINGS.

5. PRESSURE REDUCTION
INSTALL PRESSURE REDUCTION VALVE TO LIMIT PRESSURE IN ALL INTERNAL FIXTURES TO MAXIMUM 500KPA WHERE REQUIRED. PRESSURE SHALL BE LIMITED IN BOTH STATIC AND DYNAMIC STATES. OUTLET PRESSURES TO BE SET TO VALUES NOMINATED IN SCHEMATIC DRAWINGS

HOT WATER SERVICE

1. VALVE REQUIREMENTS
REFER TO SCHEMATICS FOR FULL EXTENT OF VALVE REQUIREMENTS

2. STANDARDS
THE INSTALLATION IS TO BE IN ACCORDANCE WITH AS/NZS3500.4, AND LOCAL AUTHORITY REQUIREMENTS, UNLESS THIS SPECIFICATION NOMINATES OTHERWISE AND EXCEEDS THE MINIMUM STANDARD REQUIREMENT

3. PIPE SIZING
PIPE SIZES NOMINATED ON THE DRAWINGS ARE FOR COPPER. EQUIVALENT PIPE SIZES SHALL BE USED IF AN ALTERNATIVE MATERIAL IS INSTALLED.

4. INSULATION
PIPEWORK IS TO BE INSTALLED WITH 25mm 'THERMOTEC' 4-ZERO INSULATION WHERE LOCATED IN CEILINGS AND VOIDS AND FOR ALL HOT WATER CIRCULATION PIPEWORK.

5. PRESSURE REDUCTION
INSTALL PRESSURE REDUCTION VALVE TO LIMIT PRESSURE IN ALL INTERNAL FIXTURES TO MAXIMUM 500KPA WHERE REQUIRED. PRESSURE SHALL BE LIMITED IN BOTH STATIC AND DYNAMIC STATES. OUTLET PRESSURES TO BE SET TO VALUES NOMINATED IN SCHEMATIC DRAWINGS

IRRIGATION SERVICE

1. STANDARDS
THE INSTALLATION IS TO BE IN ACCORDANCE WITH AS/NZS3500.1, AND LOCAL AUTHORITY REQUIREMENTS, UNLESS THIS SPECIFICATION NOMINATES OTHERWISE AND EXCEEDS THE MINIMUM STANDARD REQUIREMENT

2. PIPEWORK SIZING
PIPE SIZES NOMINATED ON THE DRAWINGS ARE FOR COPPER. EQUIVALENT PIPE SIZES SHALL BE USED IF AN ALTERNATIVE MATERIAL IS INSTALLED.

3. BACKFLOW PREVENTION DEVICES
INSTALL BACKFLOW PREVENTION DEVICES AS REQUIRED BY AS/NZS 3500.1 AT THE INDIVIDUAL TAKE-OFF POINTS FOR IRRIGATION SUPPLY.

CONSUMER GAS SERVICE

1. VALVE REQUIREMENTS
REFER TO SCHEMATICS FOR FULL EXTENT OF VALVE REQUIREMENTS

2. STANDARDS
THE INSTALLATION IS TO BE IN ACCORDANCE WITH AS5601.1 THE BUILDING CODE OF AUSTRALIA AND LOCAL AUTHORITY REQUIREMENTS, UNLESS THIS SPECIFICATION NOMINATES OTHERWISE AND EXCEEDS THE MINIMUM STANDARD REQUIREMENT

3. PROVISION FOR EXPANSION/MOVEMENT
ALL PIPEWORK SHALL BE INSTALLED SO AS TO ALLOW EXPANSION/CONTRACTION IN ACCORDANCE WITH AS5601.1.

DRAINAGE PIPEWORK SYSTEMS

NEW	EXISTING	ABBREV.	PIPE SYSTEM TYPE
		HSW	HARVESTED STORMWATER
		SD	SANITARY DRAINAGE
		SDPO	SANITARY DRAINAGE PUMP OUT
		SW	STORMWATER DRAINAGE
		TW	TRADE WASTE
		TWPO	TRADE WASTE PUMP OUT
		VP	VENT PIPE
		CVP	VENT PIPE - CHAMBER
		GTV	VENT PIPE - GREASE TRAP
		RV	VENT PIPE - RELIEF
		TWV	VENT PIPE - TRADE WASTE

WATER & GAS PIPEWORK SYSTEMS

NEW (>Ø40)	EXISTING (>Ø40)	NEW (<Ø40)	EXISTING (<Ø40)	ABBREV.	PIPE SYSTEM TYPE
				CCW	CIVIL WATER
				DHWF	DOMESTIC HOT WATER FLOW
				DHWR	DOMESTIC HOT WATER RETURN
				WW	DOMESTIC WARM WATER
				DCW	DRINKING COLD WATER
				GS	GAS
				NDCW	NON DRINKING COLD WATER
				RRW	RECYCLED RAINWATER

REV	DATE	BY	DESCRIPTION	CHK	APP
B	12.02.2026	SH	ISSUED FOR D&C TENDER	AA	SM
A	30.01.2026	SH	DRAFT 60% DD ISSUE FOR REVIEW	AA	SM

DRAWING STATUS: DESIGN DEVELOPMENT

900 Ann Street, Level 12, Fortitude Valley 4006
Tel: +61-7-3854-6200 Fax: +61-7-3854-6500
http://www.wsp.com

CLIENT: CQU

ARCHITECT: THOMSON ADSETT / PEDDLE THORP

PROJECT: CQU ROCKHAMPTON TAFE CONSOLIDATION

TITLE: HYDRAULIC SERVICES
GENERAL NOTES, LEGENDS & SYMBOLS

SCALE @ A0:	CHECKED:	APPROVED:
N.T.S	AA	SM
PROJECT NUMBER:	DRAWN:	DATE:
PS229518	SH	JAN 2026

DRAWING No: 00-HY-DR-010-A00-00-00 REV: B

© WSP Australia Pty Ltd

DRAWING CREATED IN REVIT