



EXISTING PORTION OF UNDERGROUND HV LINE LOCATED UNDER THE PROPOSED "NTB" FOOTPRINT TO BE RELOCATED
REFER NOTES 4 AND 5

EXISTING UNDERGROUND HIGH VOLTAGE LINE TO REMAIN

NEW BUILDING B92 MAIN SWITCHBOARD

EXISTING UNDERGROUND COMMS CABLE TO REMAIN.
EXPOSE EXISTING UNDERGROUND SERVICE PRIOR TO NEW FOOTINGS AND PROVIDE ADEQUATE PROTECTION DURING CONSTRUCTION WORKS

REFER NOTE 1

APPROXIMATE LOCATION OF PROPOSED NEW SUBMAIN ROUTE TO BUILDING B92. COORDINATE ON SITE

EXISTING UNDERGROUND SUBMAIN CABLE TO "SCHOOL OF MINING" BUILDING LOCATED VERY CLOSE OR UNDER NEW TRADES BUILDING FOOTPRINT. USE EXTREME CAUTION, EXPOSED UNDERGROUND CABLE AND PROVIDE ADEQUATE PROTECTION DURING WORKS.

EXISTING MSB-SS/EB TO REMAIN

EXISTING HV PIT JOIN AND EXTEND EXISTING NEW HV CABLE WITHIN PIT.

INSTALL NEW HV PIT AND HV CABLES AS SHOWN. FINAL HV ROUTE TO BE DETERMINED ON SITE. REFER NOTES 4 & 5

EXISTING TRANSFORMER TO REMAIN
REFER NOTE 3

EXISTING HV ROOM WITH RMU'S SUPPORTING BUILDING B84 TO REMAIN.
REFER NOTES 4 & 5

EXISTING TRANSFORMERS (3 OFF) SUPPORTING BUILDING B84 EQUIPMENT TO REMAIN UNCHANGED

INFORMATION REFLECTED ON THIS DRAWING REPRESENTS ELECTRICAL SERVICES DESIGN DEVELOPED FOR D&C TENDER ADVISE ONLY, AND SHOULD NOT BE REGARDED AS COMPLETE. THE D&C CONTRACTOR SHOULD REFER TO ALL ASSOCIATED ARCHITECTURAL AND OTHER DISCIPLINE DRAWINGS, PROJECT BRIEFS AND CLIENT REQUIREMENTS AND MAKE ADEQUATE ALLOWANCES FOR ALL NECESSARY ELECTRICAL SERVICES WORKS TO MEET THESE REQUIREMENTS, EQUIPMENT SCHEDULES AND COMPLIANCE WITH THE NCC & APPROPRIATE AUSTRALIAN STANDARDS

NOTES:

- EXISTING AREA WITH LOTS OF EXISTING UNDERGROUND SERVICES. EMPLOY THE SERVICES OF A CABLE LOCATOR TO ASCERTAIN EXACT LOCATION OF ALL EXISTING UNDERGROUND SERVICES WITHIN THE FOOT PRINT ON NEW TRADES BUILDING (B-92). PLOT SERVICES AND SEEK DIRECTION FROM CQU ON WHICH EXISTING SERVICES ARE TO REMAIN AND WHICH SERVICES CAN BE DISCONNECTED AND REMOVED. ONCE CQU HAVE DETERMINED ON WHICH SERVICES SHOULD BE RETAIN PROVIDE A PROPOSED APPROACH TO PROTECT EXISTING SERVICES TO REMAIN DURING CONSTRUCTION.
- NO VARIATION WILL BE ACCEPTED FOR UNCOORDINATED WORK. SHALL ANY EXISTING UNDERGROUND SERVICE BE ACCIDENTALLY CUT DURING CONSTRUCTION, THE CONTRACTOR SHALL RECTIFY THE WORKS AT THEIR OWN EXPENSES.
- EXISTING TRANSFORMER TO REMAIN UNCHANGED. LIAISE WITH CQU FOR PREFERRED TIMES TO SWITCH OFF AND OBTAIN WRITTEN APPROVAL.
- ALL HIGH VOLTAGE WORKS TO BE CONDUCTED BY AN HV LICENSED CONTRACTOR. LIAISE WITH CQU FOR PREFERRED TIMES TO SWITCH OFF HIGH VOLTAGE LINE AND OBTAIN WRITTEN APPROVAL.
- EXISTING HV ROOM WITH EXISTING RMU'S. OBTAIN COPIES OF EXISTING DRAWINGS FROM CQU ON EXISTING HV DISTRIBUTION AND BECOME FULLY CONVERSANT WITH THE EXISTING HV DISTRIBUTION SYSTEM PRIOR TO ANY WORKS. EXISTING RMU'S HAVE A CULVERT UNDER. ALLOW TO BORE UNDER EXISTING ROOM/S LAB TO ACCESS VAULT UNDER RMU'S FOR INSTALLATION OF NEW HV CABLES.
- UPON COMMISSIONING, PROVIDE COPIES OF CERTIFICATES/APPROVALS BY AN INDEPENDENT HV DESIGNER CONFIRMING THAT WORK CARRIED OUT IS IN FULL COMPLIANCE WITH STANDARDS PRIOR TO RE-ENERGISE THE HV LINE.

B	12.02.2026	MM	ISSUED FOR D&C TENDER	TP	SM
A	10.02.2026	CP	DRAWN BY D&C FOR REVIEW	TP	SM
REV	DATE	BY	DESCRIPTION	CHK	APP

DESIGN DEVELOPMENT



900 Ann Street, Level 12, Fortitude Valley 4006
Tel: +61-7-3854-6200 Fax: +61-7-3854-6500
<http://www.wsp.com>

CLIENT:

CQU

ARCHITECT:

THOMSON ADSETT / PEDDLE THORP

PROJECT:

CQU ROCKHAMPTON TAFE CONSOLIDATION

TITLE:

ELECTRICAL SERVICES

NEW TRADES BUILDING - SITE PLAN

SCALE @ A1

1:100

CHECKED:

TP

APPROVED:

SM

PROJECT NUMBER:

PS229518

DRAWN:

CP

DATE:

JAN 2026

DRAWING NO:

B92-EL-DR-300-A00-00-00

REV:

B

© WSP Australia Pty Ltd