NEW UNDERGROUND SUBMAIN CABLE IN CONDUIT FROM EXISTING MAIN SITE SWITCHBOARD SS/ENB. FINAL LOCATION OF CABLE ROUTE TO BE DETERMINED ON SITE.

MSSB-B92 CHILLER

CHILLER PLANT

INSTALL A 100mm DIAMETER HD PVC CONDUIT WITH 3 OFF DRAW-WIRES FOR FUTURE SUPPLIES. TERMINATED CONDUIT INTO A PIT.

APPROXIMATE LOCATION OF EXISTING UNDERGROUND NETWORK CABLE.

POSSIBLE LOCATION OF NEW COMMS PITS FOR NETWORK TO NEW TRADES BUILDING

FINAL LOCATIONS OF POWER AND COMMS TO LIFT TO BE DETERMINED ON SITE.

POSSIBLE LOCATION OF NEW COMMS PITS FOR NETWORK TO NEW TRADES BUILDING.

3000x4000 COMMS ROOM (CQU ICT GUIDELINES) PLEASE SWAP LOCATION WITH FURNITURE STORE.

NEW UNDERGROUND SUBMAIN CABLE IN CONDUIT FROM EXISTING MAIN SITE SWITCHBOARD SS/ENB. FINAL LOCATION OF CABLE ROUTE TO BE DETERMINED ON SITE.

POWER CABLE TO ISLAND BENCH INSTALLED IN THE CEILING SPACE OF FLOOR BELOW

NOTE 1 (TYPICAL TO ALL)

DB ON LEVEL ABOVE ELECTRICAL CABLES TO RISE HERE.

DB ON LEVEL ABOVE ELECTRICAL CABLES TO RISE HERE

SUPPLY AND INSTALL A 1200mm HIGH 150mm SHS FIXED TO FLOOR AND INSTALL OUTLETS AS SHOWN

ISOLATORS MOUNTED ON CABLE TRAY FOR POWER TO VEHICLE HOISTS. ALLOW TO SUPPLY AND INSTALL POWER BETWEEN ISOLATORS AND VEHICLE HOISTS VIA OVERHEAD UNISTRAT. COORDINATE ON SITE FINAL LOCATIONS. (TYPICAL TO ALL)

REFER TO SITE PLAN B92-EL-DR-300-A00-00-00 FOR REDIRECTION OF HV EXISTING CABLES

EACH GROUP OF LOUVRES HAVE A 24V DC MOTOR. ALLOW TO SUPPLY AND INSTALL A 24V DC/220V AC PER GROUP PLUGGED ONTO A SOCKET OUTLET, AND SOCKET OUTLET CONTROLLED VIA A LOCAL SWITCH FOR OPEN/CLOSE OF LOUVRES. COORDINATE ON FINAL LOCATION OF ALL EQUIPMENT

MOST OF EQUIPMENT TO WORKSHOPS, METAL FABRICATION AND AUTO-SHOP ARE EXISTING LOCATED AT THE CITY CAMPUS SITE. CONTRACTOR TO CONDUCT A FULL SURVEY OF EXISTING EQUIPMENT BEING RELOCATED AT CITY CAMPUS SITE AND ALLOW FOR ADEQUATE POWER SUPPLIES.

PROVIDE 3 PHASE OUTLET (TYPICAL TO ALL GMAW WELDING BAY)

PROVIDE 3 PHASE OUTLET (TYPICAL TO ALL MMAW + GTAW WELDING BAY)

PROVIDE 3 PHASE OUTLET, AND 2 DGPO'S (TYPICAL TO GRIND WELDING BAY)

INSTALL ISOLATORS PER MANUFACTURER'S INSTRUCTIONS. CONTRACTOR TO COORDINATE AND CONFIRM FINAL LOCATIONS AND ELECTRICAL RATINGS OF ALL EQUIPMENT SERVING THE ARC WELDING/METAL FABRICATION AREA. (TYPICAL TO ALL ISOLATORS)

EACH GROUP OF LOUVERS HAVE A 24V DC TO 220VAC AND A TRANSFORMER PLUGGED INTO A SOCKET OUTLETS AND OUTLET CONTROLLED VIA A LIGHT SWITCH. (TYPICAL TO ALL LOUVERS)

NOTES:

1. POWER AND COMMUNICATIONS CONDUITS TO RISE UP TO CEILING SPACE WITHIN WALL

INFORMATION REFLECTED ON THIS DRAWING REPRESENTS ELECTRICAL SERVICES DESIGN DEVELOPED FOR D&C TENDER ADVICE ONLY, AND SHOULD NOT BE REGARDED AS COMPLETE. THE D&C CONTRACTOR SHOULD REFER TO ALL ASSOCIATED ARCHITECTURAL AND OTHER DISCIPLINE DRAWINGS, PROJECT BRIEFS AND CLIENT REQUIREMENTS AND MAKE ADEQUATE ALLOWANCES FOR ALL NECESSARY ELECTRICAL SERVICES WORKS TO MEET THESE REQUIREMENTS, EQUIPMENT SCHEDULES AND COMPLIANCE WITH THE NCC & APPROPRIATE AUSTRALIAN STANDARDS

REV	DATE	BY	DESCRIPTION	CHK	APP
B	12.02.2026	MM	ISSUED FOR D&C TENDER	TP	SM
A	30.01.2026	MM	DRAFT 60% DD ISSUE FOR REVIEW	TP	SM

DRAWING STATUS: DESIGN DEVELOPMENT

wsp
900 Ann Street, Level 12, Fortitude Valley 4006
Tel: +61-7-3854-6200 Fax: +61-7-3854-6500
http://www.wsp.com

CLIENT: CQU

ARCHITECT: THOMSON ADSETT / PEDDLE THORP

PROJECT: CQU ROCKHAMPTON TAFE CONSOLIDATION

TITLE: ELECTRICAL SERVICES
NEW TRADES BUILDING - GROUND LEVEL - POWER AND COMMS LAYOUT

SCALE @ A0:	CHECKED:	APPROVED:
1:100	TP	SM
PROJECT NUMBER: PS229518	DRAWN: MM	DATE: JAN 2026

DRAWING No: B92-EL-DR-520-L00-00-00 REV: B

© WSP Australia Pty Ltd

DRAWING CREATED IN REVIT