General Notes:	
	Any alterations to the nominated product must be approved by the Superintendent. All samples are to be supplied to the Superintendent for approval prior to installation.*
	This Materials, Finishes & Furniture Schedule must be read in conjunction with the Landscape Drawings and Specification.
	Hold points to be observed in accordance with the Landscape Specification.
	The Superintendent must be notified of any discrepancies prior to ordering and installation of materials.*
	**Superintendent or the appointed Superintendent's Representative*

CODE	ITEM	PRODUCT DETAILS	FINISH/COLOUR	SUPPLIER (or approved equivalent)	SAMPLE / SHOP DRAWING / DATA SHEET REQUIREMENTS (Refer Specification for additional requirements)	OTHER NOTES
SURFACE TREATMENTS						
General Notes:	*All external paving must meet the Australian Standards AS/NZS 3661 coefficient for slip-resistance. Finished Surface shall comply with 'P4 Wet Pendulum' test classification and R12 minimum oil wet inclining test*					
	Luminance contrast testing of substrates against the specified nosings and TGSI's to be undertaken in wet and dry conditions prior to their installation to confirm compliance.					
PA1	**Pavement Type 1**	Insitu Coloured Concrete. Pedestrian Grade 125mm depth.	Finish: Light acid wash Colour: CCS Prairie Aggregate: Hanson 5-7mm Blue Healer	Concrete Pigment: CCS Concerete Colour Systems Aggregate: Hanson		
PA2	**Pavement Type 2**	Insitu Coloured Concrete. Pedestrian Grade 125mm depth.	Finish: Light acid wash Colour: CCS Paperbark Aggregate: Hanson 5-7mm Blue Healer	Concrete Pigment: CCS Concerete Colour Systems Aggregate: Hanson		
PA3	**Pavement Type 3**	Insitu Concrete. Pedestrian Grade 125mm depth.	Finish: Light acid wash Colour: Plain Grey / natural Aggregate: Hanson 5-7mm Blue Healer	Concrete Pigment: CCS Concrete Colour Systems Aggregate: Hanson		
STR	**Stairs - Cast In-situ**	Insitu Coloured Concrete.	Finish: Light acid wash Colour: Plain Grey / natural Aggregate: Hanson 5-7mm Blue Healer	Concrete Pigment: CCS Concrete Colour Systems Aggregate: Hanson		As per AS 1428 and associated amendments -See Plan and Details
TGSI	**Tactiles Type 1 - Warning**	Ground Surface Indicators Cautional - Charcoal 300x300x40mm Paver	As per AS/NZS 1428.1.2099 Colour: Charcoal	Boral Concrete Rockhampton07 4936 1133 36-40 Johnson Street Rockhampton, QLD, 4700	As per manufacturers installation specification.	As per AS 1428.4 and associated amendments -See Plan and Details
FENCING, EDGING AND WALLS						
W1	**Wall Type 1 - Custom Precast Seat Wall**	Plinth: Class 2 Precast Concrete Formed - Shop drawings Required Seat: 5m Mild Steel Custom Backed Bench with Arm Rest, fixed to Custom Mild Steel Bench - Shop Drawings Req	Plinth: Class 2 Finish, 20mm Chamfer to all exposed edges Backing & Arm Rest: Powdercoated Mild Steel Bench: Powdercoated Mild Steel Frame: 3mm Powdercoated SHS Plinth: Natural, anti grafitti coating Backing & Arm Rest: Powdercoat: Dulux Powdercoat Duralloy Wedgewood Satin 27250279 Bench: Powdercoat: Dulux Powdercoat Duralloy White Satin 2601139S RC Fame: Powdercoat: Dulux Powdercoat Duralloy White Satin 2601139S RC	Custom Seat Design - Shop Drawings Required for approval	Backed Bench and Armrest: 10mm 316 SS Countersunk Socket Head Cap Screw and Anchor	Perforations as per Detail
W2	**Wall Type 2 - Blockwork Retaining Wall**	Blockwork: 200 series, core filled, designer blockwork wall - Split Face Austral GB Sandstone Brick Split Face Concrete Capping: 50mm thick, 20mm Chamfer to exposed edges	Height varies (max. 900mm high) - Refer detail Concrete: Smooth Finish Blockwork: Austral Sandstone to match Architectural Spec. Concrete: Sandstone, Natural	Approved Local Supplier	Brick Ties	Refer Plan and Details
E1	**Edge Type 1 - Concrete Edge**	Concrete Formed Edge Size: 100 x 100mm. Refer detail and specification	Finish: Trowelled Finish Colour: Natural Grey cement	Approved supplier	Minimum Tool jointing at 4m centres, Joints at junctions and transitions	Refer Plan and Details
HR	**Handrail**	316 SS Tubular Steel Handrail, Surface Mounted - Refer Detail	Finish: Brushed Colour: Natural	Approved Local Supplier	Surface Mounted- refer detail	Refer to Plan and Details
RB	**Root Barrier**	Product Code: Global Synthetics Root Barrier Material: HDPE Size: 900 mm depth	Colour: Black	Global Synthetics (07) 3865 7000 44 Telford St, Virginia, QLD 4014	N/A	Not in plans. Assumed required for tree planting adjacent to Wall Type 2.
FURNITURE						
BI1 & BI2	**Rubbish Bin Enclosure Combined - General Waste (BI1) & Recycling (BI2)**	Street & Garden Bin Enclousure Product: Flight FLT5 2-2 Size: 1520x1420x844mm Capacity: 240L	Body Powdercoated Duralloy Colour - White 2601139S RC General Waste Feature Panel Colour - Red as standard Recycling Feature Panel Colour - Yellow as standard	Street and Garden Furniture (07) 3844 1951 Unit 1, 11 Donkin Street, West End, Brisbane QLD 4101	As per manufacturer's installation specification	Not in plans. Assumed required for costing 1x BI1 and 1x BI2. Location TBC.
BO1	**Bollard Type 1 - Fixed**	Street & Garden Product: FLT6-F Size: 1000x180mm	Body Powdercoated Duralloy Colour - White Satin 2601139S RC	Street and Garden Furniture (07) 3844 1951 Unit 1, 11 Donkin Street, West End, Brisbane QLD 4101	As per manufacturer's installation specification	Not in plans. Assumed required for costing 10x BO1. Location TBC.
BO2	**Bollard Type 2 - Removable**	Street & Garden Product: FLT6-R Size: 1000x180mm	Body Powdercoated Duralloy Colour - White Satin 2601139S RC	Street and Garden Furniture (07) 3844 1951 Unit 1, 11 Donkin Street, West End, Brisbane QLD 4101	As per manufacturer's installation specification	Not in plans. Assumed required for costing 2x BO2. Location TBC.
BR	**Bike Rack**	Street & Garden Product: Flight LLT7 Size: 900mm x 900mm	Body Powdercoated Duralloy Colour - White Satin 2601139S RC	Street and Garden Furniture (07) 3844 1951 Unit 1, 11 Donkin Street, West End, Brisbane QLD 4101	As per manufacturer's installation specification	Not in plans. Assumed required for costing 3x BR. Location TBC.
DF	**Drinking Fountain**	Street & Garden Drinking Fountain Product: Flight FLT8 Size: 840x150x206mm	Body Powdercoated Duralloy Colour - White 2601139S RC	Street and Garden Furniture (07) 3844 1951 Unit 1, 11 Donkin Street, West End, Brisbane QLD 4101	As per manufacturer's installation specification Connect to potable water Connect discahrge to SW	Not in plans. Assumed required for costing 1x DF. Include 1x1m concrete pad. Location TBC.
SN	**Stair Nosing**	Product: Latham SB Series Bevelled Code: 765SB Suregrip Colour Strip: Sparkling Black LRV 28.9	As per manufacturer	Latham 02 98979 7888 14 Tennyson Road, Gladesville New South Wales, 2111	As per manufacturer's installation specification.	Assume nosing to all stairs.
SOFTWORKS						
TU1	**Turf Type 1**	Couch Grass (Cynodon dactylon) laid over 100mm of imported organic topsoil	N/A	Approved Local Supplier	N/A	Refer Plan and Details
GB1	**Garden Bed Type 1**	Planting on natural ground Topsoil: Refer Details and Specification for type/depth	Mulch: Hoop Pine Mulch Refer Details and Specification for depth	Approved Local Supplier	N/A	Refer Plan, Details and Planting Schedule
	New Tree Planting	Soil: Refer details and specification Amelioration: In accordance with the specification and laboratory test results Staking: 1800mm HWD stakes with hessian ties.	Mulch: Hoop Pine Mulch Refer Details and Specification for depth	Approved Local Supplier	N/A	Allow 1m diametre mulch ring to all trees in turf.

GENERAL NOTES

1. DO NOT SCALE DRAWINGS. FIGURED DIMENSIONS HAVE PREFERENCE OVER SCALED DIMENSIONS.
2. ANY DISCREPANCIES MUST BE REPORTED IMMEDIATELY TO THE SUPERINTENDENT.
3. THESE DRAWINGS ARE TO BE READ IN CONJUNCTION WITH THE DETAILS, SPECIFICATIONS AND ENGINEERING DOCUMENTS.
4. LOCATE AND PROTECT ALL UNDERGROUND SERVICES PRIOR TO ANY EXCAVATION. MAKE GOOD ALL DAMAGE TO EXISTING WORKS CAUSED BY THE ACTIVITY OF THESE WORKS.
5. THESE DRAWINGS ARE TO BE PRINTED IN COLOUR.

These designs, plans and specifications and the copyright therein are the property of TRACT CONSULTANTS PTY. LTD. and must not be used, reproduced or copied, wholly or in part, without the written permission of TRACT CONSULTANTS PTY. LTD.

60% DD
NOT FOR CONSTRUCTION

REV	DESCRIPTION	DATE	DRWN	CHKD
1	Revision 1	Date 1	STa	BM
2	Draft Issue	30/01/2026	STa	BM
3	60% DD	11/02/2026	STa	BM

Tract
Landscape Architects
Urban Designers
Town Planners

Melbourne P: 03 9429 6133
Brisbane P: 07 3002 6400
Sydney P: 02 9954 3733
Geelong P: 03 5221 0105
Adelaide P: 08 8223 1324
www.tract.com.au

PROJECT
CENTRAL QUEENSLAND UNIVERSITY (CQU) ROCKHAMPTON NORTH CAMPUS

CLIENT
CENTRAL QUEENSLAND UNIVERSITY (CQU)

DRAWING TITLE
MATERIALS, FINISHES & FURNITURE SCHEDULE

DRAWING NUMBER	REVISION
725-0085-L-00-DR102	3

DRAWN	CHECKED	APPROVED	DATE
STa	BM	BM	11/02/2026

SCALE
A1