

1. ALL ARCHITECTURAL DRAWINGS TO BE READ IN CONJUNCTION WITH OTHER DISCIPLINES.
2. REFER TO F&E, SANITARYWARE SCHEDULES FOR ALL FURNITURE, FIXTURES, AND EQUIPMENT.
3. REFER TO HYDRAULIC ENGINEER'S DRAWINGS FOR HYDRAULIC SERVICES. FINISH OF VALVE/BOX COVERS TO MATCH ADJACENT WALL/JOINTERY FINISH.
4. REFER TO ELECTRICAL DOCUMENTATION FOR OUTLET DETAILS (ie. POWER, DATA, COMMS etc.)
5. REFER TO AUDIO VISUAL DOCUMENTATION (VideoPro) FOR AV REQUIREMENTS AND DETAILS.
6. AV SUPPLIER TO CONFIRM EXACT POSITIONS OF EQUIPMENT ON SITE
7. ALL F&E ITEMS ARE TO BE READ IN CONJUNCTION WITH FF&E SCHEDULES AND CQU DESIGN MANUAL.
8. ALL F&E AND TRANSFER ITEMS TO BE REVIEWED AND CONFIRMED WITH CLIENT PRIOR TO COMMENCING ON SITE
9. PROVIDE ALLOWANCE AND ADD SUPPORT TO WALLS, WHERE FITTINGS ARE WALL MOUNTED. THIS INCLUDES BUT NOT LIMITED TO HANDBASINS, HANDRAILS, SCREENS, PROJECTORS, etc.
10. FF&E COUNT IS FOR INFORMATION ONLY. THE TOTAL NUMBER OF FF&E ITEMS ARE TO BE CONFIRMED WITH CLIENT AND ARCHITECTS BEFORE PURCHASE OF ITEMS.
11. CONFIRM ALL DIMENSIONS ON SITE FOR JOINTERY ITEMS.
12. ALL SANITARY FIXINGS & FIXTURES IN PWD TOILETS TO BE INSTALLED IN ACCORDANCE WITH AS1428.1
13. ALLOW FOR FIRE EXTINGUISHERS & FIRE BLANKETS AS PER AS2444.2001
14. POWER AND DATA POINTS SHOWN ON THE ROOM LAYOUT SHEETS WERE SHOWN AND DISCUSSED DURING USER GROUP BRIEFING. THESE RELATE TO PARTICULAR EQUIPMENT THAT WAS DISCUSSED AS REQUIRING POWER AND DATA. THESE REFLECT STAKEHOLDER EXPECTATIONS FOR SPECIFIC POWER AND DATA POINTS AND HAVE REMAINED IN THE DOCUMENTATION AS A USEFUL REFERENCE FOR THE CONTRACTOR. THESE ARE NOT A COMPLETE QUANTITY AND SPECIFICATION OF POWER AND DATA. THE CONTRACTOR IS TO REFER TO ELECTRICAL ENGINEER'S DOCUMENTATION FOR ALLOWANCE. REFER TO ELECTRICAL DOCUMENTATION FOR AMPS AND 3 PHASE POWER REQUIREMENTS. REFER TO AUDIO VISUAL (VIDEOPRO) DOCUMENTATION FOR ADDITIONAL POWER AND DATA REQUIREMENTS
15. ALLOW FOR STRUCTURAL PLY BACKING BEHIND PLASTERBOARD FOR FULL EXTENT OF WALLS WITH MOUNTED AUDIO VISUAL EQUIPMENT. REFER TO AUDIO VISUAL (VIDEOPRO) DOCUMENTATION FOR LOCATIONS OF WALL MOUNTED EQUIPMENT.
16. ALLOW FOR PRIVACY FILM TO ALL INTERNAL GLAZING (DOORS AND WINDOWS) TO OFFICES AND MEETING ROOMS. CONFIRM SET OUT PRIOR TO INSTALLATION
17. ALLOW FOR DOUBLE BLOCK OUT BLINDS TO ALL WINDOWS UNLESS NOTED OTHERWISE
18. ALL INTERNAL DOORS ARE TO BE SOLID CORE DOORS WITHIN ALUMINIUM FRAMED SUITES UNLESS NOTED OTHERWISE.
19. FLOOR BOXES MUST BE COORDINATED WITH BOTH THE STRUCTURAL AND ELECTRICAL ENGINEERS. BEFORE ANY CUTTING OF THE EXISTING SLAB OCCURS, CONFIRM THE EXACT LOCATIONS AND REQUIREMENTS WITH THE STRUCTURAL ENGINEER.
20. HEARING AUGMENTATION TO AUSTRALIAN STANDARDS – REFER VIDEOPRO AND ELECTRICAL SPECIFICATION

GROUP 1 ITEMS
(PROVIDED & FITTED UNDER CONTRACT)

GROUP 2 ITEMS
(PROVIDED BY CLIENT & FITTED UNDER CONTRACT)

GROUP 2T ITEMS - EXISTING EQUIPMENT
(PROVIDED BY CLIENT & FITTED UNDER CONTRACT)

GROUP 3 ITEMS
(PROVIDED & INSTALLED BY CLIENT)

PLANS TO BE PRINTED IN COLOUR

SCH_Code FF&E TAG

J0.PROC JOINERY TAG

SETOUT MARKER

DENOTES TILE SETOUT POINT.
NB: WALL TILES ALIGN WITH FLOOR TILES.

NOTE: ALL SANITARY FITTINGS AND FIXTURES TO BE INSTALLED IN ACCORDANCE WITH AUSTRALIAN STANDARD AS1428.1

NOTE: REFER TO SCHEDULES FOR ALL SANITARY FITTINGS AND FIXTURES.

	SINGLE POWER OUTLET		LIGHT SWITCH
	DOUBLE POWER OUTLET		TV
	SINGLE DATA		FLOOR BOX (FB)
	DOUBLE DATA		

REFER TO ELECTRICAL ENGINEER'S DRAWINGS FOR DETAILS

60-LEGEND JOINERY - MALE TOILET	
FFE_Mark	Comments
J.33.20	Vanity Counter

60-LEGEND JOINERY - FEMALE TOILET	
FFE_Mark	Comments
J.33.29	Vanity Counter

40-LEGEND FFE - PWD 2.18			
Code	Description	Group	Count
AR38L	Mirror - Framed	1	1
BN15B	Accessible Basin	1	1
GR1	Horizontal Grabrail	1	1
TP1	Mixer - Sink Accessible	1	1
WC2A	Toilet - Accessible PWD With Grab Rails	1	1
BI10A	Bin - Sanitary Waste	2	1
DS12A	Dispenser - Soap	2	1
DS22A	Dispenser - Toilet Tissue Roll Drop	2	1
DS34A	Dispenser - Paper Hand Towel	2	1

