



PROPOSED LOCATION
OF NEW MAIN
SWITCHBOARD MSB-33

NEW SITE SWITCHBOARD MSB CHILLER PLANT
SWITCHBOARD TO BE OUTDOOR RATED AND MOUNTED ON A 150mm HIGH
CONCRETE PLINTH
SWITCHBOARD TO BE 2000A AND FITTED WITH THE FOLLOWING BREAKERS:
1x630A = BUILDING 32 LIGHT AND POWER
1x630A = BUILDING 32 AIR CONDITIONING
1x400A = BUILDING 34 AIR CONDITIONING
1x630A = NEW CHILLER 2
1x400A = BUILDING 33 LIGHT AND POWER
1x315A = BUILDING 34 LIGHT AND POWER
1x400A = BUILDING 87 (DATA SERVER)
1x400A = BUILDING 31
1x630A SPARE SPACE
2x400A SPARE SPACE
3x250A SPARE SPACE
REFER TO LINE DIAGRAM FOR FURTHER DETAILS

EXISTING MAIN SWITCHBOARD
WITHIN TRANSFORMER ENCLOSURE
TO BE DECOMMISSIONED AND
EXISTING SUPPLIES RELOCATED TO
NEW MAIN SITE SWITCHBOARD
EXISTING TRANSFORMER SSS/SSC
CURRENTLY BEING ASSESSED ON
SPARE CAPACITY

EXISTING PIT
PULL EXISTING SUBMANS (B OFF)
BACK TO THIS PIT AND STRAIGHT
JOINT ALL EXISTING SUBMANS
WITHIN PIT. ALL JOINTS TO BE
UNDERWATER RATED.

EXISTING UNDERGROUND SUBMANS
TO BE REDIRECTED TO NEW MSB-
CHILLER PLANT

ONCE EXISTING SUBMAN
IS LOCATED REDIRECT TO
NEW MSB-833

APPROXIMATE LOCATION OF NEW PIT

ROUTE OF EXISTING
UNDERGROUND SUBMAN
IS UNKNOWN
ENGAGE A CABLE LOCATOR
TO DETERMINE THE
EXACT LOCATION OF
EXISTING ROUTE CABLE

TX

NEW MSB
CHILLER PLANT

EP

EP

EP

MSB-33

DB-L11

BUILDING 32
SOCIAL SCIENCES C

BUILDING 34
SOCIAL SCIENCES A

RUN NEW SUBMAN TO
BACKFEED EXISTING
DISTRIBUTION BOARD
WITHIN CEILING SPACE OF
GROUND FLOOR.
COORDINATE FINAL LOCATION
ON SITE

EXISTING MAIN SWITCHBOARD LOCATED
ON GROUND FLOOR TO BE CONVERTED
TO A DISTRIBUTION BOARD. NEW MAIN
SWITCHBOARD INSTALLED EXTERNALLY
IN A WEATHERPROOF CLIPBOARD.
RUN A NEW SUBMAN FROM NEW MSB-33 TO
THIS EXISTING SWITCHBOARD (REFER TO
SCHEMATICS)

INFORMATION REFLECTED ON THIS DRAWING
REPRESENTS ELECTRICAL SERVICES DESIGN
DEVELOPED FOR D&C TENDER ADVISE ONLY, AND
SHOULD NOT BE REGARDED AS COMPLETE. THE D&C
CONTRACTOR SHOULD REFER TO ALL ASSOCIATED
ARCHITECTURAL AND OTHER DISCIPLINE DRAWINGS,
PROJECT BRIEFS AND CLIENT REQUIREMENTS AND
MAKE ADEQUATE ALLOWANCES FOR ALL NECESSARY
ELECTRICAL SERVICES WORKS TO MEET THESE
REQUIREMENTS, EQUIPMENT SCHEDULES AND
COMPLIANCE WITH THE NCC & APPROPRIATE
AUSTRALIAN STANDARDS

B	12.02.2026	MM	ISSUED FOR D&C TENDER	TP	SM
A	10.02.2026	CP	DRAFT FOR D&C TENDER	TP	SM
REV	DATE	BY	DESCRIPTION	CHK	APP

DESIGN DEVELOPMENT



900 Ann Street, Level 12, Fortitude Valley 4006
Tel: +61-7-3854-6200 Fax: +61-7-3854-6500
<http://www.wsp.com>

CLIENT: CQU

ARCHITECT: THOMSON ADSETT / PEDDLE THORP

PROJECT: CQU ROCKHAMPTON TAFE CONSOLIDATION

TITLE: ELECTRICAL SERVICES
BUILDING 33 - PROPOSED SITE PLAN

SCALE @ A1	1:100	CHECKED	TP	APPROVED	SM
PROJECT NUMBER	PS229518	DRAWN	CP	DATE	JAN 2026

DRAWING NO.	B33-EL-DR-300-A00-00-00	REV	B
-------------	-------------------------	-----	---

© WSP Australia Pty Ltd